

MACHINERY

JANUARY 17, 1958

ONE SHILLING & THREEPENCE



B.S.A. GOLDEN-ARROW TWIST DRILLS

B.S.A. TOOLS LIMITED · MONTGOMERY STREET · BIRMINGHAM 11 · ENGLAND



ASQUITH

**The small radial
for high output**

This Asquith NSR Radial Drilling Machine is drilling, countersinking and tapping gearcase extensions in the mass-production lines of a large motor factory. The Asquith Tapping Unit, which prevents tap breakage and thread stripping, is shown in operation. Write for details of this high-quality small Asquith Radial—a robust machine for quantity production and versatile for general engineering shops.

WILLIAM ASQUITH LTD.
HALIFAX · ENGLAND

Sales & Service for . . .

DRUMMOND-ASQUITH

. . . the British Isles

DRUMMOND-ASQUITH (SALES) LTD., KING EDWARD HOUSE, NEW ST., BIRMINGHAM

'Phone: Midland 3431 (7 lines) 'Grams: Maxishope, B'ham. Also at LONDON: Phone: Trafalgar 7224 (5 lines) and GLASGOW: 'Phone: Central 3411

A248



The best of machine tools give only mediocre results when cutters are poorly sharpened. Have you considered the advantages of the

CINCINNATI

Nº2 CUTTER GRINDER

for efficient grinding of facemills, slab-mills, end-mills, form-milling cutters, gear hobs, reamers, taps, die-sinking cutters, lathe tools?

Work height is fixed . . . the table rolls on balls between hardened ways . . . the grinding wheel spindle runs on anti-friction bearings contained in a cartridge . . . table ways and spindle unit replaceable at small expense . . . duplicate controls offer choice of four operating positions . . . a full range of attachments available for internal and external cylindrical, surface, and corner radius grinding.


Maintain production and profit with cutting tools correctly sharpened on a CINCINNATI No. 2 CUTTER GRINDER

Write for Catalogue now to
Charles Churchill and Co. Ltd.,—
London, Birmingham, Manchester,
Gateshead, Glasgow.



CINCINNATI MILLING MACHINES LTD.

BIRMINGHAM 24



CHARGE SHEET

*wasting time by
grinding cutters inefficiently*



Swing over table	14" dia.*
Length between tailstocks	30"
Face mills on workhead	18" dia.†
Longitudinal table movement	16"

* Using raising blocks

† Using face mill grinding attachment



You can now cut **all** automotive* spiral bevel and hypoid gears on one machine

You can rough and finish both gears and pinions on either the new No. 108 or No. 118 Hypoid Generator and four cutting methods are available to meet your production requirements.

Cutting prototypes and small lots

To cut small numbers of gears and pinions accurately and economically, you can use the **Unitool Method**. A single cutter roughs and finishes both members and covers a wide range of work with simple calculations.

For full production—three methods.

Cyclex Method:

Non-generated ring gears are both roughed and finished from the solid blank in one Cyclex operation. This is the fastest method available for producing good quality spiral bevel and hypoid gears.

Single Cycle Method:

Non-generated gears are first roughed out; then on the same machine one cutting revolution of the Single-Cycle cutter finishes each tooth. This method assures even distribution of cutter chip load and exact repetition of tooth shape with the finest surface finish. This method is four to five times faster than finishing by generation.

Standard Generating Method:

In separate roughing and finishing operations you can rough out and complete spiral bevel and hypoid gears. In using this method both the gear and pinion are generated and a wide range of work can be accommodated.

Such versatility alone can reduce the unit cost of your gear and pinion production.

Add to this the low initial investment of the machines themselves and you've found new economy in gear manufacturing.

Spiral bevel and hypoid gears up to 8½ in. in diameter and up to 4 D.P. are accommodated on the No. 108 and up to 15 in. diameter and 2 D.P. on the No. 118 Hypoid Generator.

GLEASON WORKS

Builders of Bevel Gear Machinery for over ninety years.

1000 University Avenue
Rochester 3, New York

* Other bevel gears with ratios of 2½ to 1 or higher, such as used in tractors, earth moving equipment, etc., can be cut by these same methods.

FULL DETAILS FROM
MACHINE TOOL DEPT.

BUCK & HICKMAN LTD

BRANCHES - ALPERTON - BIRMINGHAM - GLASGOW - LEEDS - MANCHESTER

When answering advertisements kindly mention **MACHINERY**.

Sole agents in the British Isles for the

GLEASON WORKS


BUILDERS OF BEVEL GEAR MACHINERY FOR OVER 90 YEARS

MACHINE TOOLS - OTTERSPOOL WAY - WATFORD BY-PASS - HERTS.
HEAD OFFICE - P.O. BOX 74 - WHITECHAPEL ROAD - LONDON E.1

SCHARMANN

PRECISION BORING AND MILLING MACHINE

FITTED WITH OPTICAL MEASURING DEVICE



MODEL FB 100

Model FB 100, having a 4in. diameter boring spindle, can be fitted with optical measuring equipment; precision engraved glass scales enable direct positional readings to be made to the accuracy of 0.0004in. or less.



CHARLES CHURCHILL & CO LIMITED
 COVENTRY ROAD SOUTH YARDLEY BIRMINGHAM 25
 BRANCHES LONDON GLASGOW NEWCASTLE MANCHESTER

FF

When answering advertisements kindly mention MACHINERY.

A black and white photograph of various industrial polishing machines. The machines are arranged on a tiled floor. In the foreground, a large machine with a vertical stand is labeled 'DUAL SPEED'. To its right, a smaller machine is labeled 'BENCH BACKSTAND'. In the background, another machine is labeled '6-HP'. A label 'BACKSTAND IDLER' is also visible. The brand name 'Morrisflex' is written in a large, stylized script at the top. Below the machines, the text 'THE WORLD'S FINEST POLISHING SHOP EQUIPMENT' is printed.

Morrisflex

BACKSTAND IDLER

DUAL SPEED

6-HP

BENCH BACKSTAND


THE WORLD'S FINEST POLISHING SHOP EQUIPMENT

B. O. MORRIS LTD.
MORRISFLEX WORKS, BRITON ROAD,
COVENTRY.

Telephone: COVENTRY 5081


Telegrams: MORRISFLEX • COVENTRY

When answering advertisements kindly mention MACHINERY.



serving industry and the community

As members of a community, we are dependant on one another. Our whole organisation is based on this simple fact. The renowned M & C Sales and Technical service is our contribution to the urgent day-to-day needs of British Industry.



Monks & Crane Ltd

BRITAIN'S FOREMOST DISTRIBUTORS



BIRMINGHAM • LONDON • MANCHESTER • LEEDS • NEWCASTLE-ON-TYNE • GLASGOW




**It's no good
looking at
me!...**

ASK "MR. MAC" ABOUT BRIGHT STEEL

It may be something of a dog's life humping steel about, but it is our business . . . We have over 5,000 tons of Bright Drawn and Hot Rolled Carbon and Alloy Steel Bars to all the main E.N. Specifications to meet your requirements.

Our premises are specially designed for the storage of steel and the latest handling equipment ensures that material is delivered in "Mint" condition. Yes, when it's a question of steel it pays to ask "Mr. Mac" first.



MACREADY'S FOR BRIGHT AND ALLOY STEEL

Macready's Metal Co. Ltd.

USASPEED CORNER, PENTONVILLE ROAD, LONDON, N.1
Telephone: TERminus 7060 (20 lines). Telegrams: Usaspeed, London, Telex. Telex No. 22788

When answering advertisements kindly mention MACHINERY.



BOX-FORD MODEL 'A' LATHE

£185

42" BED 22" CENTRES
MOTOR AND CABINET
BASE EXTRA

★ Write for fully
detailed leaflet TODAY!


This Boxford screwcutting lathe has a Timken bearing spindle, 16 speeds, quick change gearbox, fully automatic apron and double vee location for the saddle.

Boxford Lathes are ideal for teaching the finer points of centre lathe practice.

- Height of centres 4½ in.
- Number of speeds 16
- Between centres 22 in.
- Range of speeds 40-1,300 r.p.m.

DENFORDS ENGINEERING CO. LTD. HECKMONDWIKE YORKS.

When answering advertisements kindly mention MACHINERY.



Single reduction fan-cooled Worm Gear Unit. Type SUH.

Illustrated is one of a range of robust reduction gear units manufactured by us at Newbury. Capable of transmitting powers up to 120 h.p., this type of unit has proved to be ideal in iron and steel manufacture, mining, chemical engineering, paper making, textiles and wherever power transmission is employed.

We manufacture reduction gear units for so many applications it would be difficult to enumerate them in this advertisement, but we will be pleased to send you particulars on request.

We will gladly design and produce reduction gear units to your individual requirements — your enquiries will be welcomed at Newbury.



OPPERMAN GEARS LTD

NEWBURY

NEWBURY, BERKSHIRE




Post your enquiries to Newbury

Telephone: NEWBURY 1701 Telegrams: OPPIGEARS, NEWBURY


When answering advertisements kindly mention MACHINERY.



HYDRAULIC COPYING ATTACHMENT



... is fitted here on the 21" swing engine lathe




DESCRIPTIVE
LEAFLET
AVAILABLE
ON REQUEST

- THE ATTACHMENT IS FITTED TO STANDARD D.S.G. LATHES ALLOWING FRONT TOOLSLIDE TO BE USED ON NORMAL TURNING AND SCREWCUTTING OPERATIONS.
- ALL CONTROLS WITHIN EASY REACH OF OPERATOR
- MICROMETER LONGITUDINAL AND INFEED ADJUSTMENT TO COPYING TOOL. REDUCES "SET UP" TIME.
- TIE BAR CONNECTING COPY CENTRES SIMPLIFIES POSITIONING OF MASTER IN RELATION TO WORKPIECE

Dean Smith & Grace
KEIGHLEY LIMITED ENGLAND

We manufacture: 13-30 SWING ENGINE LATHES · SURFACING & BORING LATHES · TOOLROOM LATHES

"It Speaks for Itself"



Schuler

P

PEARSON & ANKE LTD

1-3 HALE GROVE GARDENS • MILL HILL • LONDON • N.W.7


Telephone: MILL HILL 3232 (P.B.X.)

Telex 23273

The most modern machine tools for Sheet Metal Working

When answering advertisements kindly mention MACHINERY.

*Two opposite faces ground
concentric simultaneously
to within 0.0005"*



DUPLEX SURFACE GRINDERS

- Ends of universal joint spiders ground at rates of up to 1,600 pairs of ends per hour, depending on size.
- Faces are held square to axis within 0.0005in.
- Concentricity with locating axis within 0.0005in.
- Uniformity maintained within 0.0015in.

These high production machines have been supplied to manufacturers both at home and abroad: the 30in. machine for large joints and the 20in. model for the smaller joints.

Check the jobs in your own works where ROWLAND DUPLEX SURFACE GRINDERS would slash production costs.

OUR TECHNICAL REPRESENTATIVES ARE READY, ABLE AND WILLING TO CO-OPERATE WITH YOU.

**F.E. ROWLAND
& CO. LTD.**

Telephone:
HEATON MOOR
3201-2-3
Telegram:
HEROIC, REDDISH

REDDISH • STOCKPORT • ENGLAND

SOLE EXPORT AGENTS:

DRUMMOND ASQUITH (SALES) LTD.

Halifax House, Strand, London, W.C.2. Tel: Trafalgar 7224

When answering advertisements kindly mention MACHINERY.

...tooled for the job!

CORONA

MODEL 21A

PRODUCTION DRILLING MACHINES ONE TO SIX COLUMNS WITH SINGLE OR MULTI-HEADS TOOLED READY FOR PRODUCTION

Illustrated is a typical production drilling machine with eight-spindle cam feed multi-head for drilling valve rockers. The hand-operated rotary table has a five-station indexing fixture, giving continuous production at exceptionally high rates.



For high production drilling

OPERATIONS:

- Station 1. Load two valve rockers.
- Station 2. Drill two holes.
- Station 3. Counterbore two holes.
- Station 4. Spotface two bores.
- Station 5. Tap two holes (automatic withdrawal at correct depth).

Machines can be supplied with up to six columns, each column with up to ten stations, completely tooled ready for production.





FREDK. POLLARD & CO. LTD
CORONA WORKS, LEICESTER, ENGLAND

TEL: LEICESTER 67354 (5 LINES)

London Office COASTAL CHAMBERS, 15, ELIZABETH ST., BUCKINGHAM PALACE RD., S.W.1.
TEL: SLOANE 8880

When answering advertisements kindly mention MACHINERY.

Can you produce parts like this in
6 minutes?



YES! WITH THE...

Harrison

COPYING LATHE

SAVE, EVEN ON SMALL BATCHES

The "first off" can be produced on this HARRISON Lathe and then copied the required number of times; even on small quantities considerable savings can be made.

PRICE


£700

Where small or large quantities are needed, we shall be pleased to submit estimated times if you will send us your drawings and specification of the material to be machined.

Send for fully detailed leaflet TODAY!

T. S. HARRISON & SONS LIMITED HECKMONDWIKE YORKS

When answering advertisements kindly mention MACHINERY.



'OSB'

HORIZONTAL SPINDLE SURFACE GRINDING MACHINE

This machine is designed for work requiring extremely accurate and highly finished flat surfaces. Besides being ideal for toolroom work and for die grinding, the Model 'OSB' can be used to advantage in the production line. High rates of output are obtainable. Built in three sizes with work tables 30in. by 10in., 42in. by 10in. and 60in. by 10in.

Easy and simple operation.

Built-in motor drive to grinding wheel spindle. Motorised automatic pump lubricating system and simple bearing assembly give a high precision spindle capable of heavy grinding cuts.

Variable hydraulic cross feed to wheel. Pre-set automatic cut-out and automatic reverse.

Fine and coarse vertical feed.

Massive cross slide underneath wheelhead column gives large area of support and maximum stability.

Hydraulic table traverse up to 90 feet per minute. Hand traverse interlocked with hydraulic control.

Permanently protected precision ground table slideways. Table traverse ways, wheelhead cross slideway and cross feed gears and bearings automatically lubricated from oil supply independent of hydraulic system.



THE CHURCHILL MACHINE TOOL CO. LTD. BROADHEATH, NR. MANCHESTER.

Telephone: Altrincham 3262.

Export Sales Organisation

Home Selling Agents:

Telegrams: Churchale, Manchester.

ASSOCIATED BRITISH MACHINE TOOL MAKERS LTD.
LONDON, BRANCHES AND AGENTS.

CHARLES CHURCHILL & CO. LTD., BIRMINGHAM AND BRANCHES.

PRECISION *plus* PRODUCTION

When answering advertisements kindly mention MACHINERY.

SOMUA

"Z"

MILLING MACHINES


Model 'Z1'
Milling 45-ton
Steel.
2in. dia. end
mill.
1½ in. per min.
feed.
1in. depth of
cut.




Model 'Z3'
Rough milling
diesel engine
cylinder heads.



Model 'Z3'
Machining
with
automatic
square cycling
control.



Model 'Z3'
Climb milling.



900 "Z"
**MILLING
MACHINES
INSTALLED
SINCE THEIR
INTRODUCTION
3 YEARS AGO**

	TABLE SIZE	TRAVEL		
		Long	Transverse	Vertical
Z1	47½ in. by 11½ in.	28 in.	9½ in.	15½ in.
Z3	63 in. by 14½ in.	39 in.	12½ in.	17½ in.



Sole agents

MACHINE TOOL SALES (LONDON) LIMITED

79 PORTLAND PLACE, LONDON, W.1

Telephone: LAngham 7703

Cables: TILASH, LONDON


When answering advertisements kindly mention MACHINERY.



Automatic correction of taper, ovality and errors of surface finish, elimination of loss on scrap components and consistent accuracy of finish—these are only a few of the advantages that Delapena equipment offers. Give us a ring and we'll tell you anything you want to know, and give you the benefit of some sound advice on honing applied to YOUR particular needs. It will pay you to ask us about honing—we are the experts!


Delapena

**When honing
is called for...
ring
Cheltenham 56341
for advice
on the equipment
you need**



Horizontal Honing Machines
for bores from .120" to .3125"
internal diameter and up
to 12" in length.

Vertical Honing Machines
for bores from .375" to 10"
internal diameter and up
to 38" in length.




**precision honing
machines & equipment**

DELAPENA & SON LIMITED

*Manufacturers of Induction Heating
Precision Honing Equipment*

ZONA WORKS • CHELTENHAM • ENGLAND

Telephone: CHELTENHAM 56341



**FOR
MAXIMUM
PRODUCTION**


Ward

COMBINATION TURRET LATHES

Reproduced by courtesy of R. H. Neal Ltd., Grantham, these photographs show a Ward No. 10 Combination Turret Lathe and the Neal crane link housing produced on it. This machine carries out 17 operations at exceptionally short floor-to-floor times.

Our complete range includes Capstan and Turret Lathes with capacities up to 35 in. swing over bed and 8½ in. diameter hole through spindle.

Please write for details.



H. W. WARD & CO., LTD.

SELLY OAK, BIRMINGHAM, 29.

TELEPHONE: SELLY OAK 1131

When answering advertisements kindly mention MACHINERY.

W.613

54.75" (52 min)

37.875" (32 min)

16.06" (9 min)

24.625" (19 min)

43.25" (73 min)

2.5" (15 min)

model J 6
Unitrace Profiling
Lathe

TYPICAL PROFILING
FLOOR TO FLOOR TIMES



LANG

PROFILING + TURNING BORING SURFACING + STANDARD SLIDING SURFACING & SCREWCUTTING LATHE ALL IN ONE MACHINE

LONDON OFFICE
ASSOCIATED BRITISH MACHINE
TOOL MAKERS LIMITED
17 GROSVENOR GARDENS SW1


JOHN LANG & SONS LTD.
JOHNSTONE RENFREWSHIRE SCOTLAND
Telephone: Johnstone 400 Telegrams: "Lang Johnstone"

21/M

GENUINE COVENTRY DIES

56 years of manufacturing "Know How"
ensures the quality, accuracy and long life
which defeats the copyists.

Coventry dies for $\frac{1}{8}$ " to $\frac{3}{4}$ " dieheads
are now supplied in transparent
boxes for complete protection,
compact storage and
visibility of die data.




AD381

ALFRED

HERBERT

LTD. COVENTRY



UKF

*At the centre of things
in spindle design*

BEARINGS AND BEARING HEADS

are specifically designed for use in Machine Tools, being of unique construction incorporating three rows of balls. The two rows of load-carrying balls provide a high load capacity both radial and thrust, and the third row together with a retaining ring forms a pre-loaded rolling spacer system eliminating all radial and axial clearance.


All these features are incorporated within the standard dimensions of a conventional single-row ball bearing.

'UKF' Bearings are available in several qualities of rotational accuracy and therefore form the basis for an accurate and vibration free spindle.

Details on request.

Made in Western Germany.

Sole Agents for the United Kingdom



HIGH PRECISION EQUIPMENT LTD

Designers & Manufacturers of Special Machine Tools

TELEPHONE BLETCHLEY 3403/4/5

BLETCHLEY, BUCKS



As one of the largest Stockists of Machinery and Plant we are in a position to submit quotations against all enquiries for new and used Machine Tools of all types, Accessories and Engineering Equipment.

Our Sole Agencies for the U.K. include the following Continental manufacturers:—

Pegard, Belgium	Horizontal Boring Machines, Production Milling Machines, Plate Radial Drills.
Demoor, Belgium	Heavy Duty Toolroom Centre Lathes and Pneumatic Forging Hammers.
Imperia, Belgium	Tool & Cutter, Carbide and Universal Grinding Machines.
Jaspar, Belgium	Horizontal, Universal, Vertical and Production Milling Machines.
Gambin, France	Bi-Rotary Head Universal Milling Machines.

On request, we shall be pleased to arrange for one of our Technical Representatives to call and discuss your requirements in detail.

A cordial invitation is extended to carry out inspection of our comprehensive stocks at:—

GEORGE COHEN

SONS AND COMPANY LIMITED

23/25, SUNBEAM ROAD,
LONDON, N.W.10.

'Phone: Elgar 7222/7

STANNINGLEY Nr. LEEDS

Pudsey 2241



When answering advertisements kindly mention MACHINERY.

THE **BROOKHIRST** TYPE 616 **PLUG-IN STARTER**



To remove or replace the interior unit of the **BROOKHIRST 616 STARTER** is a matter of seconds . . .

... the front-connected block contactor and overload relay are mounted on a moulded panel having plug-in isolating contacts secured to its underside. Withdrawal entails no more than releasing a retaining clip; no tools required; no trailing cables to disconnect. The 616 starter is ideal for applications demanding continuous running. Suitable for 3-phase squirrel cage motors up to 7½ H.P. 550 V. Full details in Leaflet 1800.

BROOKHIRST SWITCHGEAR LIMITED NORTHGATE WORKS CHESTER
A METAL INDUSTRIES GROUP COMPANY

CVS-52

When answering advertisements kindly mention MACHINERY.




HUNDREDS of **BERTHIEZ** **VERTICAL BORING & TURNING MILLS**

*... are in continuous operation
with*

AERO ENGINE WORKS
AIRCRAFT CONSTRUCTORS
BALL BEARING
MANUFACTURERS
DIE & TOOL MAKERS
ELECTRIC MOTOR BUILDERS
GENERAL & HYDRAULIC
ENGINEERING
COMPANIES
MARINE ENGINEERING
SHOPS
SHIPBUILDING INDUSTRIES

**EARLY DELIVERY FOR
45", 60" and 140"
SWING SIZES**




● **FOR HEAVY HIGH SPEED PRODUCTION**

Full range of types and sizes—from 45" to 316" swing. Full details from:—

SOAG MACHINE TOOLS LTD. **LONDON**
JUXON STREET • LAMBETH • S.E.11
PHONE: RELIANCE 7201 • GRAMS: SOTOOLSAG, LONDON, S.E.11

When answering advertisements kindly mention MACHINERY.



First in Fluid Power

Are you making the most of LOW-PRESSURE HYDRAULICS?

Wherever steady, controlled movement is required oil-hydraulics really come into their own.

Most hydraulic equipment, however, is designed and built primarily for high-pressure operation. When used for low-pressure applications it runs at a fraction of capacity and it would therefore be far cheaper to design and build hydraulic equipment specially for low-pressure operation. The new range of Baldwin low-pressure hydraulics meets this need.

Right from the drawing-board stage this equipment keeps one aim in view—RELIABILITY. Polished hard-chrome plated cylinder bores and piston rods; self-adjusting oil, and water resistant seals; rugged malleable cast iron and steel construction, completely rust and corrosion proof inside and out; built-in cushioning to absorb the shock of heavy loads moving at high speeds, and many other quality design features ensure absolute efficiency even under the most arduous conditions.

Unit construction enables Baldwin to offer 432 standard types of cylinder with 6 bore sizes and 8 standard mountings.


Ask any discriminating buyer, he will tell you that it *pays* to specify Baldwin low-pressure hydraulics.



BALDWIN FLUID POWER

BALDWIN INSTRUMENT COMPANY LIMITED

DARTFORD • KENT • DARTFORD 2948 *One of the Harper Group of Companies*



Write now for your copy of this new Fluid Power Brochure Y-503 it gives complete information on the entire range of Baldwin cylinders, valves and accessories, for pneumatic and hydraulic use.

837

When answering advertisements kindly mention MACHINERY.

ahead with lower machining times

Saving time . . . automatic sequence. The heads are slide-mounted horizontally, vertically, or at angles, on a wide range of standard columns and bases, which, with rotary tables and other equipment, ensure that your requirements are normally met ex stock.



Sentinel machine tools incorporating the Renault - France system electro-mechanical heads

Sentinel Unit Machines are built up from standard bases (with enclosed switchgear) and rotary tables, all of which have machined mating faces for assembly into varied combinations of units




When answering advertisements kindly mention **MACHINERY**.

**UNIVERSAL
HYDRAULIC**

**DUPLICATING
ATTACHMENT**

A COMPLETE PORTABLE
UNIT EASILY FITTED TO
ANY STANDARD MACHINE
TOOL



The features illustrated above are the subject
matter of one or more of several patents.

The **HYPROFILE**

The 'Hyprofile' Rotary Table Copy Milling
Equipment fitted to a standard Milling Machine and
producing Steel Dies from Plaster Masters fully
automatic in operation.

'Hyprofile' Equipment is available for a wide
variety of Automatic Milling work from three-
dimensional Masters or two-dimensional Profiling.

Descriptive Catalogue supplied on application

ARMYTAGE (TOOLS) LTD

FOUNDRY LANE, KNOTTINGLEY, YORKS, ENG
TELEPHONE 2743/4

When answering advertisements kindly mention MACHINERY.

Can be fitted to
Centre Lathes
Vertical Borers
Shaping Machines
Planing Machines
Vertical & Horizontal
Milling Machines
for profiling & three-
dimensional milling

**PROVED ON
PRODUCTION**

Announcing- **NEW COST CUTTING MACHINE**

AN ELECTRONIC ARMATURE UNDERCUTTING MACHINE by E.M.I.

This electronically controlled armature undercutting machine is completely automatic and simple to operate.

- * Automatic alignment of slot with cutter to within 0.002 in.
- * Operating time cycle 1 second per slot
- * Automatic counting
- * Quick release loading and unloading system

For armatures of the following sizes:

COMMUTATOR	Diameter 0.5-2 in. Length 0.25-2.25 in.
ROTOR	Maximum diameter 4 in. Maximum length 9 in. Maximum weight 25 lb. Number of slots 9-125

Other E.M.I. equipment designed for the needs of the Electric Motor manufacturer, include:
Automatic Armature Tester • Dynamic Balancing Machine • High Power Stroboscopes



If you would like further information, please telephone or write to:

E.M.I. ELECTRONICS LTD.



INSTRUMENT DIVISION • HAYES • MIDDLESEX • Telephone: SOUthall 2468 Exts. 1071 & 655

EE131

When answering advertisements kindly mention MACHINERY.



**For
MAXIMUM
Output**



Maximum output calls for screens that are tough enough to withstand long periods of gruelling service, and so reduce to a minimum delays for repair or replacement. In fact maximum output calls for

'HARCO' PERFORATED METAL AND WIREWORK SCREENS


Please ask for Catalogues Nos.
MN858 and MN926

Harvey

Supplied as flat or curved plates, or as complete screens to specification, in a wide range of gauge, mesh and pattern for every screening, sorting or sizing requirement.

G. A. HARVEY & CO. (LONDON) LTD
Woolwich Road, London, S.E.7. GREENWICH 3232 (22 lines)

When answering advertisements kindly mention MACHINERY.



It's the Spunchilled bore that counts

FOR HIGH CLASS BEARING BUSHES

Holfos Spuncast Bronze tubes possess the additional qualities which make all the difference between something ordinary and something good.

The absence of sand in association with the chilling of the bore by special process means that the inside of the tube is clean, true and sound.

The whole process of Holfos Spuncast production ensures accuracy, concentricity and a good surface finish on both the inside and outside diameters of Holfos tubes.

These qualities give you the very practical advantage of saving your costs by reduced machining allowances.



HL14

SPUNCAST Bronze


JOHN HOLROYD & CO., LTD. HOLFOS WORKS, ROCHDALE, LANCs.

We supply the machined bushes or the tubing only . . . PLEASE WRITE FOR BOOKLET S/56

When answering advertisements kindly mention MACHINERY.

Araldite tools shape the future

Tooling techniques with Araldite resins are being adopted more and more widely. Models, jigs, fixtures, patterns and metal-forming tools, including hammer forms, stretch blocks, rubber press tools, drop-hammer and draw dies, can all be made by simple methods with virtually no machining and a minimum of skilled manual work. Araldite tooling resins are used as gravity cast mineral-filled mixtures or with glass fibre mat or woven reinforcement, the latter providing strong, dimensionally stable, but lightweight surfaces and structures. Advantages of Araldite in tool-making include ease and speed of production, low production costs, light weight and ease of handling, negligible shrinkage on curing, accuracy of reproduction, dimensional stability, durability, resistance to cutting-oils and die lubricants, resistance to moisture and chemical attack, with consequent safety in storage.



Model of part of D.H. 110 tail fin for assembly jig checking, constructed in glass fibre reinforced Araldite resin and accurate to within a few thousandths of an inch. Photo by courtesy of The de Havilland Aircraft Co. Ltd.

The recommended techniques are simple and easily acquired. Full details and practical assistance are available upon request. May we send you a copy of our new publication on Araldite for tools, jigs and fixtures?

Araldite epoxy resins are used

- * for bonding metals, porcelain, glass, etc.
- * for casting high grade solid electrical insulation
- * for impregnating, potting or sealing electrical windings and components
- * for producing glass fibre laminates
- * for making patterns, models, jigs and tools
- * as fillers for sheet metal work
- * as protective coatings for metal, wood and ceramic surfaces

Araldite

Araldite is a registered trade name

epoxy resins

Aero Research Limited A Ciba Company · Duxford · Cambridge · Tel. Sawston 2121


A.P. 387

When answering advertisements kindly mention MACHINERY.

for power and precision . . .

the **CARDIFF** *Prefect*

9" (18½" SWING) SS & SC LATHE



3 1/16" SPINDLE BORE

18	Spindle Speeds	20-1,000 r.p.m.
80	Sliding Feeds	0.0023"-0.232"
80	Surfacing Feeds	0.0009"-0.096"
60	English Threads	½-30 T.P.I
24	Metric Threads	0.5-30mm

**ALL FEEDS AND THREADS OBTAINED
BY SINGLE LEVER SETTINGS**

- Gap bed 30", 48" and 80"
—alternatively chip flow
bed 48" and 80".
- Patented totally enclosed
feed box.
- Hardened and ground gears
in gearbox and headstock
—all meshing faces tooth
rounded for easy engage-
ment.
- Patented snap action con-
trols on apron—feeds can
be varied whilst cutting.
- 11" (22" swing) Crusader
model also available.

*Write NOW for
44 page
Machine Tool Catalogue*

B. ELLIOTT & CO. LTD.

VICTORIA WORKS, WILLESSEN, LONDON, N.W.10
Telephone: ELGar 4050 (10 lines) Telegrams: Elliottons, Marles, London
WORKS: WILLESSEN · CARDIFF · MAESTEG · LEISTON · IPSWICH



When answering advertisements kindly mention **MACHINERY**.

YORK SHIPLEY USE HARPER CASTINGS

—and Harper service too!



Not only do Harpers make the cylinder castings for York Shipley refrigeration plant, but they deliver them to the customer as a finished machined component.

The requirements of commercial and industrial refrigeration practice require the castings to be free from porosity or defect. The outer surface and ends are machined in *Harper's own machine shop* to a tolerance of 0.0005 in., and the bore is also honed to a tolerance of 0.0005 in., the degree of finish being 7 micro-inches.

Harper Service covers the supply of high - grade grey iron and Meehanite castings, machining, metal pressings, enamelling and other finishes, and sub-assembly of components.



HARPER CASTINGS




JOHN HARPER & CO. LTD. **JOHN HARPER (MEEHANITE) LTD.**
ALBION WORKS Phone: WILLENHALL 124 (5 lines) Grams: HARPERS, WILLENHALL **WILLENHALL**

LONDON OFFICE: SEAFORTH PLACE, 57, BUCKINGHAM GATE, LONDON S.W.1 Tel.: TATE GALLERY 0286
 MANCHESTER OFFICE: c/o B. J. Brown & Partners Ltd. 248/9 Royal Exchange, Manchester 2 H596

When answering advertisements kindly mention **MACHINERY**.

"**BRITISH ★ BUILT**
American "for better
BROACHING!



Model T-8-24
used at
VAUXHALL MOTORS
broaching
3 Rocker Arms
every 15 seconds

SEMI OR FULLY AUTOMATIC CYCLE
MODELS NOW AVAILABLE

★ Write today for full technical information

BUILT AND TOOLED BY



WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033


ROCKWELL
MACHINE TOOL CO. LTD.

ALSO AT BIRMINGHAM - TEL: SPRINGFIELD 1134/5 - STOCKPORT - TEL: STOCKPORT 5241 - GLASGOW - TEL: MERRYLEE 2822
ABV 6

When answering advertisements kindly mention MACHINERY.

360 COMPLETE COMPONENTS per minute

with the New British-Built
**U.S. MULTI-SLIDE
MACHINE**



Photographs by
kind permission of
Brayhead Limited



Brief Specifications

Machine Model	28	35
Length of Feed	8"	12½"
Maximum Width of Stock	1½"	3"
Maximum Thickness of Stock	1/16"	3/32"

The British built 'U.S.' Multi-Slide is an automatic machine designed for the economical production of stampings from coil stock. The various motions provided by the die head (ram), forming slides, vertical stripper mechanism and a range of auxiliary units afford the die designer practically unlimited possibilities for the development of tools to produce stampings at considerably lower piece part cost by eliminating secondary operations and handlings.

The flow of power is smooth as operations are so timed that the load is distributed throughout the cycle. This reduces wear and greatly extends the life of the machine and tools.

The two sizes of British built U.S. Multi-Slide machines (built for us by Alltools Ltd) are now available and can be supplied completely tooled for one or more components; the tool design being based on the vast experience accumulated by the U.S. Tool Co. Inc.

Send for illustrated leaflets, also ask to see film showing operation of the machine and examples of components produced. Our Sales Engineer will be pleased to call on request.


ROCKWELL
MACHINE TOOL CO. LTD.

For further particulars write or telephone TODAY


WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033

ALSO AT BIRMINGHAM—TEL: SPRINGFIELD 1134/5 • STOCKPORT—TEL: STOCKPORT 5241 • GLASGOW—TEL: MERRYLEE 2822

US4



type U3
Portable Universal
RADIAL DRILLING MACHINES



Our range of machines has recently been re-designed. Models are available with 4 ft., 5 ft., 6 ft., and 7 ft. spindle radius.

Illustration shows our 7 ft. model.

- FULLY ENCLOSED DRIVE
- INCREASED NUMBER OF SPEEDS & FEEDS
- BUILT-IN ELECTRICS

Full Particulars from—

KITCHEN & WADE LTD. HALIFAX · ENGLAND

Telegrams: KAW, HALIFAX

Telephone: HALIFAX 61173


When answering advertisements kindly mention **MACHINERY**.

Slipmaterial

Naxos

P.M.S. 400

RING GRINDER



The P.M.S. 400 gives considerable stock removal when used for roughing and superfine finish for surfacing. The grinding motor is dynamically balanced, the magnetic chuck motor is mounted on rubber, both vee-belt driven with especially rigid heavy base. The quick set-up of the workpiece on the magnetic chuck, the automatic hydraulic feed, ample grinding height and ease of control make the P.M.S. 400 ideal for many difficult grinding operations.

TECHNICAL DETAILS

Max. grinding diameter ... 20"
 Max. workpiece height ... 12"
 Table speed ... 34 - 120 r.p.m.
 Wheel spindle speed ... 2070 r.p.m.
 Slide speed ... 0 - 67" per min.
 Driving motor 8 H.P.

**PRACTICALLY
VIBRATIONLESS**

DISTRIBUTORS AND STOCKISTS FOR THE UNITED KINGDOM



MORTIMER ENGINEERING

PROPRIETORS: **COMPANY** S. GUITERMAN & CO. Ltd




Showroom & Sales: 204-206 ACTON LANE • HARLES DEN • N.W.10

Tel.: ELGAR 4833

When answering advertisements kindly mention **MACHINERY**.

Now

— Precision automatic
wire straightening and
cutting at over 300 ft. per minute



The  type RA

WIRE STRAIGHTENING & CUTTING-OFF MACHINE

—used by leading manufacturers of electrodes throughout the world.

Suitable for iron, steel, aluminium and brass wire, these machines fully meet the exacting requirements of the wire industry for output, accuracy and safety. Multi-disc clutch for rapid stopping and starting cuts setting up and loading time to a minimum. Any length can be cut and pickled wire can be handled with the same ease as unpickled wire.

SEVEN SIZES FOR WIRE FROM 0.012" TO 11/16" DIA.

WRITE FOR DETAILS

SOAG MACHINE TOOLS LTD

JUXON STREET • LAMBETH • LONDON • S.E.11
PHONE: RELIANCE 7201 • GRAMS: SOTOOLSAG, LONDON, S.E.11




When answering advertisements kindly mention MACHINERY.

For controlling horse-power
in many directions -
use



'DIAMOND H'



Packet Switches

Also suitable for Rectifiers,
Transformers, Battery Chargers,
Machine Tools and Switchboards.

Designs available in 5 amp. to 60 amp.
capacity at 250 or 440 volts, AC/DC
and AC only.

'Diamond H' Packet - type
Rotary Switches have been
developed to meet the demand
for a reliable multi-circuit
rotary reciprocating unit of
extremely robust construc-
tion. Why not therefore
incorporate these Switches
in equipment of your manu-
facture and be assured years
of trouble-free service under
the most arduous conditions.

'Diamond H' Switches are doing Trojan work in Industrial and Domestic fields all over the world

'DIAMOND H' SWITCHES LIMITED

GUNNERSBURY AVENUE, CHISWICK, LONDON, W.4

Telephone: Chiswick 6444 (5 lines) Grams and Cables: Diamonhart, Chisk, London

When answering advertisements kindly mention MACHINERY.

Solve DIE SINKING and PROFILE MILLING Labour Problems



-by installing


SWISS

RIGID

AUTOMATIC HYDROCOPYING MACHINES

Fully automatic copy milling in all three dimensions solves all die sinking and profile milling labour problems once and for all. 360° profiling without circular table and at constant feed. Copies vertical angles up to 90°. Light tracer pressure permits use of wood or plaster models. Reverse image attachment enables top and bottom dies of either hand to be made from the same master.

Standard table sizes up to 92.5" x 25.6"
One, two, four or six spindles



Send for
illustrated
brochure
to Sole U.K.
Distributors



DOWDING & DOLL LTD


346 KENSINGTON HIGH STREET, LONDON, W.14

Telephone: WESTERN 8077 (8 lines)

Telegrams: ACCURATOL HAMMER LONDON

When answering advertisements kindly mention **MACHINERY**.

All three splines are hobbled and a finished shaft is completed every 110 secs.



**-at
AUSTIN
MOTOR CO.
on the**

**LEES-BRADNER
6 SPINDLE ROTARY
GEAR HOBBER**

★ OUTSTANDING FEATURES

Automatic In-Out Mechanism

Automatic Closed Cycle

Automatic Hob Shifting with

Electric Counting Mechanism

LEES-BRADNER Rotary Hobbers

are available with 4, 6 and 8 spindles. All spindles are completely independent. A different set-up can be arranged on each spindle. Automatic loading and unloading can be supplied for most components.

SOLE U.K. DISTRIBUTORS

DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14

Telephone WESTERN 8077 (8 lines)


Telegrams: ACCURATOOL HAMMER LONDON



2,500 **TON**

HASENCLEVER

*Eccentric Type
Forging
Presses*



One of three Hasenclever forging presses, producing precision forged heavy bevel gears in a modern car factory. 100 to 6,000 tons.

By courtesy of



MOTOR CO., COLOGNE, GERMANY



PAUL GRANBY & CO. LTD.

39 VICTORIA STREET · WESTMINSTER · LONDON · S W 1

Telephone: ABBEY 5338 Telegrams: POWAFORGE, SOWEST, LONDON Cables: POWAFORGE, LONDON



2000 TON HASENCLEVER


FRICTION SCREW FORGING PRESS

*With push button
Programme Control*

Producing heavy pipe flanges 12" dia. bore x 19" o/d., from billets, in one heat and three blows.

The press is equipped with push button programme control to give blows of different strength automatically for one operating cycle.

Maximum nett energy rendered is approx. 195,000 ft./lb.



PAUL GRANBY & CO. LTD.

39 VICTORIA STREET · WESTMINSTER · LONDON · S W 1

Telephone: ABBEY 5338 Telegrams: POWAFORGE, SOWEST, LONDON Cables: POWAFORGE, LONDON



When answering advertisements kindly mention MACHINERY.


CONSOLIDATED
PNEUMATIC
MAKE OVER 480
DIFFERENT
MODELS OF
POWER TOOLS

This is the
C.P.-375
IMPACT WRENCH

For bolts up to $1\frac{1}{4}$ "

IT CUTS OPERATING TIME
FROM
MINUTES TO SECONDS

Consolidated Pneumatic



Whether running up $\frac{1}{2}$ in. nuts in thousands on light assembly or driving $1\frac{1}{2}$ in. nuts on heavy construction work, there's a C.P. pneumatic Impact Wrench to drastically reduce the time and costs of the job. The patented impact clutch eliminates torque reaction and the final torque obtained can be accurately controlled by pressure regulation. There's no twisting thrust or kickback when nuts are fully seated. To this speed and efficiency, then add versatility. C.P. Impact Wrenches are available in six sizes and can also be used for tapping, stud-setting, screw-driving, drilling or reaming. Ask for the Impact Wrench section of Catalogue No. 50.

CONSOLIDATED PNEUMATIC TOOL CO., LTD., 222 DAWES ROAD, LONDON S.W.6

When answering advertisements kindly mention **MACHINERY**.


Schneider

SURFACE & SLIDEWAY

***Immediate Delivery
FROM STOCK***

Grinding Machine

MODEL JOH3



**2 Universal Grinding Heads
with 120 mm. spindles
Table size 20" x 60"**

EXCLUSIVE DISTRIBUTORS IN THE UNITED KINGDOM

ELGAR

Machine Tool Company Limited

172/178 VICTORIA ROAD · ACTON · LONDON · W.3

Phone : ACORN 5555 (7 lines)

Grams : ELGATool, LONDON, W.3

When answering advertisements kindly mention MACHINERY.

Achievement Pfeifer

BUILT TO
-002 M.M.
TURNING
ACCURACY

★



PFEIFER

★

EX STOCK
9in. CENTRE by 40in.
OR 60in. BETWEEN. 12 SPEEDS
22-1,000 R.P.M. OR 22-2,200 R.P.M. 187
THREADS, WHITWORTH, METRIC & MODULE.
TAPER TURNING ATTACHMENT MOTORIZED 415/3/50 A.C.

**TOOL
ROOM OR PRODUCTION**

W. URQUHART
1023-7, GARRATT LANE, LONDON S.W.17. Phone: BALham 8551 (5 lines)



1809 + 1810
3226 + 3287
1557
1611 + 1625
1201 + 1202
1357 + 1359

MAUSER

W. URQUHART 1023-7, Garratt Lane,
LONDON, S.W.17
SOLE CONCESSIONAIRES. Phone: BALham 8551 (5 lines)

ACE TAPPING MACHINE



**THE NEW
IMPROVED ACE
TAPPING MACHINE**
Capacity 3 BA
—1in. In STEEL
Cast Iron $\frac{1}{2}$ in
Left and right
hand threads.
Bench or pedestal
Delivery ex-stock

★ SENSITIVE OPERATION AVOIDING TAP BREAKAGE

W. URQUHART 1023-7 Garratt Lane, London
S.W.17. Balham 8551 (5 lines)

HORIZONTAL AND VERTICAL SURFACE GRINDING MACHINE

This outstanding machine grinds both horizontally and vertically and is equally economical in large and small works. Horizontal Capacity 14in. by 4in. Vertical Capacity 14in. by 8in., Table Size 20in. by 6in.

TWO MACHINES FOR THE PRICE OF ONE



FULLY UNIVERSAL TOOL AND CUTTER GRINDER

WS1.£267 • De Luxe WS2.£385

7in. swing x 20in. centre

Compact — Movements in every possible direction. Grinds all types of cutters, reamers, etc. Included in standard equipment is a special Dividing Head-stock. Silk-like movements. Built to the same fine limits and finish of 'Frikla' products.

Prompt Delivery



SOLE CONCESSIONAIRES

W. URQUHART

1023-7, Garratt Lane, S.W.17
Tel.: BALham 8551 (5 lines).

★
WITH START, STOP
AND REVERSE,
ALSO
QUICK RETURN
CONTROLLED BY
ROB-REVERSING
GEAR MECHANISM.

★
FOR THE TOOL ROOM
OR
INSTRUMENT WORKS
PRODUCTION, ETC.

PRECISION
MODELS:—
MB.400 1 4' x 23' centres
MB.400 2 5 1/2' x 23' and 31' " "
Also STEPLESS DRIVE AND BENCH MODELS.

ROBLING.

MANUFACTURERS
OF LATHES FOR
OVER 50 YEARS.

SEE THE ! ! ! ! ROBLING AT OUR SHOWROOMS

Here is all the accuracy, superb finish, silk-like operation that over 50 years' manufacturing experience can give.

12 spindle speeds up to 1,920 r.p.m., amazing thread range Met., Whit., and Module. Collett Attachments.

STOCK DELIVERY

W. URQUHART


1023-7 Garratt Lane, S.W.17
BALham 8551 (5 lines)
Sole Concessionaires

When answering advertisements kindly mention **MACHINERY**.



TILGHMAN'S WHEELABRATOR STEEL SHOT

Is the Perfect Answer to



In the short time that Wheelabrator Steel Shot has been available in this country we have been able to satisfy users of this new abrasive that they can effect a saving of at least 33½ per cent on their overall shot blast costs.

For example, on one Wheelabrator installation, 800 hours continuity of production was recorded without any change of wheel components or wearing parts.

We guarantee to prove a substantial overall saving on existing shotblast costs to any operator of shotblast equipment, on an initial trial basis and if our claims are not fully justified, no charge will be made for the shot supplied.

Contact us today, we know it will be to your advantage.

**USERS have KIND WORDS, not CROSS WORDS
for WHEELABRATOR STEEL SHOT**

**SOLE LICENSEES IN GREAT BRITAIN
TILGHMAN'S LIMITED**

A member of the Staveley Coal & Iron Co. Ltd. Group

BROADHEATH • ALTRINCHAM • CHESHIRE

W.144

When answering advertisements kindly mention MACHINERY.

VICTORIA

Precision **ARBORS**

Nos. 40 and 50 Taper
1", $1\frac{1}{4}$ " and $1\frac{1}{2}$ " Dia.



- Will repay their cost many times over.
- Additional Arbors reduce setting time — ensure consistent production.
- Manufactured to standard dimensions—fit most makes of Milling Machines.
- Nickel Chrome molybdenum steel spindle.
- Running bushes and spacing collars hardened and ground —end faces lapped to within 0.0003" to ensure true alignment of cutters.
- Individually boxed in attractive cartons.

Sold through leading Engineering Tool Merchants

B. ELLIOTT & CO. LTD.

VICTORIA WORKS, WILLESDEN, LONDON, N.W.10.
Telephone: ELGAR 4050 (10 lines) Telegrams: Elliottona, Harles, London

WORKS: WILLESDEN • CARDIFF • MAESTEG • LEISTON • IPSWICH



When answering advertisements kindly mention **MACHINERY**.

A NUMBER OF " CRAVEN "


5' 0", 6' 0" and 7' 0"

VERTICAL BORING & TURNING MILLS

OF NEW DESIGN CAN NOW BE OFFERED

For Early Delivery

These machines have full push-button control for the main motor and electrically-operated feed motions, and have taper turning by gearing. A side-head can be fitted later if required




**CRAVEN BROTHERS
(MANCHESTER) LTD.**

VAUXHALL WORKS, REDDISH, STOCKPORT

When answering advertisements kindly mention MACHINERY.

What's new about Automation?



*Sykes shaving tools to suit this machine
can be supplied from stock*



The answer is—nothing. Automation began with the lever and wheel, and it has gone on inexorably ever since. Industry is currently approaching the ultimate object of *full* automation and, for the past thirty years, Sykes have been bringing that goal nearer.

Now, they introduce a further model to their extensive range of gear cutting and finishing machines—the VS.4A, a high speed, automatic, fine pitch gear shaver. For the accurate finishing of small spur and helical gears, it has no equal. A leaflet giving full technical details is available on request.

CAPACITY

Maximum gear diameter..... 4"

Maximum face width..... 1"

Coarsest pitch..... 16 D.P.

W. E. SYKES LIMITED

STAINES · MIDDLESEX · ENGLAND

Tel: STAINES 4281 (8lines) · Grams: 'SYKUTTER STAINES'

CANADA: Sykes Tool Corporation Ltd., Guelph Street, Highway No. 7, Georgetown, Ontario

AUSTRALIA: W. E. Sykes Ltd., Mascot, Sydney, N.S.W.

When answering advertisements kindly mention MACHINERY.

Spa



PLASTICS for MODERN ENGINEERING

INJECTION MOULDING

up to 32 ozs

in

CELLULOSE ACETATE
POLYTHENE DIAKON
NYLON POLYSTYRENE



Reduce costs improve performance!
Developments in plastics have led to an increased use of Nylon, P.V.C. and Polythene in engineering. Whether your firm manufactures electronic apparatus, motor cars or machine equipment—plastic components, bearings, brackets and gears may help to reduce costs and improve performance.

As technical thermoplastic moulders, we invite your enquiries: or if you post this advertisement with your letter heading one of our engineers will call.



SPA PLASTICS (Division of Spa Brushes Ltd.) CHESHAM • BUCKS • ENGLAND


Telephone: CHESHAM 81200 (P.B.X.)

Telegrams: FREEMBRUSH, CHESHAM

When answering advertisements kindly mention MACHINERY.

KAMENICEK

UNIVERSAL GRINDING MACHINES



Model 1.U.

Heavy duty precision built, for cylindrical (external and internal) as well as for taper and face grinding. Hydraulic table traverse; hydraulic infeed; swivelling wheel head; work-head with six spindle speeds swivels 90 degs. for taper and face grinding.

RANGE INCLUDES:

Models	1.U.	2.U.	5.U.	7.U.
Swing over table	10"	11.6"	15½"	26"
Distance between centres	15½"	20", 30", 40"	40", 59", 79"	98½", 118"
Grinding wheel size: dia. face hole	11.8" x 1" x 3"	13.8" x 1.57" x 5"	17.7" x 2" x 8"	20" x 3" x 8"



Sole Agents.

**Immediate Delivery from
our London Showrooms**
(Subject to prior sale)

The Selson Machine Tool Co. Ltd

41-45 MINERVA ROAD, NORTH ACTON, LONDON, N.W.10

Telephone: Elgar 4000 (10 lines) Telegrams: Selsomach, London, N.W.10

600
GROUP

56/SMT/167

When answering advertisements kindly mention **MACHINERY**.

STEEL... *in special shapes* **—plain or** *purl!*

... simple or complex, large or small,
singles or thousands, a few pounds or 18 cwt.,
... whatever the category into which a BAKERSTEEL
casting might fall, it will be treated with the same attention
to detail, subject to the same stringent chemical and
physical control and endowed with the same inherent
characteristics which are the product of long
experience coupled with modern techniques and
the very latest equipment. Ample facilities
are available for machining the heaviest
castings and the fitting shop can, if
required, undertake complete assembly.



Bakersteel

CASTINGS

- ★ ELECTRICALLY MELTED
- ★ LABORATORY CONTROLLED

W. A. BAKER & CO. LTD., WESTGATE WORKS, NEWPORT MON.

Telephone:
NEWPORT 64845


MAKERS OF PAPER MILL PLANT IN ASSOCIATION WITH BLACK CLAWSON INTERNATIONAL LTD.

When answering advertisements kindly mention MACHINERY.

MARBAIX

FOR UNUSUAL MACHINES

new



MÄGERLE

FULLY AUTOMATIC PRODUCTION PROFILE GRINDER

The most advanced machine of its type

ENTIRELY
AUTOMATIC
EXCEPT FOR
LOADING &
UNLOADING

THREE SIZES WITH WHEELS UP TO 4in. WIDE

MODEL FP 7A TABLE WORKING SURFACE 29½in. by 9 7/8in.


MODEL FP10A TABLE WORKING SURFACE 41½in. by 9 7/8in.

MODEL FP12A TABLE WORKING SURFACE 49½in. by 9 7/8in.

ALL MODELS HAVE 15½in. CLEARANCE UNDER WHEEL

WRITE FOR FULL DETAILS TO DEPT. M10

- WHEEL PERIPHERAL SPEED CONSTANT
- AUTOMATIC SIZING WITHIN 0.0002in.
- NEW PATENTED WAYS GIVING ABSOLUTE RIGIDITY & PRECISION
- AUTOMATIC ADJUSTMENT OF WHEEL SPEED COMPENSATES FOR WEAR



TYPICAL FIRTREE ROOT GROUND FROM
SOLID TO PITCH LIMITS OF 0.0002in.

GASTON E. MARBAIX LTD

DEVONSHIRE HOUSE VICARAGE CRESCENT,
BATTERSEA, LONDON, S.W. 11
PHONE BATTERSEA 8888 (8 lines)

When answering advertisements kindly mention MACHINERY.

ARE YOU A POWER PRESS USER?

The B.H.P. "AUTO-HAND" and "SYN-CROFEED" is definitely NOT a long run feeder. You can set up each day and still increase your present figures by 75 per cent.

Examine the facts—the feeder is really a semi-automatic unit—an operator is still needed, but it allows the operator to feed during the working stroke of the press and every hour the feeder arm completes well over 2,000 strokes. (Your operator works outside the danger area!)


OFFER — A free month's trial to allow you to prove what our Press Feeders can do for YOUR production in YOUR shop!

REMEMBER—The capital outlay is only a proportion of the cost of a new press—you use the same tools and operators to get more output from existing plant with perfect safety.

Manufacturers of:—

Coil Cradles.
Strip Straighteners.
Flexfeed.
Roll Feeds.
Dial Feeds.
Scrap Choppers.
Strip Lubricators.

SYN-CROFEED



**POWER
PRESS
FEEDER**

**FOR
SECOND
OP.
WORK**

Sole Manufacturers and Patentees:—

B.H.P. MACHINE TOOL CO.

**91 WATTVILLE ROAD,
BIRMINGHAM, 21**

'Phone : NORTHERN 6623, 6220

When answering advertisements kindly mention MACHINERY.



This comprehensive 120 page publication gives full technical data of the finest range of Standard Stock Fans. If you are concerned with fan equipment and applications, please write to our reference MY/101.

STURTEVANT ENGINEERING CO. LTD.
Southern House Cannon Street
London E.C.4.

When answering advertisements kindly mention MACHINERY.



**SPECIALISTS, STOCKISTS
AND DISTRIBUTORS**

of
Precision CARBON CHROME ALLOY STEEL
GROUND FLAT STOCK

INDISPENSABLE IN THE MANUFACTURE OF
JIGS, TEMPLATES, GAUGES, PRESS TOOLS, ETC.,
OIL HARDENING, NON-DISTORTING STEEL IN
STANDARD 18in. LENGTHS.
EACH PIECE SEPARATELY PACKED WITH FULL
HEAT TREATMENT INSTRUCTIONS.
STANDARD 18in. LENGTHS, ALSO NON-
STANDARD SIZES 12in., 24in. & 36in. LENGTHS.
WIDTHS FROM $\frac{1}{2}$ in. to 12in. THICKNESSES
FROM $\frac{1}{16}$ in. to 2in.

*Guaranteed
to ± 0.001 in
thickness*



**30,000 LENGTHS
ALWAYS IN STOCK**

WRITE FOR SPECIFICATIONS AND PRICES


MAIN STOCKHOLDERS AND DISTRIBUTORS

T. NORTON & CO. LTD.

CARVER STREET BIRMINGHAM 1

Telephone: CENTRAL 4325 (5 lines)

When answering advertisements kindly mention MACHINERY.




*This Butler Hydraulic Planer is a notable example of British machine tool design and construction. It is fitted with **VICKERS-DETROIT** oil hydraulics.*

fluid assets

Throughout industry the demand is increasingly for machines that can repeat a cycle of operations with minimum manual interference and control. It is in this field that the flexibility and reliability of

VICKERS-DETROIT oil hydraulics are especially evident.

For literature on our oil hydraulic products please write for publication No. 1/10.




by

STEIN ATKINSON VICKERS HYDRAULICS LIMITED

S.A.V. HYDRAULICS

60 Buckingham Palace Road London SW1




When answering advertisements kindly mention MACHINERY.

what are you waiting for?

You want Precision Hobs? We can supply them! Spur, helical, worm wheel, spline or serration, made precisely to your requirements,

Our standard Spur and Helical range is designed to cover all normal requirements and to give you speedy deliveries, in many cases actually from stock.

If you have not been using David Brown Precision Hobs, write now for Leaflet E313.9 and get yourself acquainted with our quality and our service.




THE
DAVID BROWN
CORPORATION (SALES) LIMITED
TOOL DIVISION
PARK WORKS HUDDERSFIELD



When answering advertisements kindly mention MACHINERY.

**compact
heavy duty
control
units**


Igranic presents Industry's finest line of oil-tight heavy duty control units—
in compactness, in flexibility,
in durability and in appearance.




range of units available

This modern range of space-saving control units includes pushbuttons, indicating lights, selector switches, and roto-pushbuttons, with a flexibility in circuit arrangements almost unlimited. Full particulars upon application to Publicity Department, Bedford.


SELECTOR SWITCHES
Operated by knob or key,
for safety locking.



INDICATING LIGHTS
Normal and PresTest with
a choice of clear or coloured
lenses.



PUSHBUTTONS
Flush, extended or mush-
room heads and wide choice
of colours.



IGRANIC
heavy duty oil-tight control units

IGRANIC ELECTRIC CO LTD
HEAD OFFICE AND WORKS BEDFORD

LONDON & EXPORT OFFICE VICTORIA STATION HOUSE 191 VICTORIA STREET SW1
A METAL INDUSTRIES GROUP COMPANY



DISTRICT OFFICES: BIRMINGHAM BRISTOL CARDIFF EAST ANGLIA GLASGOW LEEDS
MANCHESTER NEWCASTLE SHEFFIELD





Never satisfied! Always improving! A steady progress towards perfection—burred the Managing Director in his most self-satisfied voice.

Take Pneumatic Screwdrivers. Efficient, you say—but perhaps a trifle noisy for the assembly line. Sir, you are living in the past. This Little Horse here ("this 'ere Little Horse, if you please" muttered the Little Horse in question) operates a screwdriver. Note that we have fitted him with a kind of gag or muffler, thus reducing the operating noise level by more than 50%. The principle is really very simple—as I will now demonstrate. I place this muffler over my mouth... so... I will now ask any member of the audience to wrap the ends—thank you, sir,—round behind my ears... and N'mm M'mm Er'rm Ah'rmm Hurh'mm mm-m-mm...!

(The audience agreed that the noise level had indeed dropped by well over 50% and the Managing Director was carried out, black in the face, amid loud cheers).



These Screwdrivers are now fitted with an improved plastic grip; they are available in four different speeds:— 2,500, 1,000, 550 and 310 r.p.m. For further details write for special leaflet.



THE NEW **DESOUTTER** silent screwdriver

DESOUTTER BROS. LIMITED, THE HYDE, LONDON, N.W.9. TEL: COLINDALE 6346 (5 LINES). GRAMS: DESPNUCO, HYDE, LONDON


When answering advertisements kindly mention MACHINERY.



Prolite FUTUR MILLS

FACE MILLING CUTTERS
incorporating these
5 unique features

- All Rake and Clearance angles incorporated in the cutter body
- Sixteen cutting faces are available before regrinding is necessary
- No time lost for blade regrinding
- Steel can be milled at high feed rates
- All inserts can be replaced without disturbing the tool setting



Home Sales: **PROTOLITE LTD.** (a subsidiary company of Murex Ltd., Rainham, Essex), **CENTRAL HOUSE, UPPER WOBURN PLACE, LONDON, W.C.1.**
EUSon 8265. Telex 23720. Telegrams: Prolite, London Telex.
Export Sales: **MUREX LTD.** (Powder Metallurgy Division)
RAINHAM, ESSEX. Telex 28632. Telegrams: Murex, Rainham-Dagenham Telex.

ARCHER
the **CENTRE**




for
your
Production
TARGET

"ARCHER" Centres are specifically designed to meet the strenuous conditions of modern production requirements. They are renowned for their consistent high quality and performance in service.


"ARCHER" REVOLVING CENTRES

Constructed to stand up to higher speeds and heavier thrust loads which modern machines demand.

4 STANDARD models are available. Ask for List No. 85




"ARCHER" SUPER CENTRES



A permanent Hardened and Ground Socket with RENEWABLE HIGH SPEED STEEL INSERT. Standard inter-changeable inserts enable centre to be quickly replaced at low cost.

"ARCHER" STANDARD SOLID CENTRES

Precision ground to give perfect concentricity. Tapers to standard gauges. Made in High Grade CARBON ALLOY STEEL, or HIGH SPEED STEEL BUTT WELDED. Ask for List No. 50B



FRANK GUYLEE & SON LTD.

ARCHER TOOL WORKS · MILLHOUSES · SHEFFIELD D



Telegram: "Cayles, Sheffield". Telephone: 50651-2

MANUFACTURERS OF
bolts, nuts and set screws
in all grades of material.

STOCKISTS OF
tools for engineers
and woodworkers.

C. Lindley & Co. Ltd.

MAIN STOCKISTS
AND DISTRIBUTORS FOR
Wolf, Bridges, Black & Decker
and Selecta Equipment.

C. Lindley & Co. Ltd.,
Englefield Road,
London, N.1.
Phone: Clissold 0643 (5 lines)
Grams: Beauvoir, Nordo, London.

When answering advertisements kindly mention **MACHINERY**.

* THE VICE BUILT AS A MACHINE TOOL . . .

Expensive machine tools deserve a machine vice of equal precision—a role befitting the precision built DOWN-GRIP vice. Laborious setting-up time is substantially reduced. The quick action jaw slides right up to the job—a slight turn of the screw then gives instant and positive downward grip!

This vice has its own hardened and ground steel table, parallel to the base, providing a permanent foundation for precision work.



By simply pressing the thumb-triggers the movable jaw is entirely free to slide, thereby eliminating time wasted adjusting the normal machine vice.

Hardened steel jaws are fitted as standard but soft jaws are available.

Vice swivels on base through 360°.

Reversible jaw plates for irregular shapes.

Standard range includes 4", 6" and 8" jaw widths.



* THE DORMER

DOWN GRIP

A NEW AND FASTER MACHINE VICE



.. definitely holds
the job down!

THE SHEFFIELD TWIST DRILL AND STEEL CO. LTD.
SHEFFIELD **ENGLAND**

DORMER MACHINE VICES ARE AVAILABLE FROM YOUR USUAL ENGINEERS' MERCHANTS

close-up...

on the
Model 540
surface
grinder



JONES-SHIPMAN
Model 540 Surface
Grinders are installed
at TURNER BROS.
(BIRMINGHAM) LTD.,

who are the world's
largest contract press tool,
jig and fixture manu-
facturers. The machine is
shown grinding punches for
Insulators produced by
Sangamo-Weston, Ltd., Enfield,
Middx.


JONES - SHIPMAN

A. A. JONES & SHIPMAN LTD., Narborough Road South, Leicester
Telephone: 823222 (8 lines) Telegrams: 'Chuck' Leicester
London Office: Murray House, 5 Vaddon Street, Buckingham
Gate, S.W.1. Telephone: Abbey 5938 9

When answering advertisements kindly mention MACHINERY.

RIGHT OUT AHEAD

- IN PRODUCTION CAPACITY & PRECISION



This model R 16, built by the world's largest and oldest producers of Swiss-type automatics, is the last word in performance, precision and production capacity.

Stock capacity $\frac{5}{8}$ in. dia., with a maximum turning length of $3\frac{1}{4}$ in. or 6 in., according to type of cam. 28 spindle speeds 485 to 5,450 r.p.m.

Full details and production data gladly sent on request.

The latest

TORNOS

SLIDING HEAD AUTOMATIC

MODEL R.16

PHONE: COVENTRY 40606

TORNOS SALES COMPANY
BROADGATE HOUSE COVENTRY

When answering advertisements kindly mention MACHINERY.

Reduce face milling times on LIGHT ALLOY COMPONENTS by as much as 80%

Are you using an expensive and complicated machine tool for face milling Non-ferrous Metals?

If so, you are taking five to six times longer than is necessary!

Why not investigate how the latest Wadkin Articulated Arm Routing Machine L.C. can make drastic reductions in your production times.


Let us give you a demonstration, preferably on your own components.

Details of the Wadkin Articulated Arm Router L.C. are given in Leaflet 831. May we send you a copy?


Wadkin

Telephone : Leicester 67114

Telephone : MAYfair 7048



High cutting speeds of 18,000 r.p.m. and the low tooth loading of the cutter make high speed routing, particularly suitable for face milling components such as this engine sump.



Wadkin Ltd., Green Lane Works, Leicester. London Office : Brookfield House, 62 Brook St., W.1

When answering advertisements kindly mention MACHINERY.



LOW-SPEED MOTOR UNITS

Type RGD with : —

- CO-AXIAL DRIVE
- RATIOS UP TO 25:1
- POWER OUTPUTS UP TO 25 h.p.
 - A.C. or D.C.

The motor component may be a squirrel-cage (including British Standard Dimension), slip-ring, or D.C. machine; a variety of enclosures are available to suit the application.

Neither gears nor motor is disturbed by removal of the top-half casing.




Helical teeth provide smooth running at an efficiency of not less than 98%.

All pinions, wheels, and bearings readily accessible for inspection.

Low specific loading of gears and bearings ensures long life.

Visible oil level for ease of maintenance.

Robust and generous casing has ample thermal capacity.




BRITISH THOMSON-HOUSTON

THE BRITISH THOMSON-HOUSTON COMPANY LIMITED · RUGBY · ENGLAND
an A.E.I. Company

AS196

When answering advertisements kindly mention MACHINERY.



THE MEASURE OF ACCURACY

Solex 10M and 4M comparator heads

Simple to use, the Solex 10M and 4M Gauge Heads provide an unskilled operator with a ready means of measuring the actual dimension of a part, a characteristic which gives absolute confidence in the accuracy of your production.

The 10M and the 4M Comparator Heads are of universal application. They can be used in workshop

comparators, for continuous strip measurements for Cee and Vee Gauges or fitted into your own jig for specific requirements.

Like all Solex air operated Gauges, they make an important contribution to the quality and rate of production.

Magnification range from 4000/1 to 23000/1.

SOLEX HAVE THE MEASURE OF THINGS

SOLEX
(GAUGES) LTD.

Send for fully illustrated details

72 CHISWICK HIGH ROAD · LONDON · W4 · CHISWICK 4815

When answering advertisements kindly mention MACHINERY.

*Q. What does it cost to drive
a 10 kW Generator from
a 14/22 h.p. Armstrong Siddeley
Air-Cooled Diesel?*

*A. \$0.01385 (1.175^d) per kW/hour**

ACTUAL COSTS

FOR 2606½ HOURS RUNNING WERE:

Diesel fuel (less tax: 1178 gals.)	\$259.27
Lubricating oil, filters etc.	\$81.71
Spare parts (fuel filter assembly)	\$20.35
Fuel consumption (Gals/Hour)	0.441


* Figure supplied by
Gt. Raymond Paper Co.
of Lac Brûlé, Canada.

YEARS OF KNOW-HOW: The diesel engines are manufactured with the same precision as the Hawker Siddeley Group's world-famous aero engines.

MATERIAL-CHECKED: Armstrong Siddeley experts regularly visit suppliers of materials and components to check on their quality controls.

PRODUCTION-CHECKED: Engines are taken off the production line at random and given a fifty-hour running test.

THERE IS NO MORE RELIABLE DIESEL ENGINE.
Three models: 6-11 h.p., 14-22 h.p., 20-33 h.p.
Write now for brochures.




Armstrong Siddeley AIR COOLED Diesels

ARMSTRONG SIDDELEY (BROCKWORTH) LTD • HUCCLECOTE • GLOUCESTER

MEMBER OF THE HAWKER SIDDELEY GROUP

THEY GO TO **TOWN**

- at MARSHALL, SONS & CO., LTD
GAINSBOROUGH



"Town" Radial Drilling Machines are renowned for rigid, simple design, conveniently placed controls, and maintaining maximum rates of production on the widest range of components—a few of the reasons why they are called upon to give service all over the world. This A.E.I. All-Electric Drilling machine, shown at work at Marshall, Sons & Co., Ltd., has centralised control, drills 2½ in. from solid in steel.

FREDK TOWN & SONS LTD. HALIFAX, YORKS
ESTABLISHED 1903

T13

When answering advertisements kindly mention MACHINERY.



Somebody's running his automatics *Flat Out!*

- so can you with

**ALMINAL W.151
FREE-MACHINING BAR**

The **ALUMINIUM ALLOY**
with all these advantages

1. Special chipping characteristics eliminate swarf jamming.
2. Automatics can operate at maximum speed and feed.
3. Longer tool life—normal angles on tool tips can be used.
4. Lower labour costs—one man can watch several machines.
5. Output dramatically increased.

Write TODAY

for full Technical Details

Southern Forge LTD

MEADFIELD ROAD · LANGLEY · BUCKS

—Telephone: Langley 301—

**ALUMINIUM AND
ALUMINIUM-ALLOY EXTRUSIONS
TUBES AND FORGINGS**

When answering advertisements kindly mention MACHINERY.

CEJ

CHASER DIES


CEJ PRODUCTS

Ground Thread Taps
Screw Plug Gauges
Screw Ring Gauges
Circular Chasers and Holders
Round Dies
Thread Milling Hobs
Thread Rolling Dies
Plain Plug Gauges
Mikrokatators
Micro Snap Gauges
Surface Finish Indicators
Micrometers
Bore Gauges
Deltameters
(Automatic Sizers)
Drill Chucks
Dynamometers
Extensometers
Plain and Screw Snap Gauges
Plain Ring Gauges
Gronkvist Drill Chucks
Dial Gauges
Tapping Attachments
Multiple Interference Microscopes
Vernier Height Gauges

Everything that care and skill can contribute go to ensuring that CEJ Dies will be correct in every detail and fully meet your requirements.

They are manufactured from specially selected H.S.S. correctly heat treated; produced by the most exacting methods, rigidly inspected in all thread elements and actually tested before despatch.

CEJ Chaser Dies can be used in CEJ 430 Die Heads and Coventry and similar type Die Heads.



CEJ JOHANSSON LTD.

PRECISION TOOLS AND INSTRUMENTS

SOUTHFIELDS ROAD, DUNSTABLE, BEDS. TEL: DUNSTABLE 422-3-4

DHB/5064

A.I.D. AND A.P.I.
APPROVED

When answering advertisements kindly mention MACHINERY.



In any language TORRINGTON NEEDLE BEARING means high capacity!

From Kalamazoo to Calcutta, the Torrington Needle Bearing is synonymous with *high capacity in minimum space at low cost.*

The unique capabilities of the Needle Bearing have won it world-wide acceptance, established it as "standard equipment" in products made all over the globe.

A full complement of free-running rollers retained by a thin hardened shell, which serves as the outer race, affords more lines of contact, and thus greater radial load capacity than other bearings of the same size.

As important as the Needle Bearing itself is the knowledge and experience our Bearings Division places at your disposal. With thousands of successful applications behind them, Torrington engineers are eminently qualified to show you the benefits of Needle Bearings in your products.

TORRINGTON BEARINGS

The Torrington Company Ltd. Bearings Division: Torrington Avenue, Coventry.
London & Export Office: 7-10 Eldon Street, EC2. Glasgow Office: 14 Moir Street, C1

Torrington Needle Bearings give you these benefits

- * compactness and light weight
- * unequalled radial load capacity
- * low starting and running friction
- * low unit cost
- * run on hardened shafts
- * allow larger and stiffer shafts



MADE AND STOCKED AT OUR
ENGLISH FACTORY

Type U-OA Universal Milling Machine

WITH TABLE SWIVELLING IN THREE PLANES

CHRISTEN

This modern, well-designed machine is especially suitable for Toolmaking and for high precision production work




Table Size 26½ in. by 9 in.


DELIVERY FROM STOCK

Sole Agents in the U.K.


ACBARS LTD

57a Holborn Viaduct, London E.C.1


Telephone: CENTral 2287 B 9, 6811/2




Vertical Milling Head & Universal circular table




Universal Dividing Head on auxiliary swivelling platen



Slotting Head & Circular Table





Infinitely variable speed range from 60 to 2,500 r.p.m. Infinitely variable feed from separate fitted motor






Patented single lever switch for easy control of milling spindle rapid traverse & power feed

A SWISS PRECISION MACHINE




SPECIALS

As "specialists in specials" our everyday concern is the production of special cutters and form tools manufactured from the finest qualities of High Speed Steel and, in certain cases, tipped with Betaloy Tungsten Carbide. Over forty years' experience ensures the quality, reliability and precision of all B.T.G. products. Whenever it's a question of "specials" you cannot do better than contact B.T.G.



BIRMINGHAM TOOL & GAUGE CO. LTD., BIRMINGHAM 19 · Tel: Northern 3344
London Office: 26 HOLBORN VIADUCT, LONDON E.C.1. · Telephone: Fleet Street 6564

Boardman



Model BPV 300/1000

VERTICAL SPINDLE SURFACE GRINDER

*Costs
less
than
you
think*



Newman

A machine specially built for the rough and precision grinding of continuous and interrupted plane surfaces. For hollow grinding the head can be tilted out of its horizontal position.

During grinding the entire working width of the table or the surface of the electromagnetic chuck can be covered simultaneously by a segmental grinding wheel.

The BPV Surface Grinder, while costing less than many similar machines, is designed to give long and reliable service wherever there is a need for top quality accurate grinding.

	BPV300		BPV700	
	1000	1500	2000	3000
Working surface of table	*(inches) 11½ x 39½	*(inches) 11½ x 59	(inches) 23½ x 78½	*(inches) 23½ x 118
Maximum width ground	11½	11½	23½	23½
Longitudinal travel of table	54½	80½	95	154
Main spindle drive, h.p.	20	20	30	30

*** Delivery — IMMEDIATE**

(subject to prior sale).

Sole selling agents in U.K.


NEWMAN INDUSTRIES LIMITED

Machine Tool Division

YATE, BRISTOL, ENGLAND

Telephone : Chipping Sodbury 3311 Telegrams : "Dynamo Yate"

Our SMALLEST miller still a BIG machine



AS
MODEL O

Built up to a standard-not down to a price

Nothing small about our Model 'O' range of horizontal milling machines. However hard the going, short of obvious overloading, they can take it. That's because they are solidly, generously, heavily* built for a lifetime of honest service with the absolute minimum of

maintenance. 20 different variations of an extremely rigid central theme; hand or automatic feeds; large range of spindle speeds right down to 150 r.p.m. Angular contact ball-bearing spindle and ball-bearing arbor bracket allow spindle speeds up to 4,000 r.p.m.

* Weight of model illustrated 9 cwt. (1,008 lbs.). Table sizes $18\frac{1}{2}" \times 5"$, $17\frac{1}{2}" \times 5"$ and $12" \times 4\frac{1}{2}"$

Write for fully illustrated leaflet

ADCOCK & SHIPLEY LTD

P.O. Box 22, ASH STREET, LEICESTER


Telephone : Leicester 24154-5-6

Telegrams and Cables : Adcock Leicester

*Many Types for
EARLY DELIVERY*

How hollow bored bars can cut your costs

All over industry people are finding it's cheaper to use Keetona Hollow Bored Bars for applications covering a very wide field. Keetons specialise in supplying Hollow Bored Bars: they've developed the process during 25 hard-thinking, hard-working years. Where a job can't be done by any other method, because the quantities needed are too small, Keetons will do it cheerfully by deep hole drilling at a much lower cost than you'd expect. For keen prices and quick delivery Keetona Hollow Bored Bars have the rest licked hollow!



*Write for our new illustrated brochure
telling you all about Keetona Hollow Bored Bars to*

KEETON SONS & CO. LTD.

KEETONA WORKS, GREENLAND ROAD, SHEFFIELD, 9. TEL: SHEFFIELD 42961/4.




A MEMBER OF THE FIRTH CLEVELAND GROUP



CRC4KH

When answering advertisements kindly mention MACHINERY.




Redifon IH.45

The world's

AIR COOLED

most powerful R.F. INDUCTION HEATER

This new 125 kW heater has been specially designed to give reliable and continuous performance under the most arduous industrial conditions. Its efficiency is unimpaired by widely varying electrical loads or poorly regulated mains supply. And the IH.45 is air cooled . . . an economy feature no other R.F. generator of this output has ever had. Typical amongst many possible applications are one shot hardening of gears . . . hardening crankshafts, sprockets and motor car cylinder walls . . . rapid melting of Nimonic alloys . . . hardening teeth of main transmission gears for lorries . . . and tube welding. The Redifon IH.45 speeds production by reducing processing time to an absolute minimum, and is so simple to operate that it can be used by unskilled personnel.



Heating a spur wheel for a tractor gearbox before hardening in the special Redifon quench bath.

Industrial Electronics Division



REDIFON LIMITED, BROOMHILL ROAD, LONDON, S.W.18

A Manufacturing Company in the Rediffusion Group

Telephone: VANDyke 7281


When answering advertisements kindly mention MACHINERY.

The logical advance in Retaining



OLD WAY

To provide a shoulder for the tensioning spring on this filler cup entailed an extra long, threaded shaft, a nut, a hole drilled to take a cotter pin and an altogether tedious assembly.



THE SALTER WAY

The spring is quickly positioned on a shorter, **PLAIN SHAFT** by a **Grip Ring** which is snapped into position for secure, frictional grip. No groove required.

save material—reduce assembly time—**cut costs**

When it's a question of assembling components in any engineering field, Salter Retainers are the answer. They replace nuts and bolts, screws, cotter pins, and eliminate expensive threading and

machining operations. A large standard range is at your immediate disposal, and we should welcome the opportunity to assist in developing special retainers to solve your problems.

Send for the Salter Retainer catalogue — no designer is complete without it.

NEATER — MORE POSITIVE — PERMANENT RETAINING

SALTER



Circlips



Fasteners



Retainers




Fixes

Geo. Salter & Co. Ltd., West Bromwich.

Spring Specialists since 1760

H-V.444

When answering advertisements kindly mention **MACHINERY**.



Special alloy steels
for
machine tools.

by **FIRTH BROWN**

HOS. FIRTH & JOHN BROWN LIMITED • SHEFFIELD

When answering advertisements kindly mention MACHINERY.

You're on a good wicket
with





Eclipse hacksaw blades and other tools are made by James Neill & Co. (Sheffield) Ltd. and are obtainable from all tool distributors

UH 23

When answering advertisements kindly mention **MACHINERY**.

THE VICE

with all the virtues



V SLIDES ADJUSTABLE FOR WEAR. LONG BEARING SURFACES. IMPOSSIBLE FOR THE JAW TO LIFT AND TILT THE JOB.

TOTALLY ENCLOSED HARDENED SQUARE THREAD SCREW WHICH CANNOT BECOME SEIZED OR BRUISED.

SLIDING JAW MACHINED OVER ITS WHOLE SURFACE FOR THE USE OF THE SCRIBING BLOCK.

GROUND TOOL STEEL JAWS AND PHOSPHOR BRONZE NUT.

ACCURATELY MACHINE DIVIDED SWIVEL BASES INDEXED FULLY THROUGH 360°.

NO TRAPS FOR SWarf.

ABWOOD Machine Vices are available in the following types:
PLAIN, SWIVEL TYPE (illustrated) SHAPER, UNIVERSAL,
UNIVERSAL COMPOUND ANGLE TABLE and DUAMATIC.

FOR THE TOOLROOM & PRODUCTION

When applying for details please quote M/561






If it's an ABWOOD - it is good

ABWOOD MACHINE TOOLS LIMITED · PRINCES ROAD · DARTFORD · KENT

Telephone: DARTFORD 5271 (5 lines)

Telegrams: ABWOOD, DARTFORD

Fine Boring — Boring — Counter Boring — Chamfering



The **PRECIMAX** *way*

**at INTERNATIONAL
HARVESTERS LTD**

Cylinder head production is maintained at peak efficiency thanks to these PRECIMAX FB 1/3 Fine Boring Machines which perform the operations shown on the left. In the upper picture valve guides are fine bored and valve seats generated with automatic compensation for the difference between exhaust and inlet seat diameters. The lower picture shows the fine boring, counterboring and chamfering of injector bores.

A growing number of engine manufacturers are finding that for accuracy, versatility and production efficiency in fine boring, the PRECIMAX automatic cycle machines are indispensable.

JOHN LUND LIMITED · EASTBURN WORKS · CROSS HILLS · Nr. KEIGHLEY
TELEPHONE: CROSS HILLS 3211 (3 LINES)

When answering advertisements kindly mention MACHINERY.


TOLIMIT

MASTER GAUGEMAKERS

GAUGES TO MILLIONTHS

AS STANDARD
COMMERCIAL PRODUCTION

At no extra cost



Here's Proof

ON TALYROND CHARTS

The charts illustrated were supplied to us by a well-known Bearing Manufacturer. The chart reproduced is typical of a batch of 13 and shows a 4in. dia. Tolimit plain ring Gauge truly round within 5 millionths of an inch.

It also illustrates the high degree of surface finish. Parallelism and roundness of Tolimit Rings and Plugs are regularly made to the highest order of accuracy obtainable—anywhere in the world.

FOR LIGHT WAVE PRECISION

Manufacturers of
PLUG, RING AND CALIPER GAUGES FOR PLAIN AND THREADED WORK,
AIR GAUGES, AUTOMATIC GAUGES, THREAD COMPARATORS, etc.

TOLIMIT · GAUGES · LIMITED

16 PETERBOROUGH ROAD · LONDON · S.W.6


Phone: Renown 2581



Press Brakes

FROM 50 to 400 TONS

UNBREAKABLE STEEL PLATE FRAME CONSTRUCTION



*We invite your enquiries
and are glad to give demonstrations in our Showroom*

HENRY PELS & CO. LIMITED

Offices & Showroom 32-38 OSNABURGH STREET · LONDON · N.W.1


Telephone: EUSTON 4113

When answering advertisements kindly mention MACHINERY.



measuring machines

up to 144" capacity



Superior quality, high precision instruments measuring to 0.00001 inch or 0.0001 mm and maintaining an overall accuracy of 0.0001" per foot., Newall Measuring Machines are indispensable equipment for the standards room or workshop.


Among a wide range of applications, they are eminently suitable for originating or periodically checking gauge sizes and standards.

The illustration below shows set-up for checking a length bar and also details the patented Newall Measuring System incorporated in the machine.

SIZE RANGE

ENGLISH	METRIC
0-24"	0-600 mm
0-48"	0-1200 mm
0-72"	0-1800 mm
0-144"	0-3600 mm

A PRECISION PRODUCT OF
OPTICAL MEASURING TOOLS LTD
MAIDENHEAD BERKS



full details on request to

NEWALL GROUP SALES LIMITED

PETERBOROUGH ENGLAND



Wimet

Internal and External

THREAD CUTTING TOOLS

WICKMAN LIMITED

WIMET DIVISION, TORRINGTON AVENUE, COVENTRY

Telephone File 66621

493 ST

When answering advertisements kindly mention MACHINERY.

MACHINERY is registered as a newspaper at the General Post Office and the name is a registered trade mark

Published every Friday by
The Machinery Publishing Co., Ltd.
Copyright reserved
Price 1/3

LESLIE R. MASON
Managing Director

CHARLES H. BURDER
Editor

EDITORIAL OFFICE

REGISTERED OFFICE, SMALL AND CLASSIFIED
ADVERTISEMENTS DEPARTMENT AND ENQUIRY BUREAU

CLIFTON HOUSE
83-117 EUSTON ROAD
LONDON, N.W.1.

Telephone: Euston 8441/2
Telegrams: Machtool, Norwest, London

HEAD OFFICE

SUBSCRIPTION, ADVERTISEMENT, SERVICE,
PHOTOGRAPHIC, ACCOUNTS AND BOOK DEPARTMENTS

NATIONAL HOUSE
21 WEST STREET
BRIGHTON, 1.

Telephone:
Brighton 27356
(3 lines)



Telegrams:
Machtool,
Brighton

NEW YORK:
93, Worth Street

PARIS:
15, Rue Bleue

SUBSCRIPTIONS:—Inland and overseas,
52 shillings per annum, post free. Cheques
and Money Orders should be made payable
to the Machinery Publishing Co., Ltd.

ADVERTISEMENTS:—Copy for displayed
advertisements, if proofs are required, should
reach the Brighton office 21 days in advance
of publication. Rates on request.

Small (classified) advertisements can be
accepted, space permitting, at the London
office up to Saturday morning for publication
on the following Friday. For rates, see
p. 139.

Blocks are held at advertisers' own risk;
no responsibility for loss is accepted by the
publishers.

MANUSCRIPTS FOR BOOKS covering all
branches of engineering production will
receive careful consideration and should be sent
to the Manager, Book Dept., MACHINERY,
National House, 21 West St., Brighton, 1.

MACHINERY

A JOURNAL OF METAL-WORKING PRACTICE
AND MACHINE TOOLS

Vol. 92, No. 2357

January 17, 1958

COPIES PRINTED.....11,500 per week

CERTIFIED DISTRIBUTION.....11,376 per week

CERTIFIED PAID DISTRIBUTION.....10,566 per week

CONTENTS

Editorial

Women in Engineering..... 119

Principal Articles (For Abstracts see next page)

The British Timken New Building Project..... 120
The Re-servicing of Carbide Tools..... 136
Typical Operations on Components for Piatti Motor Scooters..... 149
Measurement of Paint Thickness on Aircraft..... 156
Baldwin Automatic Control System for a Rolling Mill..... 157
Conference on Problems of Aircraft Production..... 159

Short Articles

New Progress Machine Vices..... 147
New Burnerd Multisize Collet Chuck..... 148
Star "Tolerance" Rings..... 155
"National" Machines to be Built in this Country..... 164

News of the Industry

Yorkshire..... 166
Classified Advertisements..... 139
Index to Advertisers..... 181

CONDITIONS OF SALE AND SUPPLY.—MACHINERY is sold subject to the following conditions:

That it shall not, without the written consent of the publishers first given, be lent, resold, hired out or otherwise disposed of by way of trade except at the full retail price of 1s. 3d. and, that it shall not be lent, resold, hired out or otherwise disposed of in a mutilated condition or in any unauthorized cover by way of trade; or affixed to or as part of any publication or advertising literary or pictorial matter whatsoever.

[p. 117]ii

Abstracts of Principal Articles

The British Timken New Building Project P. 120

At the highly-mechanized N.B. plant of British Timken, Ltd., Duston, cups, cones, and rollers for tapered-roller bearings are finished on separate lines. From the hardening department, cups are passed into storage hoppers, whence they are fed to a Gardner machine for grinding both end faces. The ground cups are next delivered to two parallel lines, equipped with similar machines. Each line incorporates Cincinnati centreless grinding machines for finishing the outer surfaces; Heald Centrimatic machines for finish grinding the bores; and Timken machines for lapping the bores, the latter employing abrasive tape as the finishing medium. After they have been finished, cups are inspected and washed, before mating inner race units are assembled. Cones are similarly treated, and pass through a Rowland duplex face-grinding machine, thence to two lines of Cincinnati, Heald and Timken machines for finishing the bore, roller track, and rib. Washing and inspection follow, before the cones are assembled to rollers and cages on semi-automatic machines. Hardened and tempered rollers are delivered to the finishing lines from the main factory, and pass through Cincinnati centreless grinders, Timken spherical-end grinding machines, and washing and drying units, to mechanized inspection stations. They are finally graded, before they are passed to the adjoining section for assembly to cones. Various interesting work-feeding, distribution and re-orientating units have been developed to facilitate the flow of cones and cups through the plant. (MACHINERY, 92—17/1/58.)

The Re-servicing of Carbide Tools... P. 136

The economic advantages of tungsten carbide tooling can be fully realized only by careful attention to the correct methods of servicing, employed at the correct times. In this article, attention is first drawn to the structure of tungsten carbide and its implications. Grinding wheels and their cutting action are discussed, with particular reference to diamond wheels. A section is devoted to off-hand grinding and its applications, including the sequence of operations to be followed and the modification of standard tools. Machine grinding is subsequently considered, and various typical operations are described in detail and illustrated. These operations are concerned, for example, with the production of a parting and chamfering tool from a standard bar tool, and the sharpening of end mills and milling cutters. Other subjects covered include chip breakers, the re-servicing of tools by spark-erosion, and surface finish and the cutting edge. (MACHINERY, 92—17/1/58.)

Typical Operations on Components for Piatti Motor Scooters..... P. 149

The Piatti motor-scooter made by Cyclemaster, Ltd., is equipped with a horizontally-mounted 2-stroke engine. Operations on some of the principal components for this engine are here described, including the final drive spindle, which is turned in two stages

on multi-tool lathes. Subsequently, the spindle is drilled, slotted, and serrated and threaded by rolling. Multi-tool lathes are also employed for the crankshaft, on which threads and oil grooves are later formed by rolling. To ensure accurate concentricity, serrations are cut on a gear generator, and the shaft is selectively hardened by the induction process prior to finish grinding. For drilling and tapping the components of the light-alloy split casing, horizontal, 2-way multi-spindle machines are employed. Other set-ups described are concerned with fine-boring operations on the cylinder, connecting rod, and front suspension arm. (MACHINERY, 92—17/1/58.)

Measurement of Paint Thickness on Aircraft P. 156

It is pointed out that in addition to being smooth, the paint layer on a high speed aircraft must be of uniform thickness within close limits. Reference is made to various methods of thickness measurement, and the manner in which a Boonton film gauge has been modified for this purpose, by the Martin Co., U.S.A., is then described. A meter is set to zero with the aid of a sample, and is calibrated to show paint thickness in thousandths of an inch. (MACHINERY, 92—17/1/58.)

Baldwin Automatic Control System for a Rolling Mill..... P. 157

A Robertson cold-strip rolling mill, installed in the works of D. F. Taylor, Ltd., Birmingham, has recently been equipped with the new Baldwin nucleonic automatic gauge-control system. With this system, which depends on bremsstrahlung radiation produced by the emission of beta rays from a strontium 90 source, material thickness ranging from about 0.004 to 0.4 in. can be checked. With the installation here described, the strip thickness is accurately and continuously measured, and is controlled by automatic adjustment of the roll setting. In addition, the thickness is continuously recorded on a paper chart, and is indicated on a dial type meter. Reference is also made to the method of calibrating the gauge. (MACHINERY, 92—17/1/58.)

Contributions to MACHINERY

If you know of a more efficient way of designing a tool, gauge, fixture, or mechanism, machining or forming a metal component, heat treating, plating or enamelling, handling parts or material, building up an assembly, utilizing supplies, or laying out or organizing a department or a factory, send it to the Editor. Short comments upon published articles and letters on subjects concerning the metal-working industries are particularly welcome. Payment will be made for exclusive contributions.

IN FORTHCOMING ISSUES

The production of components for Lambretta motor scooters—Heavy bending operations.

Women in Engineering

Although women have been employed for certain duties in engineering works and similar establishments for many years, they are seldom—in this country—engaged in the type of work that falls within the province of the professional engineer or technologist. In view of the contributions that women have made to progress in other scientific fields, there does not appear to be any valid reason why they should not undertake the most exacting duties in those branches of science and technology associated with engineering, provided that they have acquired the necessary training and experience.

Any form of engineering or technological education should be based upon practical training. At one time, the arduous physical labour involved in an engineering apprenticeship, or similar programme of training, might have deterred women from embarking on an engineering career. In the past, when heavy engineering was the backbone of our industry, such a view was justified. Conditions have improved, however, and, in progressive works, much of the heavy manual labour formerly required has now been eliminated by the introduction of mechanical appliances and handling aids on an extensive scale. Due to changes in the industrial pattern, moreover, the light and medium engineering industries occupy very important positions in the economic structure of this country at the present time. For these branches of engineering, the practical training, although exacting, is not so arduous as to be beyond the physical capabilities of young women. These branches, moreover, include industries that specialize in the production of domestic and other equipment, to which women should be able to make a particularly useful contribution.

Although the rigours of practical training should no longer deter women from embarking on engineering careers, the specialized education—both practical and theoretical—that is necessary, calls for certain sacrifices, principally in initial earning power and leisure. Such sacrifices will only be made when there is reasonable certainty that the future will afford ample compensation. Clearly, conditions of employment must have some influence, but actual working conditions need not concern us here, since it is now generally accepted that engineers and technologists, whether male or female, can only work at their optimum efficiency

in good conditions, and offices and laboratories in modern engineering establishments are of a very high standard. Other conditions must be made equally attractive if women are to be persuaded to enter the engineering profession in any numbers. It is essential, therefore, that once they have acquired the same training and experience, women should be treated as the equals of their male colleagues, not only as regards pay, but in other directions. They should not be employed merely for routine duties, but should be given work that affords full scope for the application of judgment, imagination and initiative. Equality, moreover, should extend to status, responsibility, and opportunities for promotion, up to the highest levels.

The entry of large numbers of women into the engineering and allied professions will introduce certain problems, not the least of which will be concerned with marriage. Any employer may justifiably be filled with misgivings at the prospect of losing a promising young woman engineer at the time when, after an extended period of training, she is starting to make a really worthwhile contribution to the progress of his company. It would clearly be undesirable that women should forgo marriage for the sake of a career in industry, but many would doubtless be prepared to continue working after marriage until the demands of home and family became too pressing. As with other professions, moreover, an engineering career need only be interrupted by marriage, and not ended, and provided that the work was sufficiently stimulating and rewarding, many women would probably be willing to resume their careers after a few years. It would then be necessary to arrange for them to undergo some form of refresher course, in order to bring their knowledge up to date, and to restore skills, which might have been temporarily lost, to their former efficiency. Such courses would need to be of only limited duration, however, since knowledge and skill, once thoroughly acquired, are seldom completely lost.

If British industrial expansion is not to continue to be hampered by a lack of trained technical workers, it is generally agreed that the numbers of qualified engineers and technologists must be doubled in the next ten to fifteen years. It is obvious, therefore, that we cannot afford to neglect any source of high-quality recruits, yet the pro-

(Continued on page 167)

The British Timken New Building Project

Automatic Production Facilities for the Manufacture of Tapered Roller Bearings in Large Quantities

In MACHINERY, 92/4—3/1/58, were given some details of the highly-mechanized production facilities which have been established by British Timken, Ltd., Duston, Northants, for the manufacture of certain of their tapered roller bearings in very large quantities. It may be recalled that the N.B. Plant, as it is known, is designed for a maximum output of 5-million assembled bearings per year, although at present the output rate is 3-million per year.

The N.B. Plant is housed in a modern building separate from the main works at Duston, and has its own service installations—for example, for heating, swarf disposal and cutting oil reclamation. There are three main departments, which provide for the production of cup and cone blanks, on single and multi-spindle automatics; for heat-treatment of the blanks, by carburizing, hardening and tempering; and for grinding cups, cones and rollers, assembling these components with cages to form finished bearings, greasing, and packing.

In the article mentioned, operations on cups and cones were followed, in detail, to the end of the heat-treatment cycle. At this stage, the hardened and tempered parts are shot-blasted, and then are ready for grinding. Cups and cones are delivered to separate storage hoppers at one end of the grinding department, which, it may be noted, is

divided into three sections for finishing cups, cones and rollers. In the sections for cups and cones, there are two distinct machine lines, one for large, and the other for small, workpieces. The layout of the department is shown diagrammatically in Fig. 1 (which is part of the layout of the whole plant included in the first article), and the hoppers for cups and cones may be seen at the right.

CUP-GRINDING LINES

The storage hoppers are arranged in groups of four, and are generally similar to those installed between the automatics shop and the heat-treatment department. Hoppers for cups are indicated at S in Fig. 1. Large cups are delivered to two of these hoppers directly from the Timken-built shot-blasting machine in the heat-treatment department, whereas the small cups, after being shot-blasted in the main factory, are loaded into a small intermediate hopper in that department, whence they are delivered by elevator and chute to the other hoppers in the group S. Each hopper has sufficient storage capacity for one week's work, and this reserve of parts facilitates change-overs, and provides an allowance for any interruptions in production which may occur in preceding departments. Normally, it may be noted, the full





Fig. 1. Diagrammatic Layout of Part of the N.B. Plant at the Duston Factory of British Timken, Ltd. Cups and Cones Flow from the Hardening Department at the Extreme Right, Through the Finishing Lines, to the Packaging Section at the Upper Left

Fig. 2. The Gardner Twin-disc Machine for Grinding the End Faces of Cups. It is Operated on an 8-hour Shift, and Supplies both Cup-finishing Lines



capacity of the hoppers is never used.

Cups are fed automatically from the hoppers by vibratory feeders, and pass on to belt conveyors which deliver them to a gravity-feed chute. This chute serves a Gardner type 125 twin-disc machine for grinding the end faces, to finish the cups to width. The cups pass under motor-driven brushes before they enter the chute, and the latter incorporates equipment for turning the workpieces through 180 deg., if necessary, to ensure that all enter the Gardner machine with their broad ends facing in the same direction. Limit switches and associated equipment are fitted to maintain an adequate head of parts in the chute, thus ensuring that the cups are delivered satisfactorily to the power-driven rolls, whereby they are fed between the wheels of the grinding machine.

The outlet side of the Gardner machine is shown in Fig. 2, and it is provided with air-gauging equipment which is used to control the in-feed mechanisms for the grinding wheels. Since each workpiece has one wide and one narrow face, the rates of wheel-wear differ. Compensating arrangements are incorporated, therefore, and one grinding wheel is advanced at more frequent intervals than the other. A tolerance of 0.002 in. is specified for the width of the cup, but a much closer tolerance is maintained in practice, with the aid of the automatic sizing equipment. The machine has a self-contained coolant system, with a magnetic clarifier unit, the latter being visible at the right in Fig. 2.

Other machines in the cup-grinding section, also in the sections for finishing cones and rollers, are supplied with coolant from a bulk source. This centralized coolant supply is housed in a service block, adjacent to the N.B. building, and coolant is delivered by pipes in a main service trench that links the block with all the grinding sections, and also houses the return lines. In the service block, there are settling tanks, and a battery of magnetic drum clarifiers to clean the coolant, also large capacity pumps for its distribution.

Cups pass from the Gardner machine, down a

chute, to a vertical peg-type elevator, which delivers them to two gravity-feed chutes serving 4-deck spiral feeders. The Gardner face-grinding machine is operated for one 8-hour shift each day, and supplies both cup-grinding lines. Cups of one particular size are face ground as a batch, and a change-over is made about three times in two days. Change-overs are carried out, on this and other machines in the section, by a setter and an operator acting as a team, and it is planned eventually to train the staff in the New Building so that they will be able to undertake the change-over and setting of any machine, or piece of equipment, in the grinding, heat-treatment, or automatics departments.

SPIRAL BRUSH-FEEDER

The elevator associated with the Gardner machine may be seen in the foreground of Fig. 3, which is a general view of the two cup-grinding lines. The spiral brush-feeders served by the elevator are indicated at *T* in Fig. 1, and one of these feeders is similarly indicated in Fig. 3. Cups pass up the elevator with their side faces parallel to the rows of grinding machines, and, in order that they may roll into the brush feeders, are re-oriented through 90 deg., by a standardized Timken cage-type unit *A*. A deflector below this unit directs cups to the right- and left-hand chutes as required, and the chutes connect the elevator with the upper decks of the brush feeders. These feeders are typical of the units employed throughout the N.B. plant, and their construction will be described with reference to that seen at *T*.




Fig. 3. A General View of the Cup-finishing Lines. Cups are Delivered from the Gardner Spiral Brush-feeders, One of Which May be Seen at the Left

As will be observed, the decks of the feeder are of circular form, and each has a spiral track. The track of the upper deck is connected, at its periphery, with the gravity-feed chute from the elevator, and leads towards the centre of the deck. Here, it joins another gravity-feed chute, which, in this instance, leads to the start of the spiral track of the second deck. On a single-deck feeder, however, the chute may lead to an adjacent machine. The inner end of the spiral track of the second deck is connected, by chute, to the start of the track on the third deck, and, similarly, the track of the third deck to the track of the fourth deck. A vertical shaft, passing through holes at the centres of the decks, is driven, through a reduction gear box, by a motor below the bottom deck. The shaft carries 4-arm spiders, each spider being positioned above one of the feeder decks. Secured to the arms of each spider are soft-bristle brushes, similar to a domestic broom head, and as the shaft is rotated, the brushes sweep the workpieces in the spiral track of each deck from the inlet chute towards the outlet chute at the centre. A light pressure is applied to the workpieces by the bristles, and is adequate for feeding purposes. When the tracks in the decks become full of parts, however, the bristles are deflected and pass over the workpieces without causing damage. As the brushes rotate continuously, workpieces are directed from the inlet chute of the top deck, downwards to the bottom deck, and as the stock of parts builds up, each deck is filled in turn.

The two 4-deck feeders *T* deliver cups by way

of elevators and chutes to a Cincinnati No. 3 centreless machine at the head of each grinding line. These machines are shown at *U* in Fig. 1 and 3, and provide for first-pass grinding the cups, externally. Both machines are fitted with automatic loading arrangements which will be described later. The feeder indicated at *T* in Fig. 3 serves the line for grinding the smaller cups, and the end faces of these cups are of such a width that it is necessary to ensure that alternate cups are delivered to the Cincinnati machine with their broad and narrow faces leading, in order to prevent "riding up" and jamming in the machine throat or the automatic loading mechanism. A re-orientating unit, developed by the company, is installed between the outlet chute from the bottom deck of the feeder and the associated elevator, and this unit is shown in Fig. 4.

AUTOMATIC RE-ORIENTATING UNIT

Supported on a floor-mounted, sloping platform, the unit embodies an indexing drum *A* in a cylindrical housing. An aperture in the housing allows cups to pass into a slot in the drum from the chute *B*, connected to the lower deck of the brush feeder. There are two other apertures in the housing, which provide for communication with the ends of the horseshoe-shaped trough *C*. This trough is of U-section, and at the lower end of the horseshoe a slot is cut in the bottom of the U-form and leads to the delivery chute *D* for the elevator serving the Cincinnati machine.

A pinion is secured to the lower end of the shaft of the indexing drum *A*, and meshes with a sliding rack *E*, a bracket on the outer end of the rack being coupled to the piston rod of an air cylinder. Pressure-air is directed by a valve to each end of the cylinder alternately, and this valve is actuated

by means of a cam, driven by the motor *F*, through an integral reduction gearbox. The arrangements are such that the drum *A* is oscillated continuously through 240 deg., so that its slot moves from a position in line with one end of the horseshoe trough, past the aperture associated with the chute *B*, to a position in line with the other end of the trough.

As the slot passes the aperture, a cup rolls into it from the chute, and is delivered to the right- or left-hand side of the horseshoe trough. The cup then rolls round the trough, and drops through the opening at the bottom of its curved form, into the chute *D*. Cups enter the slot in the drum with their broad side faces to the left, and are passed to the ends of the horseshoe with these faces to the right. A cup delivered to the right-hand side of the horseshoe passes through the opening leading to the chute *D* with its broad face away from the drum *A*, whereas a cup delivered to the left-hand side passes through the opening with its broad face towards the drum *A*. Thus, cups pass down the chute *D* with their broad faces to the right and left, alternately.

FEED ARRANGEMENTS FOR CENTRELESS GRINDERS

From the lower end of the chute *D*, the cups are lifted by a standard Timken peg-type elevator, and are discharged into an inclined chute leading to the loading mechanism of the Cincinnati No. 3 centreless grinder. Cups are fed into the machine throat along a trough, and it is important that a steady feeding pressure should be applied, since irregular pressure would result in an uneven finish on the external surfaces of the cups. Moreover, if the cups were not maintained in a "solid" stack in the trough, they might swing sideways, so that their outside surfaces were not ground square with their end faces. The feed mechanism was designed by the Timken Roller Bearing Company, U.S.A., and similar arrangements are provided on the machines for grinding large and small cups, the equipment on a machine for large cups being shown in Fig. 5.

The chute leading from the elevator is indicated at *G*, and its lower end, which is free to pivot, is connected to the moving carriage *H*. This carriage is fitted with rollers, and moves on one flat and one vee guideway on a bracket secured to the grinding machine base. A third guideway is provided for the roller of a support *I*, for the swinging portion of the chute *G*. A constant force is applied to the carriage by a cable and weight system, so that it is urged towards the grinding throat of the machine. During initial setting and loading, or when adjustments are being made, the carriage can be held in

the position shown, by means of the latch piece *K*.

A trough *L*, of V-form, is disposed parallel with the guideways and extends into the grinding throat. The outer end of this trough is located beneath the downwardly-curved extension of the chute *G*, and cups pass down the chute into the trough. Secured to the under-side of the carriage is an f.h.p. motor *M*, with an integral reduction gearbox, for driving a cam which oscillates a mushroom-head pusher in line with the trough *L*.

The carriage is urged towards the grinding throat by the action of the weight and cable system, and the mushroom-head pusher applies a constant feeding pressure to the stack of cups in the chute *L* (shown empty in Fig. 5). As the carriage moves forward, it contacts an adjustable stopscrew *N*. In this position, one of two striker screws on the carriage trips the switch *P* to engage the motor drive. Oscillated by the cam, the pusher thrusts against the stack of cups, and forces the carriage outwards, a constant pressure still being applied to the stack by the weight. At the front of the carriage, there are three spring-loaded pawls which engage the outermost cup of the stack to hold it square, and to maintain the feeding pressure when the pusher is withdrawn by the cam.




Fig. 4. This Timken-designed Re-orientating Unit is installed to Ensure that Cups are Delivered Alternately to the Finishing Line with Their Broad and Narrow Faces Leading




Fig. 5. Feed Mechanisms of the Type Here Shown are Fitted to the Cincinnati No. 3 Centreless Grinding Machines for Cups, which are also Provided with Etamic Gauging Equipment

As the pusher is withdrawn, a cup from the chute *G* passes downwards into the trough *L*, and occupies the space between the pusher and the end of the stack. When the pusher is again advanced, during the next oscillation cycle, it thrusts against the cup that has just been loaded, and the carriage is again moved outwards, so that another cup can drop into the trough, when the pusher is retracted. Cups are loaded during successive oscillatory cycles of the pusher, and the carriage is moved outwards until the switch *P* is re-set by the second striker screw *R*. The driving motor is then stopped, and the complete stack of cups is fed into the grinding throat of the machine as the carriage is urged forwards by the weight and cable system. When the carriage reaches the limit of its forward travel, the switch *P* is again re-set, and a further loading cycle is initiated.

GAUGING EQUIPMENT FOR CUPS

From each of the Cincinnati machines (*U*, Fig. 1 and 3), rough-ground cups pass, by way of a chute, into a single-deck spiral brush feeder, and are delivered to a second Cincinnati No. 3 centreless machine, for finish grinding. Both the finish-grinding machines are equipped with automatic loading arrangements of the type just described, and all the Cincinnati machines are fitted with Etamic gauging and size-control units. At present, the Etamic equipment on three of the machines provides a visual indication of work-size during grinding by means of coloured signal lamps. One of the

roughing machines has been equipped with feed-back control for automatic adjustment of the grinding wheel, because of the higher rate of wheel-wear which occurs at this stage. Eventually, however, all four machines will be thus equipped.

A quality control check is carried out after finish grinding, and one cup is removed every 30 min. from the outlet chute of the second machine of each line. Checking is carried out with the aid of the bench-mounted equipment shown in Fig. 6, which is located between the second Cincinnati machine, and the first of a battery of Heald 190 Centrimatic internal grinders. The outside diameter of each cup is measured by means of the adjustable gauge





Fig. 6. This Bench-mounted Equipment is Installed for Carrying Out Periodical Checks on Cups, for Size, Lobing, Tri-lobe Form, and Taper

Fig. 7. The Bores of Cups are Finish-ground on a Battery of Heald 180 and 190 Centrimatic Machines. This 190 Machine has Federal Automatic Size Control Equipment



A. Lower and side supports can be set to position the cup beneath a gauging jet, which is connected to a Solex manometer unit at the rear of the bench. The gauge A is supported on a bracket at the left-hand side of the bench, and on the bench itself is mounted a 2-station gauge, and the associated Taylor-Hobson dial-type indicating units. A check for "lobing" is carried out at the left-hand station, while the work is rotated between a V-support and a stylus-type gauging head, which is connected to one of the indicators. Two stylus heads are employed at the next station to ascertain whether the cup has a "tri-lobed" form. The cup is finally checked for external taper by the sensitive dial-indicator gauge at the right of the bench.

Cups are delivered by chute from each of the Cincinnati finish-grinding machines to a 4-deck, spiral brush-feeder, and thence to a turn-over unit, which serves the Heald and Timken machines for finishing the bores of the cups. From the feeder, the cups are delivered to an elevator, and thence to the band conveyor of a distributor unit at the rear of the bore-finishing machines. One of the distributors may be seen at V in Fig. 3, and both units are similarly indicated in Fig. 1. The conveyor band circulates continuously, and its upper run moves over angularly-disposed support plates, mounted about 6-ft. above floor level. The structure whereon the conveyor is mounted takes the form of a long, shallow cabinet, which houses the service mains for the line of bore-grinding machines. These service mains provide for the delivery and return of grinding coolant, and hydraulic fluid, from and to centralized sources, also the supply of compressed air, and electrical power of both normal and high frequency.

The service mains, including those housed in the distributor units for the cone-finishing lines, are connected by a main service trench below floor

level, to the service block, adjacent to the New Building. In this block is installed the plant for clarifying and pumping coolant for the grinding machines, as has already been mentioned. All the machines for grinding and honing cups and cones, and for grinding the ribs on cones, are hydraulically operated, and a central pumping installation circulates oil at a pressure of 150 lb. per sq. in. The system incorporates a by-pass centrifuge for continuous purification of the oil, and a stand-by pump unit.

All bore grinders are equipped with high-frequency spindle heads, and the electrical supply for these heads is generated by four motor-alternator sets, two further sets being provided as reserves. Since the bore-sizes of the components produced on each line differ, it is necessary to run the spindles at different speeds. In consequence, each of the four alternators is arranged to provide power of a suitable frequency for a particular line. Any alternator can be disconnected from one line and re-connected to another, and the frequency adjusted, in a few minutes, should a breakdown of any set of supply equipment occur.

WORK-DELIVERY ARRANGEMENTS FOR BORE GRINDERS

The distributor unit for one of the bore-grinding lines for cups may be seen at the rear in Fig. 7. Cups are carried on the band, and move in contact with a guide strip A, at its lower edge. At intervals

along the conveyor, above the moving band, there are deflectors, which direct the workpieces into chutes leading to the three Heald 190 Centrimatic machines employed for grinding the bores of the large cups. One of these machines may be seen in the foreground in Fig. 7, and the delivery chute is indicated at B. On the parallel line for small cups, it may be noted, Heald 180 Centrimatic machines are employed, with similar delivery arrangements.

When each chute leading to a Heald machine is full, the cups continue to move on the band until they reach a transverse chain conveyor C. Then, the cups pass through a gap in the lower guide strip, and are transferred by the chain conveyor to a second horizontally-disposed band, which moves in the opposite direction to the first, on top of the distributor unit. On this band, cups are carried to the head of the distributor, where they are deflected, through a gap in the guide strip at one side, on to the first conveyor, and are re-circulated. Work-flow on the conveyor bands, and delivery of cups to the distributor, are controlled by limit switches, and the stock of cups maintained in circulation is sufficient to allow for routine stoppages—for example, to allow for replacement of the grinding wheels.

The entry end of each chute leading to a Heald machine incorporates a re-orientating section, whereby the cups are turned through 90 deg., before they enter the main portion of the chute. Cups roll down the chute, past a freely-rotating toothed-wheel D, which serves to control the flow, and are released, one at a time, to a pair of carbide-tipped shoes located between the wheel head E and the backing plate fitted to the work-spindle of the machine. While the conical bore is being ground, the work is supported on the shoes, and is driven by the backing plate, with which it is held in contact. On most of the Heald machines, the arrangements for holding the work against the backing plate are generally similar to those described in *MACHINERY*, 89/463—24/8/56. The machine shown in Fig. 7, however, is provided with a magnetic backing plate, and the usual clamping ring is not required.

This machine—the last in the line for large cups—is equipped also with Federal equipment for the control of bore size. Control is effected by means of a fork-type gauge, which is in position in the bore of the cup while it is being ground, and is connected to the unit F. During each cycle of the machine, under the automatic control system, the grinding head is advanced at a rapid-approach rate, and the bore is then ground to a diameter that is 0.0004 in. below finished size. The head is then withdrawn, the grinding wheel is

dressed automatically, compensation is made for the amount of wheel material that has been removed, and the head is again advanced into the bore, to grind the part to finished size. Finally, the head is withdrawn, and the cup is automatically ejected. At the top of the control unit F there are three signal lamps, which are illuminated to indicate the various stages of the cycle. A green lamp signifies that the preliminary grinding stage is in progress; an orange lamp, the dressing stage; and a red lamp, the finishing stage. During grinding, the amount of metal removed is indicated by means of a large dial gauge below the lamps. This Federal control equipment has been found particularly effective in connection with the grinding of cups for bearings which must have close assembly limits. These bearings are required for certain applications, for example, the differential assemblies of motor cars.


GAUGING CUP BORES

At regular intervals, cups are checked for bore-size by patrol inspectors, and a gauging station is installed between the second and third Heald



Fig. 8. Periodically, the Tapered Bore of a Cup is Checked with this Equipment. The Bore Diameter is Indicated by the "Stand-up" of an Air Gauging Plunger, which is Registered on an Associated Mercer Dial-type Instrument

Fig. 9. One of the Timken-designed Machines for Honing the Tapered Bores of Cups. Abrasive Tape is Employed as the Honing Medium, and is Held in Contact with the Work by an Oscillating Shoe



TIMKEN BORE-HONING MACHINES

machines of each line. A gauging station is shown in Fig. 8, and the equipment comprises an air-operated gauging plunger, and an associated Mercer dial-type instrument. The gauging plunger is mounted in a bracket, above a lapped surface plate on which the cup to be checked is placed. At the lower end of the plunger is secured a tapered adapter to suit the size of cup. By resetting a valve at the front of the gauging unit, the plunger is thrust downwards by air pressure, so that the adapter is engaged with the bore of the cup. The gap between the lower end of the adapter and the surface plate controls the flow of air from an associated jet, which is connected to the Mercer indicator. The arrangement is such that the diameter of the bore is indicated by the "stand up" of the adapter, which must lie between limits set by pointers on the dial of the instrument. Master cups are employed for setting the Mercer gauge, and a set of masters and adapters is provided for the complete range of cups produced.

From each of the Heald machines, large cups are delivered by chute to a belt conveyor, which is located between the machines of each group and the associated distributor. On the belt conveyor, cups are transferred to the elevator C, Fig. 7, from the top of which they roll, by way of a chute, to the second section of the angularly-disposed band conveyor of the distributor. From this second section, cups are deflected into the chutes of two machines (W, Fig. 1) on which the bores are honed. The arrangements of the second half of the distributor are generally similar to those that have already been described, and when the chutes are full, cups are transferred by a chain conveyor to the horizontal band conveyor, and are re-circulated.

The machines for honing the bores of the large cups were designed and developed by British Timken, Ltd., and a typical unit is shown in Fig. 9. Honing is effected by abrasive tape, which is drawn from a bulk-supply on the reel H. The tape passes, over guiding and tensioning rollers, to a honing shoe that projects from the head J, and thence, over further guide rollers, to a feed unit K. Pivotaly mounted, the head J can be adjusted angularly in the vertical plane, with reference to a protractor scale, in order that the shoe may be set so as to support the tape in contact with the conical surface of the bore to be honed. Within the head, the shoe is supported on leaf springs, and can be oscillated rapidly, over a fixed stroke, parallel to the bore surface.

From the distributor at the rear, cups are fed down an inclined chute L to a loading unit mounted on the front of the workhead of the honing machine. The leading cup in the chute rests in the position indicated at M. In Fig. 9, the machine is shown with a workpiece loaded in position and the honing operation in progress. At the start of each cycle, a bifurcated lever N is swung downwards to carry the cup from the position at M, round an arcuate guideway, until it comes to rest on a pair of idler support rollers located in front of a rotating magnetic plate. Sufficient clearance is provided between the arms of the bifurcated lever to allow the workpiece, which is driven by the magnetic face plate, to

rotate freely on the supporting idler rollers.

With the cup rotating, the honing head is moved inwards, and then downwards, by hydraulic means, so that the abrasive tape is held against the cup-bore by the shoe. This shoe applies a pre-set pressure for a specific period, governed by a timer, during which the cup bore is rough-honed. At the end of this period, the head is lifted, hydraulically, to allow the abrasive tape to be advanced by the feed unit *K*, so that fresh tape is positioned around the shoe. Next, the head is again lowered, to apply the fresh abrasive tape to the bore for a further specified period, governed by a second timer, during which the bore is finish-honed.

At the end of the second, or finish-honing stage, the head *J* is lifted, and then retracted from the cup bore, fresh tape being advanced during this movement. At the end of this movement, the bifurcated lever *N* is swung upwards, and, at the same time, outwards. Next, the finish-honed cup is lifted by the lower arm of the lever, and, since it is no longer held against the back plate of the loading unit, it rolls sideways over the front supporting roller, through a gap in the arcuate guideway, and into the chute *P*. This chute leads to an elevator serving a 4-deck, spiral-brush feeder, and as the cup rolls downwards it passes through a de-magnetizing tunnel at the left-hand side of the honing machine. During honing, a mixture of 1 part of sulphurized honing oil and 9 parts of "300" burning oil is applied, to remove the fine particles of metal produced, and at this operation a finish of 4 to 8 micro-inches is obtained in the workpiece bores.

Honed cups are delivered from the brush feeder at the end of each cup line to a degreasing unit *X*,



Fig. 1, where they are cleaned by high-pressure jets of distillate, which are directed on to them, from above and below, as they move on a twin-lane mesh belt. The distillate is continuously cleaned by means of a centrifuge. After they have been washed, the cups pass, by way of spiral-brush feeders and chutes, to a visual inspection station seen in Fig 10, where they are subjected to a 100 per cent check by two female inspectors. The cups roll down a chute *R* to a track in front of the first inspector, seen at the right. Of an S-form in plan, the track is built up from rods, and the open construction facilitates viewing. The track is arranged so that the cups are disposed at a slight angle, and their bores are readily visible to the inspectors. A mirror is mounted on the side of the track opposite to the inspector at each station, and enables the rear faces of the workpieces at each position to be viewed by reflection. Cups are rolled along the track by the first inspector, using a length of brass wire, and then pass by way of the inclined, middle section to the second station. Here, the face which was away from the inspector at the first position is presented towards the second inspector. Cups are checked for finish, presence of chamfers, marking defects and surface cracks. The thin coating of distillate left on the cups from the washing stage, it may be noted, emphasizes any cracks or flaws. At each station, the upper front-rail of the track is interrupted, and any faulty workpieces are deflected from the track by the inspectors, and fall into a chute below. The end of the second section of the inspection track communicates with a chute, whereby the cups are delivered to a greasing installation (*Y*, Fig. 1). Here, they travel on a moving belt through a bath of heated grease, which provides a protective coating, and, after draining, are delivered to a packing station (*Z*, Fig. 1) where they are fitted to pre-assembled cones, cages and rollers.

Automatic air gauging equipment is shortly to be installed, and one unit will be located at the end of each cup line, before the greasing installa-

Fig. 10. Cups are Visually Inspected, on a 100 per cent Basis, at this Station, where they are Fed along Tracks, Past Operators who Inspect Each Side in Turn. Faulty Cups are Deflected from the Tracks into Chutes which Direct them into Bins

tion. Each unit will be capable of measuring bore size, bore angle, cup width, and external diameter. Provision will be made on each unit for automatically rejecting those workpieces that are not within prescribed limits.

One group of work-people tend both cup lines. One setter and one operator, working on day shift only, serve the first two operation stages (Gardner and Cincinnati machines). The third and fourth operation stages (Heald and Timken machines) are run on three shifts, and are tended by one setter and one operator per shift. When the automatic gauging equipment is installed, final inspection will be carried out by two inspectors, who will work on day shift only.

CONE RE-ORIENTATING UNIT

Like the cup-finishing section, the section for finishing cones is divided into two lines, and provides for processing two different sizes of cones, simultaneously. Hardened and tempered cones are fed by vibratory feeders and chutes from the hoppers *a*, Fig. 1, to a Rowland duplex face-grinding machine *b*. This machine is provided with a dial-feed mechanism, also automatic sizing and control equipment. It may be of interest to note, moreover, that the wheel spindles of the Rowland machine, and of the Gardner machine for cups, are fitted with Timken tapered-roller bearings. The Rowland machine is operated for one 8-hour shift per day, and supplies both cone-finishing lines. Batches of cones of one size are ground at a time, and are stored in a spiral brush-feeder, or a hopper between the Rowland machine and the starting ends of the lines.

Cones are fed from the hoppers *a*, Fig. 1, with their large ends either to the right or left, and before cones enter the Rowland machine it is necessary that they should be arranged with their large ends on the same side of the delivery chute. A simple but effective, re-orientating unit is incorporated in the chute and is shown in Fig. 11, where the section of the chute leading from the hoppers is indicated at *A*. As may be seen, the chute has two branches, one of which is in line with the section *A*. The other branch, *B*, curves to the right (looking in the direction of cone travel). The curved portion of the branch *B* subtends an angle of about 160 deg., and the bottom plate of the chute terminates at the end of this portion, so that a cone can drop into the lower chute *C*. This latter chute follows an angular path, and is finally aligned with the entry chute *D* of the Rowland machine. The straight upper chute of the re-orientating unit is also aligned with the chute *D*, but is positioned above it, and the length of the bottom plate of the



Fig. 11. This Re-orientating "Point" is Installed in the Chute that Delivers Cones to a Rowland Duplex Face-grinding Machine, and Ensures that the Cones Enter the Machine with their Large Ends Facing in the Same Direction. This Unit can be Adjusted to Take Different Cones

upper chute is such that a cone passing along it eventually drops into the chute *D* and thence to the Rowland machine.

Mounted above the junction of the straight and curved chutes of the unit is a reversible plate *E*, to which are secured upper and lower guides. Each guide has one straight, and one curved, arm, and the arrangement is such that, when each is positioned below the plate *E*, there is a gap between the straight arm and the left-hand side of the chute (looking in the direction of cone travel), and between the curved arm and the right-hand side of the chute. If a cone rolls down the chute *A* with the rib at its large end to the left, the rib passes into the gap between the straight arm of the guide and the left-hand side of the chute. In consequence, the cone is directed down the straight, upper chute of the re-orientating unit, and drops into the chute *D*, with its larger end still at the left.

When a cone rolls down the chute *A* with its large end to the right, the rib at that end enters the gap between the curved arm of the guide and the side of the chute *B*. It is directed round the chute *B*, and drops, through the gap in the lower plate, into the chute *C*. During this movement, it has been turned through about 160 deg. relative to its original setting, and it enters the chute *D* with its large end to the left—that is, on the same side as for the cones delivered by the upper chute. The upper and lower guides on the plate *E* cater for cones of different diameters, and can readily be brought into use by releasing four nuts and reversing the plate.

MAGNETIC ELEVATOR

From the re-orientating unit, cones pass down a curved chute, and enter semi-circular seatings in the feed-dial of the Rowland machine, one at a time. The dial rotates in the vertical plane, and is positioned between the grinding wheels. Cups are carried round on the dial, to pass between the wheels, and after they have been ground, drop into a chute that leads to a vertical elevator. This elevator differs from the others in the N.B. plant, since it is not of the standardized chain-and-peg design, but is of a recently-developed magnetic type. A close-up view of the upper end of the elevator is given in Fig. 12, and it will be seen that it incorporates a moving belt *F*, of plastics-reinforced fabric. This belt passes over pulleys at the upper and lower ends of the supporting framework, which is constructed from steel sections. The upper pulley is driven by a motor, with an integral reduction gearbox, and the run of the belt seen in Fig. 12 moves upwards over a continuous series of permanent magnets, mounted between the side-members of the supporting frame.

The chute from the Rowland machine terminates in front of the belt, at the lower end of the elevator,




Fig. 12. The Elevator on the Outlet Side of the Rowland Machine Differs from the Others in the N.B. Plant, and Incorporates Banks of Magnets for Holding the Cones on an Upwardly-moving Belt

and cones are attracted to, and held on, the belt by magnetic force. Carried upwards on the belt, the cones enter a casing which surrounds the belt at the upper end of the elevator, and are thrust sideways by a deflector blade, towards the chute *G*. A heavy-duty electro-magnet *H* is mounted on the outside of the casing, and serves finally to pull the cones from the belt, and into the chute. Once a cone is clear of the belt, it passes down the chute, through the de-magnetizing tunnel *J*, and into the standard Timken re-orientating cage *K*. As it drops through this cage, it is turned through 90 deg., and subsequently enters either of the two chutes that connect the elevator to the storage units for the two cone-finishing lines.

A general view of one of the two parallel cone-finishing lines is given in Fig. 13, and the magnetic elevator may be seen in the foreground, with the two delivery chutes extending to either side. Cones are directed into each chute as required by a simple pivoted deflector. It may be noted that the arrangements for feeding workpieces to the machines in each line are generally similar to those that have been described in connection with the finishing of cups. A distributor unit, incorporating angularly-disposed and horizontal band conveyors, is located at the rear of the machines in each line, and cones are deflected from the angularly-disposed conveyor into the delivery chute of each machine. If the chutes of a group of machines are full, cones are transferred by transverse chain conveyors to the horizontal band, which moves in the opposite direction to the angularly-disposed band. On the horizontal band, workpieces are returned to the head of the group, and are there deflected back on to the first band, for re-circulation.

DRUM FEED UNIT

The 4-deck spiral brush-feeder that serves one cone-finishing line may be seen at the extreme left in Fig. 13, and is indicated at *c*, in Fig. 1. Since the plant was originally laid down, it has been found that cones with narrow ribs tend to lock in the spiral tracks of such feeders, and a different type of storage unit (*d*, Fig. 1) has been installed for the other finishing line. This storage unit is shown in Fig. 14, and the chute whereby cones are delivered from the magnetic elevator is indicated at *L*.

Cones fall into the bulk storage hopper *M*, which is provided to avoid an excessive load on the rotating drum feeder *N*. A Riley Stoker vibrator unit is fitted to the hopper to facilitate delivery of the cones to the feeder *N*, and is controlled by means of the Syntron unit mounted at the side of the hopper support frame. Cones pass, one at a time,




Fig. 13. A General View of One of the Two Parallel Cone-finishing Lines. Work is Delivered Automatically to each Machine by Distributor Conveyors at the Rear of the Line

into seatings in the feed drum, which is driven by an f.h.p. motor, through a reduction gearbox. As the drum rotates, the cones are transferred to the chute *P*, down which they roll to the pick-up position at the lower end of the elevator *R*. This elevator is of the standard Timken chain-and-peg design, and the cones, carried upwards on the pegs, are deflected into the chute *S*. As they pass down this chute, the cones are turned through 90 deg., and are delivered to the angularly-disposed band of the distributor unit, at the left, with their large ends downwards.

The guide strip at the lower edge of the conveyor band (with which the cones make contact as they travel along the distributor) incorporates a hinged section, just visible at *T* in Fig. 14. Normally, this section is maintained in line with the remainder of the strip by a counterweight, but if the number of cones that are circulating on the distributor is excessive, their weight deflects the strip,

the hinged section resumes its normal setting, and feeding is resumed.

CONE-FINISHING LINES

Similar operations are performed on each cone-finishing line. Cones are delivered first to one of two Cincinnati No. 1 Microcentric race-grinding machines in each line, on which the conical roller track and the face of the small rib is finished. Each cone is fed from an upper chute on to two work-supports in front of an electro-magnetic driver plate on the work-spindle of the machine. At the




Fig. 14. To Avoid Interlocking of Certain Sizes of Cones, This Hopper and Drum Feeder are Employed for the Storage and Delivery of Cones at the Head of One Finishing Line, in Place of the Usual Spiral Brush Feeder




Fig. 15. One of the Timken-designed Automatic Grinding Machines for Finishing the Ribs at the Large Ends of Cones. Each Cone is Held on a Magnetic Face-plate on the Work-spindle, and, after it has been Ground, Passes Through a De-magnetizing Tunnel in the Outlet Chute

end of the grinding cycle, the cone is deflected into a lower chute, which passes through a de-magnetizing tunnel. By way of this chute, cones are directed to a band conveyor at the rear of the Cincinnati machines, and are delivered to a chain-and-peg elevator, which returns them to the angularly-disposed band conveyor of the distributor unit. Each Cincinnati machine is fitted with automatic control equipment, whereby the abrasive wheel is dressed after 7 to 10 cones have been ground.

The cones pass along the second section of the distributor band, and are deflected into chutes serving three Heald 190 Centrimatic machines for grinding the bores. These chutes differ from the conventional U-section type associated with the Cincinnati machines, and each consists of a side-plate with upper and lower L-shaped strips which embrace the rib at the large end of each cone. Consequently, the cones are fed towards the Heald machines with their large ends in contact with the chute side-plate, and their small ends extending outwards. The Heald machines are fitted with Sizematic gauging equipment, whereby the bore of each cone is checked automatically by means of a plug gauge, and the grinding wheel is dressed during each cycle.

From the Heald machines, the cones are passed back to the distributor, whence they are fed by chute to either of the rib-grinding machines. These machines were designed by British Timken, Ltd., and the second machine of the right-hand line (as viewed in the direction of work flow) is shown in Fig. 15. The delivery chute for cones is indicated at U, and the workpieces roll down to a transfer unit mounted on the work-head of the machine.

This transfer unit is somewhat similar to that fitted to the Timken machine for honing cups. In this instance, however, there is a swinging lever with a plug which enters the bore of the cone at the pick-up position. The arm is then swung downwards, by the action of a hydraulic cylinder, to position the cone in front of the magnetic face-plate on the work-spindle, where it is supported on a pair of rollers.

The wheel-head of the machine, seen at the right in Fig. 15, is fed inwards towards the work-piece by means of a vertically-moving wedge, coupled to the piston rod of a hydraulic cylinder. Initially, the wheel-head is fed inwards at a fast rate until the wheel makes contact with the rib of the cone. Then, as the load on the driving motor increases, the rate of infeed is automatically reduced to that required for the grinding operation proper. When the grinding has been completed, the wheel is rapidly withdrawn, after a pre-determined spark-out period. Next, the transfer arm is moved outwards, and upwards, to pick up the next cone, and the workpiece that has just been ground is thrust into a chute below the work-support rollers.

This chute is bent through an angle of 90 deg., and the bottom member is cut away at the end of the curved portion, so that the cone can fall into the chute V below. By this arrangement, the cone, which was held on the magnetic face-plate with its small-end outwards, passes down the chute V with its small-end inwards. As it rolls down the chute, it passes through a de-magnetizing tunnel W, and thence to a helical portion at the lower end of the chute, whereby it is turned through 90 deg. before it is delivered to the band conveyor at the rear of the machine, with its large-end downwards. From the band conveyor, cones are deflected into a chute X, which leads to the loading position at the bottom of the elevator Y. This unit is of the chain-and-peg type, but, in this instance, the pegs are arranged at 90 deg. to the chain pivot pins. The cones are carried upwards and are delivered to a 4-deck, spiral brush-feeder, at the end of the line, as indicated at e in Fig. 1.

At pre-set intervals, the angle between the rib and the track of a cone is checked by means of an optical projector, and Mercer air gauging equipment is provided for an occasional check of the diameter of the cone bores. Machines, similar to those used for cups, have been designed and developed by British Timken, Ltd., for honing the roller tracks of the cones after the ribs have been ground. These machines are now being built, and should be installed before the end of the year.

From the spiral brush feeder at the end of each finishing line, cones are delivered to a cleaning unit, where they are carried on a belt through jets of distillate. After they have been cleaned, cones are subjected to a 100 per cent visual inspection, similar to that for the cups. Automatic air gauging equipment will shortly be installed, and will provide for measuring the diameter of the bore, the diameter of the roller track, the angle of the roller track, the overall width, and the thickness of the rib on each cone.

After the final inspection stage, the cones from each line are graded for track diameter, using equipment that incorporates a precision indicator gauge, with the dial divided into coloured segments. After being graded, the cones are delivered, in batches of one grade, to a semi-automatic machine, where the rollers and cages are assembled to them, to form complete inner races. Rollers, also graded and batched, are delivered from an adjacent section, which will be considered later, and cages are supplied, as finished products, from the press shop of the main factory. The assembly machines are similar to those used in the main plant, and have been described in *MACHINERY*, 91/420—23/8/57. Rollers are delivered in batches of different grades, and a grade is selected to suit the batch of cones that is

being handled. Inner-race assemblies are passed through a washing unit, and are finally coated with protective grease, by immersion.

As in the cup-finishing section, one group of work-people tend both cone-finishing lines. Face grinding (Rowland machine) and assembly are carried out for one shift per day, and the remaining operations for three shifts. One setter and one operator per shift are responsible for the Rowland and Cincinnati machines, and two setters and two operators per shift tend the Heald and Timken machines. One operator is required for each of the assembly machines.

ROLLER-FINISHING SECTION

At present, two different types of rollers are required for the bearings produced in the N.B. Plant, and they are finished on two parallel lines, one of which is indicated at *f* in Fig. 1. Work flows continuously along the lines, which are equipped with similar machines. The equipment provides for the production of rollers, of each main type, in a number of different grades, or size groups. The size-difference between grades is 0.00025 in. (on body diameter), and rollers are later sorted into half-grades, which differ by 0.000125 in. Rollers are delivered, in bulk, to the finishing section from the main factory, where the earlier operations in the production sequence are performed. These operations include heading, barrelling and hardening, and are carried out on a batch-production




Fig. 16. General View of the Roller-finishing Section of the N.B. Plant. There are Two Parallel Lines Comprising Centreless Grinding, and Spherical-end Grinding Machines, Connected by Rotating-spiral Conveyors

basis, using conventional machines and equipment.

A general view of the roller finishing department is given in Fig. 16, looking from the left-hand end of the lines (as viewed in Fig. 1). Operations start at the opposite end, and, on each line, the first stage consists of rough-grinding the bodies of the rollers on a standard Cincinnati No. 2 centreless machine, equipped with a hopper feed mechanism and a spiral control drum. From 0-008 to 0-010 in. (on diameter) of metal is removed at this stage. From the outlet side of the first machine, the rollers are fed, by chute, to an angularly-disposed, rotating-spiral conveyor, whereby they are delivered to the hopper of a second Cincinnati machine. This machine has equipment similar to that of the first, and provides for semi-finishing the rollers, from 0-004 to 0-005 in. (on diameter) of metal being removed. Next, the rollers are fed by way of a spiral conveyor to a machine on which their large ends are ground to a spherical form. On this machine, which was built in this country to American Timken design, the rollers are carried between spring-loaded rotating plates, whereby their large ends are presented to a cup grinding wheel. Finally, the body of each roller is finish-ground on a Cincinnati No. 2 machine, with similar equipment to that provided for the first two stages, and 0-002 in. (on diameter) of metal is removed. From the last Cincinnati machine, rollers are passed through a washing unit, and are then dried by feeding them through a spiral conveyor, which is electrically heated. From this conveyor, rollers are delivered to the hopper unit of a mechanized inspection station, where they are subjected to a visual check.

MECHANIZED VISUAL INSPECTION

A close-up view of the inspection station is given in Fig. 17. The operator is seated in front of a bench, whereon is mounted a work-support, which incorporates a power-driven inner drum. This drum is rotated in an anti-clockwise direction, through a worm and wheel, and is surrounded by a cage, which is free to rotate. A layshaft is pivoted below the drum, and is driven by a belt from the drum-shaft. This layshaft carries a friction disc, which engages a similar disc mounted on the cage, and drive can thus be transmitted from the drum shaft, through the layshaft, to the cage, the latter then rotating in a clockwise direction. Rotation of the cage can be started and stopped by tilting the layshaft, and a lever is provided, which forms an extension of the shaft, and is controlled by the operator's left hand.

Rollers are fed, from the hopper above the bench, through an escapement mechanism, which



Fig. 17. Rollers are Visually Inspected on a 100 per cent Basis at this Bench Station, which is Provided with Equipment for Rotating the Rollers Continuously and Indexing Each in Turn to the Viewing Position

is actuated by a vertical shaft, oscillated from the drum-driving mechanism. The rollers are delivered, one at a time, down a tube to the left-hand side of the unit, where they enter one of the slots in the cage. The drum and cage are of conical form, and the roller rests in the cage with its small end in contact with the lower end of the slot. Due to the motion of the drum, the roller is continuously rotated at a slow speed, and, by engaging the cage drive, it can be brought to a position under a magnifying lens, which is adjustably mounted on a pillar at one side. The cage-drive is then disengaged, so that the roller rotates slowly in the viewing position. Inspection is facilitated by the bright illumination provided by an overhead fluorescent lamp, and a mirror is adjustably mounted at the rear of the drum, in order that the large end of the roller may be viewed.

When the inspector has satisfied herself that the roller is satisfactory—or has removed it from the cage and placed it in one or other of two bins at the right of the bench if it is faulty—she engages the drive to the cage, to bring the next roller into the viewing position. Rollers that have passed inspection are carried in a clockwise direction, by successive movements of the cage, and when they reach the "3-o'clock" position, fall into a chute at

the right, and thence into a work-pan below the bench.

After visual inspection, rollers are passed, in batches, to one or other of the two Timken-designed grading machines at the end of each line, as seen in the right foreground in Fig. 17. These machines, which are hopper-fed and automatic in operation, are similar to those described in *MACHINERY*, 91/422—23/8/57. The machines segregate the rollers into over- and under-size grades, also into nine intermediate diameter groups, which differ by 0.000125 in. In practice, however, in order to facilitate assembly, rollers are finished-ground to an accuracy such that their diameters rarely lie outside the middle three or four grades. Finally, the graded rollers are washed, stored, and withdrawn, as needed, to meet assembly requirements.

PACKAGING

Assembled inner races—each comprising a cone, cage, and set of rollers—are matched to cups at the packaging station at the end of the cup-finishing line. Complete bearings, or separate matched cups and inner race assemblies, are packed into cylindrical cartons. At present, this work is performed manually, as are the final capping and stamping of the cartons. A packing machine is now in the final stages of development, however, and will be capable of inserting bearings in cartons at a rate of 42 per min. Four of these machines will eventually be installed.

FUTURE DEVELOPMENT

British Timken, Ltd., do not consider that the N.B. plant can ever be regarded as complete, since there are continual developments, whereby old problems can be solved, or improvements can be made. Already, many of the outstanding problems associated with the automatic production of bearings have been solved technically, and the introduction of the necessary new equipment depends solely upon sufficient standardization by bearing users to make such equipment economically justifiable. It is not considered that the degree of mechanization and automatic control in the British plant will approach that in the comparable plant of the American Timken company, since there is less standardization of bearing sizes here than in the U.S.A., British wage rates are lower, and certain machines and items of equipment, which can only be purchased from America, would involve the expenditure of dollars.

Apart from obvious benefits to consumer and manufacturer, which arise from reduced production costs, the N.B. project has many other advantages.

Working conditions in the automatic plant are excellent, and the building is clean, light, and air-conditioned. The accident rate has been reduced to a remarkably low level, since the operators' hands need only be in contact with the mechanisms of the machines during tool change-overs, and manual loading has been completely eliminated. With the introduction of mechanized loading for furnaces and quenching presses, the discomforts associated with working close to heat sources, and in oil fumes, have been minimized, and, in general, all heavy manual work has been eliminated.

It was planned, initially, that as factory employees became more experienced in the working of the lines, and the lines themselves became more stabilized, both operators and supervisors would be circulated from one section to another. This system is now in operation, and not only provides a broad supervisory experience, but also helps to eliminate any boredom among operators, who might otherwise continually be performing repetitive tasks. In these various ways, British Timken are trying to create a factory that is technologically and economically worthwhile, and provides working conditions of the best modern standards.

In the future, the company plan to apply the results of technological developments to the N.B. plant as they become available and economically justifiable. It has already been mentioned, for instance, that it is intended to incorporate automatic final-gauging and inspection machines for some bearing sizes, in the near future. Moreover, the techniques practised, partially or completely, in this factory will be installed elsewhere in the Timken factories, if they are considered suitable. Thus, the experience gained will be applied to the design and construction of similar production lines, whenever the volume of production permits. In this connection, it should be mentioned that the company has recently designed and started to build, a new factory at Daventry, of approximately the same area as the N.B. plant. This new factory will have automatic production lines for the manufacture of those larger Timken tapered roller bearings associated with railway applications, and is planned to be in full production next year.

THE PRODUCTION OF PORTABLE POWER TOOLS in the first quarter of 1957 reached a total value of £4,203,000, of which £1,587,000 was for export. In the second quarter of the year, tools to the value of £4,116,000 were produced, and exports totalled £1,533,000. For comparison, it may be noted that the values for production in the first and second quarters of 1956 were £2,700,000 and £4,164,000, respectively.

The Re-servicing of Carbide Tools

The economic advantages of tungsten carbide tooling can be fully realized only by careful attention to the correct methods of servicing employed at the correct times. In this article, based on material supplied by Wickman, Ltd., are discussed both grinding by conventional methods, and the recently developed spark-erosion process for servicing carbide tools. It includes some recommendations which may prove helpful to those who want to get the best from carbide tooling.

TUNGSTEN CARBIDE STRUCTURE

Tungsten carbide has a granular structure, and, for this reason, the individual grains are liable to chip or flake-off, if pressure or shock is applied when the material is not adequately supported. It is important to bear this fact in mind in connection with the re-servicing of carbide tools, and, when grinding, it must be ensured that the wheel rotates into the tool, as indicated in Fig. 1, and not away from it. Unless this precaution is taken, the grains of carbide on the edge of the tool are unsupported, and may flake-off, leaving irregularities which will result in poor performance.

A tool which has been ground on the periphery of a wheel will have a concave front clearance, and the effective support for the edge will, therefore, be reduced. Then, under cutting pressure, early deterioration of the edge is likely to occur, as will be evident from Fig. 2. Similarly, too much front clearance is liable to result in breakdown of the

cutting edge. For general work, a front clearance of between 4 and 5 deg. has been found satisfactory and will provide adequate support for the edge of the tungsten carbide tip.

GRINDING WHEELS

To ensure efficient re-servicing of carbide tools, it is important that the grinding wheel is of the correct type and grade.

For this purpose, wheels incorporating the following abrasives are employed: silicon carbide, aluminium oxide, and diamond. Grinding wheels have also been made from boron carbide, but, at the present stage of development, this material does not appear to be satisfactory for stock removal, and is more suitable for burnishing operations.

As a matter of interest, it may be noted that silicon carbide and boron carbide are of approximately the same hardness, whereas diamond is nearly four times as hard, and, for this reason, is much more effective than the other abrasives mentioned. On the other hand, it is expensive.

Grinding wheels are made from grains of uniform size, and, in general, the coarser grains ensure more rapid stock removal. However, rapid cutting is achieved at the expense of surface finish, and several successive grinding operations are often performed with wheels of progressively smaller grain size. For polishing, grain sizes of the order of 300 to 400 mesh are commonly employed.

The properties of the bond material, which holds the abrasive grains, have an important influence on the performance of the grinding wheel. It will be apparent that the harder the bond, the more securely will the individual grains be retained. After an abrasive grain has been in operation for some time, the cutting edge becomes dull, and the forces tending to pull the grain




Fig. 1. When Grinding Tungsten Carbide, the Wheel Should Rotate "Into" the Tool, as Here Shown, and not Away from it




Fig. 2. Unless the Carbide Tip is Adequately Supported, the Cutting Edge will Rapidly Deteriorate. (left) Tool with Adequately Supported Tip. (centre) Tool with Too Much Front Clearance. (right) Tool Ground on Periphery of Wheel

out of the bond are then increased. In wheels with a soft bond, the abrasive particles are pulled out when the cutting efficiency has deteriorated only slightly. A soft-bond wheel, therefore, always cuts with sharp edges, so that rapid stock removal can be expected. For the same reason, the life of a soft-bond wheel is relatively short.

A soft-bond wheel, moreover, is much more susceptible to accidental damage and grooving, and such wheels are more suitable for machine grinding operations, where cutting pressures are controlled, than for off-hand grinding.

It is the usual practice to employ metal-bonded wheels for the latter purpose, because they are much less likely to be damaged if an operator inadvertently "digs in" the point of a tool. Because these wheels retain the abrasive grits until they have lost much of their efficiency, cutting tends to be slow, but the "life" is greater than for soft-bond wheels.

So long as the edge of the abrasive grains remain sharp, they will cut without inducing excessive heat in the work. Tungsten carbide is, however, so hard that the edges of the abrasive particles are dulled fairly rapidly, and, unless the wheel is re-dressed at frequent intervals, undue heating will occur and hair-line cracks may develop in the tip. Such overheating is more liable to occur if the bond is too hard, and the cutting surface of a wheel which has become glazed, as the result of grinding tungsten carbide, is seen on the left in Fig. 3. A wheel in this condition requires to be re-dressed to expose new and sharp abrasive particles. In contrast, the surface of a wheel in good condition is seen on the right.

DIAMOND WHEELS

The extreme hardness of diamond makes it particularly suitable for grinding tungsten carbide, and diamond particles, held by a suitable bonding

material, are made into various forms of wheels for this purpose. Diamond is expensive, and for this reason the grinding wheels are made up in such a manner that the diamond particles are concentrated in a rim or layer, and are not distributed throughout the body, as in silicon carbide or aluminium oxide wheels.

Grit sizes are chosen in the same manner as for ordinary grinding wheels, and the following are representative of those employed in the manufacture of diamond wheels suitable for re-servicing carbide tools:—

Coarse	85/100 (fast stock removal)
Medium	120/240
Fine	140/300
Superfine	400 (slow cutting, but good surface finish)

Diamond wheels are available commercially with bonds of different hardness. For the softest types of wheels, synthetic resins are employed, and for the harder types, metals such as bronze, cast iron, or steel. Resin-bonded diamond wheels are




Fig. 3. Photomicrographs of a Wheel Surface with Dulled Cutting Edges (left) and in Good Condition (right)

generally recommended for machine grinding, and metal-bonded wheels for off-hand grinding. Some users, however, employ resin wheels for off-hand work, on account of their rapid cutting and good surface-finishing properties, and rely upon well-trained and experienced operators to avoid accidental damage.

A further characteristic of diamond wheels is concentration, which indicates the weight of diamond contained in a unit volume of the abrasive rim. Concentration is usually designated as follows:—high or 100, normal or 50, and low or 25.

Concentration of a diamond wheel is also related to the number of cutting points. High concentration wheels, with the greatest number of cutting points, therefore, obtain faster cutting than those of low or normal concentration.

OFF-HAND GRINDING

In off-hand grinding, the operator holds the tool against the wheel with manual pressure, and, normally, moves it so that the face to be ground is passed to and fro across the wheel surface. Off-hand grinding machines are available, however, on which the wheel oscillates relative to the worktable. With this type of machine, it is claimed, the full width of the diamond wheel face is em-

ployed, so that long life is ensured, and less operator skill is required, since the tool has only to be pressed on to the table and pushed against the wheel. A prototype Neven GF2 Mark V machine, with an oscillating wheel-head, is shown in Fig. 4.

Off-hand grinding is widely used for tool reconditioning in the engineering industry, and is suitable for many types of tools where extreme accuracy is not required. Many machines are available which have been specially designed for this form of grinding, and an adjustable worktable is usually provided, which can be set and locked at the required angles for grinding the faces of the tool. There is also an adjustment whereby the table can be advanced towards the face of the wheel to compensate for wear.

It is important that the spindle of an off-hand grinding machine should be of generous dimensions, and free from vibration, run-out, or end play. If these defects are present, uneven wear of the grinding wheel is inevitable. There may be provision for reversing the direction of rotation, so that both right- and left-hand tools can be processed on the same wheel.

Normally, a copious flow of coolant is directed over the tool and wheel during grinding, so as to prevent over-heating, and off-hand grinding machines, a typical example of which is shown in Fig. 5, normally are equipped with coolant tanks and pumps to ensure an adequate delivery. An intermittent supply of coolant is extremely undesirable, as the alternative heating and cooling of the tool tip is likely to result in cracking. It is preferable to grind dry than with an insufficient or interrupted flow of coolant.

To obtain optimum performance, and to ensure maximum economy in re-servicing operations, a carbide tool should be sharpened when the wear land on the tip reaches a width of 0.015 to 0.020 in. It may, of course, be necessary to re-service a tool before this amount of wear has occurred if it has become chipped or cratered.

Provided that a tool is withdrawn from service before excessive wear has taken place, cracking of the carbide can generally be avoided, and the cutting edge can be restored by using a "green grit" silicon carbide wheel of medium/hard bond, or, alternatively, a metal-bonded diamond wheel.

In cases where, because of the presence of cracks in the carbide tip, there is a considerable amount of material to be removed before the tool can be put back into service, a soft "green grit" wheel is used for removing the bulk of the material, and the tool is finished with a silicon carbide wheel of harder grade, or with a diamond wheel.




Fig. 4. Prototype Neven GF2 Mark V Grinding Machine, with Oscillating Wheel-head, for Carbide Tools




Fig. 5. A Typical Off-hand Grinding Machine for Carbide Tools

During off-hand grinding, the tool should not be pressed too hard against the wheel, as this may cause overheating, with the attendant danger of crack formation in the carbide tip. To avoid any tendency for the wheel to become grooved, the tool should be passed right across the face.

SEQUENCE OF OPERATIONS FOR OFF-HAND GRINDING

ROUGH GRINDING. For the purpose of explanation, the complete sequence of operations, from preliminary rough grinding to final lapping, will be described.

At the preliminary rough-grinding stage, the required cutting rake, on the top surface of the tip, is rough ground. Normally, this operation should be avoided in re-servicing, in order to preserve the overall depth of the tool. Chipped or broken cutting edges are usually cleaned up during the rough grinding of the side and front clearances.

Next, the secondary front and side angles on the steel shank are ground with an aluminium oxide wheel. These angles should be 2 to 4 deg. greater than the clearance angles required on the tip, to ensure that the shank does not contact the silicon carbide wheel subsequently employed for grinding the tip. Thus, if the tool is to be ground to give a 4 deg. primary clearance, the machine should be set at 6 to 8 deg. for grinding the secondary clearance.

The front clearance on the tip now is ground, using a soft-bond silicon carbide wheel, and, then, the primary side clearance. If a nose radius is required, it should be ground on the same wheel.

FINISH GRINDING. For the finish-grinding operations which follow, a slightly harder bond, silicon carbide wheel is used. Alternatively, the tool may be finish lapped on a metal-bonded diamond wheel.

Provided that tools are withdrawn from service at the correct time, finish grinding or lapping is all that is required to re-sharpen them for further use. The sequence is the same as for rough grinding, namely: grind cutting rake; grind front clearance; and grind nose radius, if required. In connection with the cutting rake, the previous remarks apply. It is not necessary to grind the secondary clearance again. Once more, it is emphasized that for all carbide grinding operations, and particularly off-hand grinding, the lightest possible pressure should be used.

GRINDING PRIMARY RAKE. The provision of primary and secondary cutting rakes is proving extremely successful as a means of improving carbide tool performance. When employing a tool with a negative cutting rake, a secondary positive rake can be applied to relieve chip pressure. The required cutting rake is then left as a negative primary land, as indicated in Fig. 6, and its width is normally three to four times the feed.

MODIFYING STANDARD TOOLS BY OFF-HAND GRINDING

For certain operations, tools may be wanted with shapes that are not included in the standard range, or a tool may be needed urgently with a standard shape which is not carried in stock. In such




Fig. 6. Diagram Showing a Tool with Negative Primary Land




Fig. 7. A Tool which has been Badly Chipped or Broken Can Often be Reclaimed by Grinding to a Different Shape

cases, it is usually possible to modify an available tool to obtain the shape required. Tools which have become badly chipped or broken in service, moreover, can usually be reclaimed by grinding them to a different shape, as seen in Fig. 7.

When a special shape is needed, a tool should be selected which can be modified with the least amount of grinding and wastage of carbide. In this connection, it should be remembered, for example, that an approach angle need only be of sufficient length to accommodate the depth at which it is proposed to cut.

Some modifications, such as alterations to cutting rake, plan-approach or plan-trail angles, or clearances, are performed by off-hand grinding, in the manner already described.

If a large amount of material must be removed, the operation should be performed in stages, as indicated in Fig. 8, so that a single face of the tool is not subjected to continual grinding and consequent excessive heating. It is necessary to relieve the shank material with an aluminium oxide wheel when a tool shape is being modified by grinding.

MACHINE GRINDING

Whereas off-hand grinding can be employed for re-servicing tools where accuracy of form is relatively unimportant, the method is not suitable if geometric accuracy of tool form must be maintained. For such operations, control of relative movement between the tool and the grinding wheel is essential.

Form tools are normally re-serviced on tool and cutter grinders, and sometimes on profile grinders. In many respects, machine grinding is ideal for re-servicing carbide tools, since the whole operation is under strict control. The rate at which the tool is traversed over the face of the wheel does not vary from one pass to another, and the amount of in-feed of the wheel is always the same.

used without the fear of damage, and their rapid cutting properties can be exploited fully. Despite these advantages, the setting-up time for machine




Fig. 8. If a Large Amount of Material Must be Removed, the Operation Should be Performed in Stages, as Indicated




Fig. 9. Form Tool with Concave Radius Produced from a Standard Bar Turning Tool




Fig. 10. (left) Set-up for Grinding the Concave Form Tool. Fig. 11. (centre) Method of Rough Grinding. Fig. 12. (right) The Tool is Finished with a Formed Wheel

grinding is not warranted for simple turning tools, for which the off-hand process gives quite satisfactory results.

MODIFYING TOOLS BY MACHINE GRINDING

When complex modifications to standard tools are required, it may be necessary to perform the operations on a tool and cutter grinder, surface grinder, or profile grinder.

The form tool shown in Fig. 9, which has a concave radius, is produced from a standard bar turning tool, on a tool and cutter grinding machine. In this instance, it is not possible to relieve the shank material with an aluminium oxide wheel, so that both shank and tip must be ground together. For this operation, the tool is held in a universal vice set to give the desired clearance angles. As previously mentioned, the direction of wheel rotation must be such that it grinds into the cutting edge of the tool, as indicated in Fig. 10, in order to prevent slight flaking of the carbide.

Grinding is carried out downwards and outwards, as shown in Fig. 11. This procedure reduces the rate of wheel wear, which is usually very high for such operations, and the wheel is not form dressed until the tool is approaching the final shape.

If an accurate form is required, the wheel must be shaped with a radius attachment, but where the limits for form permit, it may be dressed by hand, using a Carborundum stick. It is sometimes advisable, when form grinding, to employ a slightly harder grade of wheel for the finishing cuts, so that the rate of wheel wear is reduced. Fig 12 shows the formed wheel in use.

Another example, indicating the methods employed for modifying standard bar tools by machine grinding, will now be considered. In this case, a bar tool is to be modified to form a parting and chamfering tool, as in Fig. 13, and the sequence of operations is as follows: (1) The tool is set in a universal vice, so that the required clearance angles are obtained (Fig. 14), and an aluminium oxide wheel is employed initially. (2) Grinding is performed, downwards and outwards, with an unformed silicon carbide wheel, until the point is reached at which the radius is to be produced at the neck of the tool. (3) After the radius has been formed on the wheel, as previously described, finish grinding is carried out (Fig. 15). (4) The tool is re-set in the vice, for grinding the opposite side, and the same procedure is followed, the chamfer finally being produced with a formed wheel




Fig. 13. Bar Tool Modified to Form a Parting and Chamfering Tool




Fig. 14. (left) The Tool is Set in a Vice at the Required Clearance Angles. Fig. 15. (centre) The Radius is Finished with a Formed Wheel. Fig. 16. (right) The Chamfer is Ground with a Formed Wheel

(Fig. 16). (5) Then, it remains only to grind the front clearance, and this is done by the off-hand method (Fig. 17).

GRINDING MULTI-TOOTH TOOLS

In the preceding sections of this article, the re-servicing techniques for bar-type turning tools have been considered. The grinding procedure for reamers, milling cutters, and similar end-cutting tools will now be described. Such tools are always re-serviced on tool and cutter grinders, and resin-bonded diamond wheels are recommended for this class of work.

END MILLS. In Fig. 18 is shown a spiral end mill, mounted between centres on a tool and cutter grinder. The tool is prevented from turning by a spring-loaded finger, attached to the wheelhead. With a tooth of the tool resting on the finger, the table is raised to obtain the desired clearance, the machine is set to remove between 0.0005 and 0.001 in. per pass, and the spiral flute is kept in contact with the spring-loaded finger while grinding is in progress. The same procedure is followed for each tooth on the tool.

Then, it is necessary to grind the end cutting edges of the tool, and, for this operation, the spring-loaded finger is attached to the work table as can be seen in Fig. 19. The workhead of the machine is tilted to give the required end clearance angle, and each tooth is ground until all evidence of wear has been removed.

MILLING CUTTERS. When a milling cutter is ground, it should be indexed, from blade to blade,

against a spring-loaded plunger. Small equal amounts of material should be ground from each blade, until all have been re-sharpened, and the cutter should then be checked for concentricity.

The procedure is as follows:—(1) For grinding the faces of the blades (Fig. 20) the cutter is mounted on the workhead of the machine, with the face to be ground parallel to the face of the lapping wheel. (2) Next, the peripheral surfaces are ground, with the spring finger attached to the




Fig. 17. The Front Clearance is Ground by the Off-hand Method




Fig. 18. (left) Spiral End Mill Mounted Between Centres on a Tool and Cutter Grinder

Fig. 19. (right) Set-up for Grinding the End Cutting Edges

wheel head, as shown in Fig. 21. The desired clearance is obtained by adjusting the table height. (3) The spring finger is attached to the workhead, as shown in Fig. 22, when grinding the side face. The clearance angle is obtained by tilting the table of the machine. (4) Finally, the chamfer is ground (Fig. 23). For this purpose, the spring finger is attached to the table of the machine, which is adjusted to give the required clearance. The workhead is then rotated through 45 deg., and the chamfers ground to the specified width.

FACE MILLING CUTTERS. The following method is used for re-servicing face milling cutters:—With

the workhead set at the required helix angle and radial rake, the faces of the blades are lapped in turn (Fig. 24). Next, the workhead is swung over to the required bevel angle, and the finger, which is attached to the head, is adjusted to obtain the required clearance. With this setting, the bevel angle on each blade is lapped in turn (Fig. 25). Then, with the workhead at 45 deg., the finger attached to the head, and the cutter at the required clearance angle, the chamfer on each blade is lapped (Fig. 26).





Finally, the workhead is set at 90 deg. less the amount required to give in-rake or dish, with the

Fig. 20. (top left) Grinding the Face of a Milling Cutter Blade

Fig. 21. (top right) Grinding the Peripheral Surface

Fig. 22. (bottom left) Grinding the Side Face

Fig. 23. (bottom right) Grinding the Chamfer









Fig. 24. (top left) Set-up for Lapping the Front Surface of a Face Milling Cutter Blade

Fig. 25. (top right) Lapping the Bevel Angle

Fig. 26. (bottom left) Lapping the Chamfer

Fig. 27. (bottom right) Lapping the Blade Clearance

cutter tilted to the required angle, and the blade clearance is lapped (Fig. 27).

CHIP BREAKERS

Most metals possess characteristics which result in the production of a continuous chip during machining. For ease of disposal, and to protect the operator from injury, the continuous chip must either be curled, or broken into short lengths. Chip breaking can sometimes be ensured by increasing the feed to obtain an increase in cross-sectional

area (feed \times depth of cut). Alternatively, a chip breaker may be formed or ground in the tool tip. Chip-breaker widths are varied, depending upon the feed and depth of cut, and some typical forms are shown in Fig. 28.

Where extreme difficulties are experienced in breaking the chips, various methods of chip-flow control can be adopted, and involve the provision of deeper and wider grooves than those associated with chip breakers, with blending radii or inclined step faces. These grooves are known as chip curlers.

As so many variables, including degree of duc-




Fig. 28. Some Typical Chip-breaker Forms. The Dimension W Depends on the Feed and Depth of Cut

tility, feed, speed, depth of cut, and diameter of workpiece are involved, the correct form in any particular instance can only be determined by practical trials.

Chip breakers, or curlers, can be ground on conventional machines which have provision for correct angular setting of the tool. Alternatively, special chip-breaker grinding machines are available. Special metal-bonded wheels are recommended for grinding chip-breaker grooves in tools, but the operation can also be carried out with a resin-bonded peripheral-type wheel.

RE-SERVICING TOOLS BY SPARK-EROSION

The spark-erosion method of machining is comparatively new, and is not so well known as the long-established grinding techniques. With this process, metal is removed by means of an electrical spark discharge which occurs between an electrode and the work. Although the mechanics of metal removal by this method are beyond the scope of this article, it may be noted that it is now firmly established as a production process. Spark-erosion is employed for a variety of operations involving hard metals, where normal machining would be difficult or impossible. Typical applications of the process include the reconditioning of extrusion dies, and the machining of intricate shapes in carbide and other hard materials.

A feature of the electro-erosion process is that the work and electrode are not in physical contact, as there is always a spark gap between them. This gap is filled with a suitable dielectric fluid, through which the spark discharge takes place. If the electrode and workpiece touch, there is a short circuit, no sparking can occur, and no metal removal takes place.

The equipment used for re-servicing carbide tools by the spark-erosion process closely resembles a conventional off-hand grinding machine, but the wheel is replaced by a circular electrode, made from cast iron. Suitable electrical gear is incorporated in the machine, the output from which serves to energize the rotating circular electrode. Provision is also made for directing a copious flow of dielectric fluid over the face of the electrode, and over the tool. The Wickman Erodosharp Mark II machine is shown in Fig. 29.

Tool sharpening with this equipment is also similar to conventional grinding. As sparking occurs, material is removed from the tool. Some metal is also removed from the electrode, but the quantity is very small, so that the life of an electrode is considerable. Experience has shown that, under average conditions, an electrode life of 8,000/10,000



Fig. 29. Wickman Erodosharp Mark II Machine for Re-servicing Carbide Tools by Spark Erosion

tools is obtained. If the majority of tools processed require the removal of large amounts of stock, the electrode life is reduced to some 5,000 tools.

A further advantage of spark-erosion as a method of re-servicing carbide tools is that no heat is generated in the tool material during processing, so that the danger of cracks being formed in the tip, due to thermal shock, is eliminated. Because there is no physical contact between the tool and the electrode, moreover, problems of "wheel loading" do not arise. It is possible, therefore, to remove metal from both tip and shank simultaneously, and the need for two operations, as in grinding, is avoided.

SURFACE FINISH AND CUTTING EDGE

The surface finish produced by the spark-erosion process is of a different character from that associated with more conventional machining methods. With spark-erosion, numerous small saucer-shaped depressions are formed, with a depth of approximately one third the diameter of the associated sphere. This type of surface is shown diagrammatically at the top in Fig. 30. Enlarged photographs of an eroded surface and one produced by normal grinding methods are also illustrated in Fig. 30. The eroded surface is dull and non-




Fig. 30. (top) Diagram of Surface Produced by Spark Erosion. (centre) Photomicrograph (25 \times) of Coarse Spark-eroded Surface. (bottom) Photomicrograph (25 \times) of Surface Produced by Normal Grinding

reflective, and resembles a fine shot-blast finish. On account of this unconventional matt finish, doubts have been expressed as to the suitability of the spark-erosion process for re-servicing carbide tools. Results which have been achieved with eroded tools, both in this country and in the United States, however, have clearly established the fact that spark-erosion is a sound and practical process.

Since the degree of roughness on an eroded workpiece depends upon the intensity of the spark discharge, it is possible to control the surface quality. Heavy discharges result in rapid metal-removal, but the surface finish produced is rough, and the converse also applies. In consequence,

a spark-erosion, tool re-servicing machine is provided with a selector switch to alter the intensity of the spark discharge, so that it is possible to remove the bulk of the material rapidly at the "coarse" setting, and to obtain the final finish with a "fine" setting, which gives a spark of lower intensity.

Considerable caution is necessary in making comparisons of the surface-finish readings for eroded and conventionally-processed surfaces. It is possible, for example, for the tracer needle of a surface-analyzing unit to bridge a deep, hair-line crack, so that a misleadingly low centre-line-average figure is obtained. The presence of such hair-line cracks is not of major importance on the flat surfaces of tools, but they may cause crumbling at the cutting edge of the tool, with consequent deterioration of performance.

This point will be appreciated better if reference is made to Fig. 31, in which are shown magnified portions of two cutting tools processed by




Fig. 31. (top) Photomicrograph (50 \times) of the Cutting Edge of a Conventionally Ground Tool (Surface Finish, 20 micro-inches, C.L.A.). (bottom) Photomicrograph (50 \times) of the Cutting Edge of a Tool Sharpened by Spark Erosion (Surface Finish, 50 micro-inches, C.L.A.)

conventional means and by spark-erosion. It will be seen that the conventionally-ground tool has several irregularities on the cutting edge, whereas the eroded tool shows a more uniform edge. The centre-line-average surface readings for these two surfaces, it may be noted, are 20 and 50 micro-inches respectively.

For machining operations involving coarse feeds—for example, planing—an eroded tool will be found satisfactory, but for fine feeds, up to about 0.010 in., it may be desirable to re-service tools by both spark-erosion and diamond-lapping methods. The bulk of the material can be removed by erosion, and careful diamond lapping with a fine, or superfine, grit wheel can then be carried out, to obtain a highly-polished land adjacent to the cutting edge.

The examples in the accompanying table indicate that, in general, the spark-erosion process can be utilized for tool re-servicing, with results which are equal to, or better than, those obtained by conventional grinding.

CONCLUSIONS

(1) In view of the high cost of diamond wheels, any steps taken to reduce the wear and tear on such wheels will result in appreciable savings.

(2) For work involving feeds in excess of 0.010 in., the surface finish and the cutting edge produced by spark-erosion methods are satisfactory, without subsequent diamond lapping. To use diamond wheels in these circumstances is wasteful, and, if spark-erosion is adopted, it may be possible to achieve savings.

(3) For work involving feeds below 0.010 in., a diamond-lapped tool is normally desirable. When re-servicing such tools, economies can be effected by first employing the spark-erosion process for removing the bulk of the material, with subsequent diamond lapping to produce a land adjacent to the cutting edge of the tool. In this way, diamond consumption can be reduced to a minimum.

(4) The time required for "grinding" by spark-erosion is somewhat longer than for conventional methods. This drawback is off-set, however, by the fact that "grinding" can be carried out continuously, without the danger of overheating. In addition, since the shank and tip can be ground simultaneously, only one operation is needed, whereas two are required with normal grinding.

(5) The replacement cost of a spark-erosion electrode is low—about one-twelfth of that of a diamond wheel—and it has a long life.

Thus, it will be evident that whereas the spark-erosion process cannot be regarded as superseding

EXAMPLES OF RESULTS OBTAINED WITH GROUND AND SPARK-ERODED TOOLS


Component	Operation	No. of pieces produced	
		Conventional ground tool	Spark eroded tool
Cast-iron flywheel	Rough facing	305	404
Steel gear-shaft	Rough turning	75	80
Steel plate	Milling	510	550
Cast-iron camshaft	Facing ends	325	575
Flywheel ring gear	Finish turning inside diameter	170	170
Cast-iron flywheel	Rough facing	287	365

diamond lapping, by employing the two methods in combination, savings in diamond wheel costs can be made.

New Progress Machine Vices

A new range of Progress machine vices, one of which is shown in the figure, has been introduced by B. Elliott & Co., Ltd., Victoria Works, Willesden, London, N.W.10.

The subject of a patent application, these vices have detachable swivel bases, and are made in four sizes, which will accommodate workpieces up to 2, 3½, 5 and 6½ in. thick. They are available with 3-, 4½- and 6-in. wide by 1½-, 1½- and 2½-in. deep jaws. The moving jaw slides on flat guide-ways, which extend for its full width, so that a large area is provided for supporting the work. The design is such as to obviate risk of the jaw being lifted from the guiding surfaces when clamping pressure is applied. Graduations are provided on a bevelled portion of the swivel base.



An Example from the New Range of Progress Machine Vices

New Burnerd Multisize Collet Chuck

The Multisize collet chuck shown in Fig. 1, has been introduced recently by F. Burnerd & Co., Ltd., 5 Balfour Place, London, W.1. It is intended for use with a range of patent collets of entirely new design, one of which is seen in Fig. 2.

With this design of collet, the work is gripped by a number of narrow, wedge-shaped blades, which can be moved radially in equally-spaced slots. An important feature of the arrangement is that a uniform gripping pressure is applied, over the entire length of the blades, to workpieces with diameter variations of as much as $\frac{1}{8}$ in. A total of only 11 collets is provided for gripping all diameters from $\frac{1}{8}$ to $1\frac{1}{2}$ in. Collets of other sizes will be available shortly.

Either six or eight blades are incorporated, depending on the size of the collet, and their inclined outer edges are held in contact with a taper bore in the body of the chuck by torsion springs. Axial movement of the collet, for gripping the work, is effected by the action between an internally-threaded ring and a sleeve with an internal flange at the nose end. This sleeve surrounds a reduced-diameter portion of the body, and is prevented from rotating by means of a key. A cross-hole is provided in the body to take a chuck key, which meshes with gear teeth of the collet. The ring turns on steel balls, which at the rear end of the ring for opening and closing engage tracks in the bore and on the chuck body,




Fig. 1. Burnerd Multisize Collet Chuck





Fig. 2. One of the New Burnerd Collets for Use with the Multisize Chuck Shown in Fig. 1

and, in addition, serve to prevent axial movement.

The gripping pressure applied to the work enables heavy cuts to be taken without risk of slip or vibration, and it is stated that concentricity of the piece within 0.0005 in. is obtainable at a distance of 4 in. from the nose end of the collet. An adjustable end-stop for the work is available, which takes the form of a disc fitted with a central bolt and a locking screw. Spring-loaded balls are provided round the periphery of the disc which engage with an internal recess in the body of the chuck, and thus provide for endwise location.

The body is available in different designs, one of which has a flange, at the rear end, whereby the chuck can be mounted on a faceplate, for example. Alternatively, chucks can be provided for mounting on lathe spindles with American type A1, type D1 cam lock and type L long taper noses.

ELECTRICITY GENERATED FOR PUBLIC SUPPLY and sent out during October last totalled 7,603 million kilowatt hours, as compared with 7,205 million and 6,598 million in October, 1956 and 1955 respectively. The simultaneous maximum load during the month was 17,376 megawatts, as against 17,347 and 16,059 for the earlier periods. At the end of October installed capacity amounted to 25,861 megawatts, whereas the corresponding figure for the end of 1952 was 17,740.



Typical Operations on Components for Piatti Motor Scooters

Methods Employed by Cyclemaster, Ltd.

The Piatti all-British motor scooter is being produced by Cyclemaster, Ltd., at Byfleet, Surrey, in a modern factory, equipped with plant specially installed for the purpose. The factory is a self-contained organization, comprising administrative offices, design department, production and assembly shops, despatch bay, stores, and service depot.

Certain parts of the Piatti scooter, notably the ignition equipment, pressed steel body shell, and road wheels, are obtained from outside sources, but the engine, gearbox and final drive sub-assembly, and front suspension unit are produced within the works. The integral engine and transmission unit is mounted in the body shell at three points, of which the front two, provided with Silentbloc bushes, are located behind the engine cylinder. The third mounting point is connected to an abutment at the rear of the frame, through the rear spring. This mounting arrangement offers several advantages, and enables the entire propulsion unit to be attached to, or released from, the body. The latter, it may be noted, is a rigid pressed steel shell, internally stiffened by cross members and gussets, the whole forming a stable structure, to which various sub-assemblies are attached.

Measuring 55 in. long by 24½ in. wide, this motor scooter weighs 180 lb., and has a maximum road speed of 45 m.p.h. Power is provided by a single-cylinder, air-cooled, horizontally-mounted 2-stroke petrol engine, with crankcase compression, which develops 4.75 b.h.p. at 4,750 r.p.m. Of

2 per cent nickel iron, the cylinder has a bore of 51 mm., and is secured to a light-alloy crankcase by four studs. It has a detachable head, made from light alloy, and the split-skirt piston, of aluminium silicon alloy, is fitted with two compression rings, the upper ring being chromium plated. The bosses of the H-section connecting rod are bored and ground, to accommodate a cage-type needle roller bearing for the large end and a wrapped phosphor-bronze bush for the small end, and a gudgeon pin of ample dimensions is located in the piston by two circlips.

Some of the operations performed in the production of the final drive spindle, also the crankshaft, which is machined to close tolerances from a forging in En. 8 D steel, are described in this article. Set-ups for machining the crankcase casting, cylinder, and front-suspension swinging arm are also discussed.

PRODUCTION OF THE FINAL DRIVE SPINDLE

In Fig. 1 are shown the principal dimensions and tolerances of the final drive spindle, which is machined from 1½-in. diameter En. 24 bright steel bar. The spindle blanks are produced to length, and centred and faced at one end, on a Wickman automatic, and are centred at the opposite end on a capstan lathe. Next, turning operations are carried out, in two stages, on a Drummond Maximor multi-tool lathe, equipped with front and rear tool slides, the layout for the first stage being




Fig. 1. The Final Drive Spindle in Elevation and Section

shown in Fig. 2. With the work gripped in a driver, four diameters of 20-650 mm., 22mm., 29.5 mm. and 30 mm. are turned, with four tools held in a block on the front slide, at a spindle speed of 708 r.p.m. Each of the diameters turned with this set-up is 0.010-0.012 in. greater than the final size, to allow for subsequent finishing on a Newall type L plain-grinding machine. The 20-deg. taper on the spindle and the undercut are produced by two form tools, held in a box on the rear slide, which are fed in to depth when the turning cuts with the front tools have been completed. All tools employed at this set-up, and for the subsequent turning stages, are tungsten-carbide-tipped.

In preparation for the next multi-

tool turning operation, the opposite end of the spindle is broken down to a diameter of $\frac{1}{2}$ in., over a length of 2½ in., on a Maximinor lathe. The work is again gripped by a driver, and the cut is completed with a single tool on the front slide, in 72 sec. at a work speed of 708 r.p.m. Subsequently, the three diameter steps on the reduced portion of the shaft are turned, also on a Maximinor lathe. Three single-point tools on the front slide produce the 16-mm. diameter at the end of the component, on which a thread is later rolled, also the 19-mm. and 20-mm. diameters. On the 16-mm. diameter, it may be noted, a tolerance of 0.0015 in. is held. In addition, there are three tools on the rear slide which serve to produce a 45-deg. chamfer at the end of the spindle, an undercut between the second and third diameter steps, and a shoulder leading up to the largest diameter. At this set-up, it may be pointed out, the work is held in a driver, as before, and is located endwise against a stop, through which protrudes the point of a spring-loaded headstock centre. The time for this operation is 45 sec.

Both the 16-mm. by 1.5-mm. pitch thread at the end of the spindle, and the 48 serrations (to B.S. A19) on the adjoining portion, are produced on a Steidle No. 1 thread rolling machine.

Using tooling supplied by the makers, a Herbert 2D capstan lathe is employed for drilling and reaming a stepped hole along the axis of the spindle, which is held in a 7½-in., 3-jaw, air-operated chuck. A standard length $\frac{3}{8}$ -in. diameter drill, a $\frac{1}{2}$ -in. by 9½-in. drill, and a $\frac{3}{4}$ -in. by 10½-in. drill provide for removing the bulk of the metal. The bore is then sized over a distance of 98.5 mm.




Fig. 2. Tool Layout on a Drummond Maximinor Lathe for the First Turning Operation on the Final Drive Spindles




Fig. 3. Centec 3R Production Milling Machine Set Up for Producing Slots in Opposite Sides of the Final Drive Spindle

with a semi-finish reamer and a Coventry expanding reamer. Finally, the outer portion of the reamed bore, over a distance of 39.63 mm., is opened out to a diameter of 15.08 mm., and is checked by means of a special double-ended plug gauge. The complete drilling and reaming sequence occupies 5 min. 12 sec.

The 8.2-mm. wide, opposed slots in the spindle are produced on the Centec 3R production milling machine seen in Fig. 3. On this machine, the work is held at one end in a Centec air-operated indexing head, and the other end is supported by a tailstock centre. The automatic working cycle, which is initiated by the operator, is controlled hydraulically. A Clarkson end-mill of special size is employed, and the head descends rapidly until the tool is about to start cutting, at which point the feed rate is engaged. The end-mill is plunged into the work until it breaks through into the bore. Next, the down feed is interrupted, and the longitudinal table traverse is engaged to mill the slot to length. At the completion of this stage, a stop on the front of the table trips a micro-switch, and the head is returned to the starting position. Then, the operator indexes the work through 180 deg., by means of the pneumatic head, to present the other side

for slotting, and starts the automatic working cycle again. With this set-up, slots are cut in ten spindles per hour.

A square end, with radii of 1.5 mm. in the two corners, is produced at one extremity of the slot by a broaching operation, which is performed on an Edgwick machine, with tools supplied by Coventry Tool & Gauge Co., Ltd. The limits on the broached form are ± 0.1 mm.

Burrs and roughness are then removed from the slot by hand, preparatory to heat treatment, during which the part is first generally hardened and tempered to 32/36 Rockwell C, and subsequently hardened to 58 ± 2 Rockwell C, over specified zones, with high-frequency induction equipment. Then, the spindles are inspected, and random samples are sectioned lengthwise, and the exposed surfaces etched to reveal grain structure. After the four diameters and a shoulder have been ground on the Newall machine, Solex external air-gauging equipment is employed for checking the 20.65-mm. and 30-mm. portions, which are held to close tolerances. The two other diameters are checked with adjustable gap gauges. Finally, the spindles are deburred, polished, and washed.

OPERATIONS ON THE CRANKSHAFT

The crankshaft is machined from an En. 8D steel forging to the dimensions shown in Fig. 4. It is inspected for flaws before being passed to a Herbert milling machine, equipped with a Centec air-operated vice, on which it is faced to length. Next, the larger end of the component is spotfaced and centred, and the opposite end is faced on a Herbert No. 4 capstan lathe, in 45 and 60 sec., respectively. For turning and facing the balance weight, and producing a chamfer at the junction of the two surfaces, a Drummond Maximinor lathe is employed. The outside of the web is turned with a single front tool, and two rear tools are fed in to face the side of the web and produce the chamfer. For this operation, the work is rotated at a comparatively low speed, and Stellite-tipped tools are used to withstand the interrupted cutting. The floor-to-floor time is 126 sec.

With a tool mounted on the front slide of a Maximinor lathe, the spindle portion of the crankshaft then is reduced from the rough forged size to a diameter of $\frac{1}{8}$ in., over a length of 3 $\frac{1}{8}$ in. from the smaller end of the component. A second tool is brought into operation, shortly before the end of the traverse, to bring the end of the shaft to a diameter 0.020 in. above the size required for subsequent threading.

At a further set-up on a Maximinor lathe, with front and rear tooling, the remainder of the turning




Fig. 4. A View of the Crankshaft, Showing the Principal Dimensions

on the long part of the shaft is completed in a floor-to-floor time of 81 sec. The front tools provide for turning eight diameters and one taper during a single traverse. Taper turning is controlled by a former plate and follower, the tool being mounted in a separate slide. The rear slide is equipped with six tools to produce five undercuts and one chamfer.

A Herbert No. 4 capstan lathe, which is provided with a throw fixture, is employed for turning, facing and undercutting the eccentric pin; facing the end of the balance weight; and drilling and tapping an 8-mm. by 1.25-mm. pitch hole in the eccentric pin. An allowance of 0.010 in. on the eccentric pin diameter is left for subsequent finish turning. The 3-mm. wide by 1.8-mm. deep slot across the end of the eccentric pin, and a 3-mm. wide Woodruff keyway in the tapered portion of the shaft, are both milled on a Centec 3R production machine.

Oil grooves are formed on two bearing surfaces by a rolling process on the Steidle No. 1 thread rolling machine mentioned earlier. In Fig. 5, a crankshaft is seen in position between the forming and support rolls, where it is held between centres in a fixture which permits rapid loading and unloading. By this method, batches of crankshafts are grooved quickly and accurately, in an average time per piece of 23 sec. Other rolls are fitted, as necessary, to produce thread forms of 19.5 mm. by 1 mm. pitch, and 10 mm. by 1 mm. pitch, on the component, as indicated in Fig. 4. The grooving

rolls seen in Fig. 5 have already produced many thousands of grooves of the correct form without noticeable wear.

Next to the 19.5 mm. diameter by 1-mm. pitch thread, there are 48 serrations, which are cut on a root diameter of 0.777 in. The general form of these serrations is indicated in the enlarged view in Fig. 4, and to ensure that

they are accurately centred with the axis of the crankshaft, they are cut on a Sykes V10A gear generator, set up as shown in Fig. 6. The serration cutter is reciprocated at 413 strokes per min., and completes the operation in 2 min. 33 sec. The finished form is checked with "go" and "not go" serration roller gauges.

Subsequently, the crankshaft is loaded into a




Fig. 5. Steidle No. 1 Thread Rolling Machine Set Up for Rolling Oil Grooves in the Crankshaft




Fig. 6. Set-up on a Sykes V10A Gear Generating Machine for Cutting Serrations on the Crankshaft




Fig. 7. The Two Portions of the Split Casing which Houses the Transmission and Final Drive

fixture on a Herbert No. 4 Senior capstan lathe, on which the eccentric pin is finish turned. This operation is completed in 2 min. 15 sec., and the pin is reduced to 20 mm. diameter, with limits of $+0.030$ mm. $+0.020$ mm. After being deburred, the component is induction hardened to 58/62 Rockwell C to a depth of 0.4/0.65 mm. over the areas indicated in Fig. 4. Finally, five diameters and a taper are finished in a total time of 5 min. 40 sec. on a Newall type L plain grinder.

MACHINING THE LIGHT-ALLOY CASING

Three Grob two-way drilling, tapping and fine-boring machines are employed for a number of operations on both parts of the light-alloy split casing which encloses the crankshaft, flywheel magneto, clutch, transmission, and final drive. The two halves of the casing are shown in Fig. 7,

fully machined in readiness for assembly. An insert, seen at A, is a carbon-steel investment casting in the form of a curved ratchet, which is used in conjunction with a pawl to alter the position of the chain-tensioner arm. The casting on the left in Fig. 7 is shown in Fig. 8, set up on a Grob drilling machine, in a fixture which enables operations to be performed on both faces simultaneously.




Fig. 8. Set-up for Drilling Holes in Both Faces of One Portion of the Transmission Casing on a Grob Machine




Fig. 9. Set-up for Boring the Cylinder on a Grob Fine-boring Machine

In the figure, the work is seen after the completion of the operation during which 18 holes of various diameters on the near side of the casting, and 13 holes on the far side, are drilled in a total time of 77 sec. Next, the holes thus produced are tapped on a Grob machine, of generally similar design, in 69 sec. A Grob fine-boring machine is used to finish the principal shaft holes and ball race bores in the castings which, again, are held in fixtures that are designed to enable operations to be carried out on both sides simultaneously. Certain miscellaneous side holes are subsequently drilled on Archdale and Herbert machines.

CYLINDER BORING

The cylinders of the two-stroke engine are bored in two operations on Grob fine-boring machines. In Fig. 9, one of these machines is shown set up for rough boring a cylinder, which is held in a fixture by cam-operated clamps. At

the conclusion of the boring operation, the fixture is in a position close to the spindle head, and, at this point, a hydraulically-controlled facing tool is applied to machine the joint face on the end of the casting. The spindle speed on this machine is 200 r.p.m., and the feed, $1\frac{1}{2}$ in. per min. Finish boring is carried out on a similar machine, which is fitted with special bearings for the spindle, to ensure the necessary accuracy.

In Fig. 10 is shown a set-up for three boring operations on three different components, which are accommodated in fixtures mounted on a Precimax 3-spindle fine-boring machine. At A may be seen the front suspension swinging arm, which is held in a latch-type fixture and located on two pegs. The 35-mm. diameter hole, through which the front wheel mounting passes, is finish bored with a tungsten carbide-tipped tool, fitted to the head in the foreground, at a speed of 1,050 r.p.m. and a feed of $1\frac{1}{2}$ in. per min. This component is afterwards transferred to a Centec milling machine, on which the spaces between the two lugs at both ends are finished to size with two 6-in. serrated-blade cutters. It may be noted, in passing, that the fixing lugs are subjected to X-ray




Fig. 10. A Precimax 3-spindle Fine-boring Machine Equipped with Three Work Holding Fixtures




Fig. 11. A View of the Assembly Line, Showing the Track and Special Fixtures for Supporting the Scooters

examination for the detection of internal flaws

The fixture at B, in Fig. 10, holds a connecting rod while the phosphor bronze bush in the small end is fine bored. For this boring operation, the spindle speed is 2,500 r.p.m., and the feed, 1½ in. per min. In the third fixture, at C, may be seen a driving gear fitted with a phosphor-bronze bush. This bush is bored to finished size at the same speed and feed. Although shown mounted together on this machine for the purpose of illustration, the components are not handled simultaneously. One spindle only is used at any one time, and the components are machined in batches.

The assembly line for the scooters is shown in Fig. 11. A track, constructed from opposed channel-section steel girders, braced by T-section spacers, serves to guide the special wheel-mounted assembly fixtures to the various stations. Each fixture has a square base, fabricated from angle iron, to which is welded a vertical tubular column. The latter is provided, at its upper end, with a spigot to engage with a hole in the body shell of the scooter. With the body thus firmly held, the fixture is moved along the assembly line, and is locked in position by a draw bolt at each station, while the various sub-assemblies are attached.


Star "Tolerance" Rings

George Angus & Co., Ltd., Oil Seal Division, Coast Road, Wallsend-on-Tyne, have recently acquired the sole manufacturing and selling rights in this country for the range of patent "tolerance" rings developed by Deutsche Star Kugelhalter, G.m.b.H., Schweinfurt, Germany.

Available in a variety of sizes up to 3 in. diameter, these rings, some examples of which are shown in the figure, are made from spring steel, of strip form, with a central corrugated portion. In use, a ring is interposed between a bore and the periphery of a mating part, to provide the equivalent of an interference fit for transmitting a predetermined torque. With this arrangement, the need for machining the mating parts to close dimensional limits is obviated, and drive can be transmitted without the use of splines and keys.

The fit obtained, and, consequently, the maximum torque that can be transmitted, depends upon the width of the ring and the extent of compression of the corrugations during assembly. Compensation for small amounts of misalignment between the mating parts is provided by the rings, and the narrow plain portions at their ends prevent variation of the corrugation-pitch during assembly.

Another advantage claimed for the rings is that they obviate risk of slip due to differential expansion caused by temperature changes, when the mating parts are made from different metals. For this reason, it is stated, the rings may be used to advantage between the outer races of anti-friction bearings and light-alloy housings. Among other applications of the rings may be mentioned the mounting of pulleys, flywheels, gears, bushes and impellers. They also provide a convenient means of fixing knobs, for instance, to operating levers.



Some Typical Star "Tolerance" Rings

Measurement of Paint Thickness on Aircraft

By N. R. KEEGAN

The paint layer on a high-speed aircraft, in addition to being smooth, must be of uniform thickness to close limits. If the thickness varies by only 0.001 in., film failure in the form of cracking and "alligatoring" may occur. This failure, in turn, may reduce the speed of the aircraft by as much as 50 miles per hour, and take-off distance may be increased by as much as 100 yards.

Accurate measurement of paint thickness is thus essential. Tolerances specified by the United States Navy vary with the type of finish, and in some cases are as small as 0.0001 in.

The simplest method of determining thickness is to measure the sheet metal with a micrometer before, and after, it has been painted. Obvious disadvantages are that such measurements are limited to an area near the edge of the sheet, and cannot be made on an assembled aircraft. Another method involves the use of a device which forces a needle through the paint to the base metal, and registers the depth of penetration on a gauge. Apart from the disadvantages that frequent recal-

ibration and needle changing are required, the method is tedious and destructive.


With a third method, which is probably the most widely applied, a portable electronic device produces an oscillating tone when a probe is held against the test surface. The tone is heard through earphones, and is balanced out to the vanishing point by using a potentiometer to control a bridging circuit. Finally, the potentiometer setting is read and applied to a graph, from which the paint thickness is obtained. The disadvantages of this device are that it depends on human hearing, and the necessity of adjusting the graph whenever the device is recalibrated.

Engineers in the Quality Division Laboratory of the Martin Co., Baltimore, Md., U.S.A., recently modified a Boonton film gauge to enable paint thickness to be measured more accurately and conveniently than by other methods. This instrument, originally developed to measure the thickness of metallic plating, was modified and recalibrated for checking organic films. It comprises a

probe, indicating meter control, and a set of samples. The probe, which has three feet that rest against the surface to be measured, is an induction coil which sets up an electrical field.

When a conductor with an organic finish is brought into the electrical field, eddy currents circulate through the conductor. These currents generate an electromagnetic field, which induces an electromotive force in the coil. This force opposes the original current and changes its impedance, and the change produces a reading on the meter.

The meter is first set to zero, with the probe resting on a sample of an alloy of the same composition as the work sheet. Calibrations of the meter indicate thickness of the paint in thousandths of an inch. The Boonton gauge is non-destructive, and can be used on any non-ferrous metal surface where there are no sharp irregularities of contour.



Measuring Paint Thickness on an Aircraft Skin Panel with a Boonton Gauge. The Meter is First Set to Zero with a Sample of the Same Alloy

Baldwin Automatic Control System for a Rolling Mill

The cold strip rolling mill shown in Fig. 1 is installed in the works of D. F. Tayler, Ltd., Carver Street, Birmingham, and has recently been equipped with the new nucleonic automatic gauge control system developed by Baldwin Instrument Co., Ltd., Brooklands Works, Dartford, Kent. It is stated that the mill is the first of its type in the country to be fitted with this equipment, which provides for automatic adjustment of the screw-down mechanism while rolling is in progress, so that strip is produced to a high degree of accuracy for thickness.

Intended for use on strip mills for the cold rolling of brass, copper and steel, the control system depends for its action on bremsstrahlung radiation, which is produced by the emission of beta rays from a radio-active strontium 90 source, on to a metal target. Whereas, with beta rays, steel strip with a maximum thickness of only about 0.02 in. can be measured, bremsstrahlung radiation, it is claimed, enables thicknesses ranging from approximately 0.004 to 0.4 in. to be checked.

Cast steel housings, for the radio-active source and the receiver unit, are mounted on a C-shaped bracket, which embraces the strip and is posi-

tioned between the rolls and the re-coiling reel. Part of this assembly may be seen in the close-up view Fig. 2, the detector unit being indicated at A. Of robust construction, the assembly is mounted on a substantial cross-slide, and may be moved to the working position, and withdrawn to the rear so that it is clear of the strip, by means of a Baldwin air cylinder. Electronic equipment incorporated in the measuring head is supported by anti-vibration mountings, and electric cables are housed in heavy-gauge copper tubing.

While gauging is in progress, radiation from the source is directed on to a sodium iodide crystal in the receiver head, and, in passing through the strip, its strength is reduced by an amount which depends upon the thickness. The reduced-strength radiation causes the crystal to scintillate, and the resulting light rays are passed to an adjacent photomultiplier which generates an electric current proportional to their intensity. This current is fed to a separate floor-mounted control unit, and then is compared with a potential, which represents the required thickness of the strip and can be varied, as desired, by adjustment of a "set thickness" potentiometer. Any out-of-balance in this system

causes a signal to be passed to a low-gain D.C. amplifier, which is connected electrically to the screw-down motors of the mill, by way of a discriminator unit and relays.

When the out-of-balance represents a deviation in the thickness of the strip from the




Fig. 1. The Robertson Cold Strip Rolling Mill Here Shown is Fitted with the New Baldwin Nucleonic Gauge Control System




Fig. 1. Close-up View Showing Part of the Measuring Head and the Indicator Panel

nominal value of between ± 0.0003 and ± 0.0005 in., the discriminator unit causes the screw-down motors to be operated intermittently for a period of $\frac{1}{4}$ sec., at intervals of 2 sec. Signals resulting from deviations of strip thickness exceeding ± 0.0005 in. cause the screw-down motors to be operated continuously for adjusting the roll setting. Alternatively, the equipment can be set so that intermittent and continuous adjustments of the screw-down mechanism are initiated when the thickness of the strip reaches tolerance boundaries different from those stated.

During the rolling operation, the thickness of the strip is continuously recorded on a paper chart by a pen mechanism incorporated in the control unit. The strip thickness in relation to the nominal value is also indicated on a dial-type meter. An indicator panel, mounted close to the rolling mill, incorporates signal lamps which are automatically illuminated when the screw-down motors are at rest, and when the roll is being adjusted upwards and downwards. A safety arrangement is provided which prevents the control system from being brought into use until the mill is running at a preset speed.

Upon completion of the rolling operation, a micro-switch is operated by the trailing end of the strip, and, then, the measuring head is moved clear on the cross slideway. Alternatively, cross-

movement of the measuring head can be controlled by hand, through a solenoid-operated air valve. While the rolled strip is being removed from the take-up reel and a fresh coil is loaded in readiness for rolling, the control system is automatically calibrated. An indexing shutter incorporated in the source holder has three apertures, one of which is fitted with a 0.03-in. thick steel sheet, the second is closed by a thick piece of lead, and the third is blank. Indexing of the shutter is carried out automatically at the end of the rearward travel of the measuring head, and, by setting a selector switch, either the blank aperture or the steel sheet can be interposed between the radio-active source and the receiver head. Calibration of the instrument is carried out by means of the steel sheet when the thickness of the rolled strip ranges from 0.02 to 0.08 in., and the blank aperture is presented to the source when strip of thickness from 0.005 to 0.02 in. is to be produced. The lead reference piece is brought to the working position, by operation of a "manual standardize" switch, when the unit is to be calibrated at the infinity setting.

For calibrating purposes, current from the amplifier is applied to a second discriminator unit, which is connected to a servo-motor by way of relays. Operation of the servo-motor causes a potentiometer to be adjusted until a zero signal is received by the amplifier, from the photo-multiplier in the receiver head. The action of the discriminator causes the potentiometer to be adjusted intermittently for fine setting, and continuously when fairly large corrections are to be made.

Separate signal lamps are provided on the indicator panel, which are automatically illuminated, during, and at the end of, the calibrating operation, and when gauging of the strip is actually in progress. Other lamps show which reference piece is in use during the calibrating stage.

Built by W. H. A. Robertson & Co., Ltd., Bedford, the mill is of the 4-high, non-reversing type, and has 5½-in. diameter by 18-in. wide, work rolls, and 15-in. diameter support rolls. It is employed for finish-rolling brass strip up to 15-in. wide, with thicknesses down to 0.004 in., at speeds up to 500 ft. per min. Drive to the work rolls is taken from a 100-h.p. mill motor. Of 12-in. diameter, the collapsible re-coiling reel is driven by a separate 15-h.p. D.C. motor, and an air-operated stripper mechanism is provided for unloading coiled stock at the end of the rolling operation.

PRODUCTION OF DOMESTIC ELECTRIC WASHING MACHINES during the third quarter of 1957 totalled 170,400 units. During the corresponding period in 1956, 141,500 units were produced.

Conference on Problems of Aircraft Production

The sixth Conference on Problems of Aircraft Production, organized by the Southampton Section of the Institution of Production Engineers, was held at the University of Southampton on January 2 and 3, with an attendance of about 250. The first contribution was the Lord Sempill paper, presented by Mr. Boyd K. Bucey of the Boeing Airplane Co., Ltd., Seattle, U.S.A., and entitled "Manufacturing in the Aeronautic Age." In the opening section of this paper, the author discussed the conditions facing the aircraft industry in the U.S.A., and the methods which were being adopted to overcome the difficulties associated, for example, with rapid technological advances, reductions in Government financial support, management in very large organizations, and complexity of designs, especially of weapon systems and test equipment. Among the methods mentioned were the adoption of quality control to replace inspection, by placing the responsibility for quality on all the employees of a plant, the system being extended even to the tool stores, since loss of tools had been found seriously to affect production schedules.

New production techniques, developed for the manufacture of aircraft and weapons to operate at increasing speeds, were then discussed, and many of them were illustrated in a colour, sound film, which was shown after the paper had been read.

Among the subjects touched upon was the friction sawing of titanium and stainless steel, and mention was made of a skin saw in the form of a 6-in. disc, with two carbide blades, which was run at 10,000 r.p.m., and would cut aluminium up to 1 in. thick. Improved results had been obtained in blanking sheet material, it was stated, by using a steel punch, produced by a patented method, in conjunction with a die of the steel rule type, and with this arrangement, upwards of 100,000 parts had been blanked from $\frac{1}{4}$ -in. material with a single tool. Machining of heavy-gauge stainless steel and titanium was carried out with a contouring machine equipped with a tool of about 1 in. diameter (with inserted carbide blades) which projected vertically from the surface of the machine table. Speeds of 1,600 and 800 ft. per min. were quoted for stainless steel and titanium respectively, and liquid carbon dioxide was applied to the cutter for cooling purposes.

Other operations illustrated in the film, which

ran for about 20 min., included, for example, those involved in the manufacture of a double panel from two stainless steel skins with X-section stiffeners between them. Extensions of each limb of the X were spot-welded to the top and bottom skins on a special machine, with the aid of a support mechanism which could be expanded for the welding operation, and then contracted to permit of indexing of the assembly. Fusion-type machines for welding sheet titanium, in which a trailing shield of gas is applied to both sides of the material, were also shown.

Attention was drawn to the use of heat in forming metals for which conventional methods were not suitable, and the film illustrated a Yoder roll-forming machine for sections, and stretch-forming machines for sheet and sections, on which the material was heated to between 1,000 and 1,500 deg. F. (for titanium) by means of gas furnaces and electrical heating elements. An interesting application of hot working, mentioned in the paper, was the upsetting of titanium rivets on a squeezing machine controlled by the yielding of the heated rivet. Titanium alloy sheet could be formed by heating it, with a simple blow-torch set-up, while it is in position over the punch. A drop hammer, fitted with a rubber pad, was then employed to form the sheet round the punch, the rubber being confined in a recess in the tup, and being in contact with the hot sheet for such a short time that it is not adversely affected.

Other subjects mentioned in the paper included forgings, integrally-stiffened skin panels, super high strength steels, chemical milling, the standardization of machine tools, and numerical control. Improved techniques for forming, in addition to others already mentioned, included those involving the use of explosives, flow-turning, and shot peening. A new method of making radomes, whereby layers of resin-impregnated glass fibre material were wrapped round a tapered mandrel in the circumferential and longitudinal directions alternately, was said to give very consistent electrical properties, and to enable the production time to be considerably reduced.

Abstracts from the paper entitled "Manufacturing Practice—A Review of the British Aircraft Industry," presented by Mr. L. G. Burnard, M.I.Prod.E., A.F.R.Ae.S., Vickers-Armstrongs (Air-

craft), Ltd., were published in *MACHINERY*, 92/37—3/1/58 and 92/97—10/1/58, and references to this paper during the discussion at the end of the Conference will be given later. Instead of reading his rather long paper, Mr. Burnard showed an interesting silent film, in black and white, of some of the machines described in it, including routing machines for the production of ribbed skin panels and other components, and the procedure for making ribbed panels by chemical erosion. Equipment for the programme control of machine tools, and machines for accurately bending aircraft pipes, were also shown in operation.

Subsequently, a colour, sound film made by the Fairey Aviation Co., Ltd., was shown. Running for about 10 min., this film was concerned with the 3-dimensional sculpture-milling machine built by the company, to which some reference was made at the Fourth Conference, two years ago. This machine incorporates the Ferranti system of magnetic tape control, and will accommodate stretched aluminium slabs measuring up to 27 ft. long by 7 ft. wide. We hope to describe the Fairey machine in detail in a future issue of *MACHINERY*.

The paper entitled "Some Aspects of the Design, Development and Manufacture of the P.1 Wing," which was presented jointly by Mr. F. Bradford, A.F.R.Ae.S., and Mr. G. H. Taylor, who are concerned with design and production, respectively, for the English Electric Co., Ltd., was restricted in its scope by security considerations, but was of considerable interest to aircraft designers and production engineers. The wing was designed for production in two halves, each of which comprised an upper and a lower portion. These two portions were made separately, and was then assembled into a complete structure which incorporated fuel tanks and other features. Sealing of the fuel tanks, of which the wing skin panels form the sides, presented difficulties, and various methods were tried. One of these methods, for sealing 3-corner joints, involved the use of a rubber block, cured to the required contours in a mock-up joint which served as a die, and then bolted into the corner. Compression of the rubber block, by the fixing bolt, forced the material into close contact with the joint surfaces in the final assembly, which was thus rendered completely leak-proof.

Rivets for the attachment of the skin panels were made leak-tight by machining a ridge, of 90-deg. section, in the countersink surface. When the rivet was upset, this ridge bit into the rivet head, and a joint with the required characteristics was obtained. For a bolt, the ridge was machined on the conical surface of the head, so that, when tightening took place, the ridge bit into the skin

material. Joints made with these bolts and rivets were found to be satisfactory under pressure, even without the use of conventional sealants.

Among the production methods considered in the part of the paper contributed by Mr. Taylor were those concerned with the forming of T-section extrusions to various angles for spar booms, and reference was made to an extrusion of special design from which these booms could be produced more readily. Booms were formed to fit the wing skin panels on a Hufford A.46 machine (Wickman, Ltd.), and drilling and reaming of the skin panels, booms and other components, performed with the aid of fixtures, was followed by riveting on a special machine. Among the wing components which were produced by machining methods, was a frame with a double curvature, which was now being made from a precision die pressing supplied by High Duty Alloys, Ltd. This pressing was made to limits of $-0.000/-0.030$ in. over its length of about 30 in. Another interesting component mentioned was a steel bearing housing made from DTD 124 and S 92 material, which was fabricated by welding, and subsequently heat-treated to provide a tensile strength of 45 to 50 tons per sq. in.

APPLICATIONS OF NUMERICAL CONTROL

The discussion which followed each paper was somewhat limited, but a longer period was provided after the third paper, during which questions could be addressed to any speaker, and those attending the conference were invited to make their own contributions, where they had any special knowledge of the subject raised. Among the matters discussed was the design of a capstan lathe mentioned by Mr. Burnard, which would be capable of setting itself from numerical information supplied in the form of a punched tape or card. As outlined, the lathe, arranged for bar feed, would be so equipped that the cutting tool, on passing a datum point, would register its position. The tool would then be controlled numerically and would be fed into the required depth, after which it would be traversed longitudinally according to the shape of the component required. By controlling the bar feed, and the tool slides and capstan head, it would be possible, theoretically, to prepare the lathe merely by clamping tools in position without setting, and to insert the punched tape or card, whereupon the machine would produce a number of components and stop.

In reply to subsequent questions, Mr. Burnard said that where quantities as small as 10 were concerned, as often happened in the aircraft

industry, it might take, say, 1½ hours to set the machine and 20 min. to make the parts. Progress which had been made so far had shown that it would be possible to control one slide in the manner indicated, and it was now intended to apply the system to the remainder of the machine.

Another application of numerical control, which was also in its early stages of development, was for the production of aircraft tubing in which complicated and accurate bends were required. The machines described in Mr. Burnard's paper would lend themselves to numerical control, and work was proceeding in this connection. The production of integrally-stiffened skin panels, and other intricately-shaped parts, was being undertaken in this country largely by high-speed routing techniques, as described in Mr. Burnard's paper, and such methods were now being applied to high-tensile steel components, of which two examples were on view. These parts had been machined by the routing technique, at cutting speeds of 700 to 800 ft. per min., as compared with speeds up to 10,000 ft. per min. for light alloys, by Ferrand Luttmner, Ltd., London, with a tool of special design and liquid carbon dioxide cooling.

One of the examples shown was for the Gloster Aircraft Co., Ltd., and had been finished on the outer profile in a time of 1 hour 20 min. This component was of S.99 steel, and had been machined with a cutter tipped with Prolite 14 carbide, running at 4,000 r.p.m., and cooled by carbon dioxide at the rate of 20 lb. per hour. One such component could be finish-machined, and another rough-machined, for each regrind of the cutter. In the other, smaller part, a pocket had been machined by the routing technique.

TITANIUM

In connection with titanium, perhaps the most interesting point to emerge from the discussion was the statement by Mr. W. S. Hollis, of the Ministry of Supply, that the material now cost £6 per lb. in the raw state and between £22 and £30 per lb. of installed weight in an aircraft. Mr. Hollis also mentioned that, whereas tool lives of 30 to 40 sec. were common in the early days of machining titanium, they had now been extended to as much as 20 min. Both forming and resistance welding were being carried out satisfactorily. Mr. Taylor, of the English Electric Co., Ltd., said that his company had been machining C130AM titanium with carbide tools, which could be used for periods up to 4 hours without re-grinding, at a cutting speed of 180 ft. per min. It was advisable, he said, to produce blanks for small forgings by machining from the bar, rather than by upsetting

methods, since the latter rendered the material almost unmachinable. Scalping between heats might also be carried out with advantage.

Mr. J. Purcell, of the College of Aeronautics, Cranfield, described some experimental work in which it had been found that build-up of titanium took place on the cutting edge of a tool, and if it was removed, some of the tool material was carried away. If the build up was allowed to take place at a slow cutting speed, of the order of 50 ft. per min., a protective shield of titanium was formed on the cutting edge and the speed could then be increased by as much as five times, while still obtaining reasonable tool life. In answer to Mr. Burnard's suggestion that a chemical coolant should prevent pressure welding, and consequent build up, Mr. Purcell said that it was difficult to maintain a film between the tool edge and the component face.

MIST LUBRICATION FOR CUTTING TOOLS

Mist lubrication of cutting tools was also discussed at length, following a description of the system by Mr. Burnard, in which he mentioned the machining of light alloys with carbide cutters. These cutters originally had a life of one or two days between regrinds, but with mist cooling they lasted for a week or more. On this subject, Mr. A. E. N. Bolton, of Sperry Gyroscope Co., Ltd., reported that slots, $\frac{1}{16}$ in. wide and up to $\frac{3}{8}$ in. deep, were being milled in forged steel, of 65 tons tensile strength, with a solid carbide cutter, which was run at 30,000 r.p.m. The best results had been obtained with DTD 585, a hydraulic fluid based on paraffin, which had enabled cutter life to be increased by 50 to 60 per cent.

Mr. J. Glennie of Bristol Aircraft, Ltd., asked Mr. Burnard whether the use of mist coolants might not be undesirable for health reasons, and the answer was that less than a pint per day per cutter was employed and was delivered through a very small jet. On reaching any metal parts of the machine, the jet was converted into a liquid which ran away, so that there was very little mist in the air breathed by the operator.

Mr. Bolton said that owing to discomfort experienced by operators on machines adjacent to those equipped for mist cooling, his company had fitted vacuum extraction nozzles on the opposite sides of the cutters to the mist jets, to take away overspray. For one operation, more than $\frac{1}{2}$ gal. per day was being used. Mr. Burnard remarked that only the minimum of spray needed to form a coating on the cutter, to provide lubrication and prevent pick-up and consequent smearing of the machined face, was employed. It was suggested by Mr. Bolton, however, that any reduction in the

amount of coolant applied would result in shorter cutter life, and extractors had therefore been fitted. Mr. Purcell described an apparatus for measuring the amount of coolant that would be breathed in by an operator.

STANDARDIZATION

On the subject of standardization of design, Mr. Bucey commented that, at one time, it had been the practice of the Boeing Co. to place in a book a drawing of any clip or bracket which might be useful in another application. Eventually the number of books became so large that no one would consult them. It was now found to be quicker to design another component than to search for an existing design. Among the items that were standardized were bolts, screw and flange holes, tools, tube-bend radii and milling cutter sizes. Pulley brackets were normally made from standardized double extrusion material.

For tooling, Mr. Bucey outlined an elaborate system of consultation whereby everyone likely to be concerned with a tool was asked to make comments and suggestions. In this way, even badly-designed tools were made acceptable to the men in the shop. He also described a bonus system operated by the Boeing Co., whereby a percentage of profits was put aside and distributed at the end of the year, according to the quality of the work done by each individual employee. Part of this money was normally paid in the form of shares to foster an interest in the company, and this year it would all be in shares because of the need for re-equipment.

USE OF CASTINGS

Mr. J. W. Jones, of the College of Aeronautics, asked if any castings were employed in airframes in the U.S.A. and if any were used in the P.1, to which Mr. Bucey replied that inconsistencies in the physical properties of castings were limiting their application in America. Mr. Bradford said that some castings were used on the P.1, but since they often had to be machined all over they might prove uneconomic. Mr. Taylor indicated that he was very interested in the application of castings to airframe construction, and showed a photograph of a typical component, made by the shell moulding process, which had been produced to limits of 0.010 in. and required no machining. This part, a corner bracket, had been used in the Canberra. Another component, which was being cast, was incorporated in the front undercarriage, and investment castings in steel were employed for aileron hinges. The Investment-X process of investment casting (MACHINERY, 86/37—7/1/55), was being

investigated. Mr. P. V. Brown, of the Ministry of Supply, said that the Ministry was arranging for the installation of a vacuum furnace capable of melting and casting weights up to 600 lb., and important developments could be anticipated, since steel makers felt that they could achieve up to 85 tons ultimate tensile strength, with 7 per cent elongation. There was some doubt, however, about the reliability of the castings.

With reference to forgings, Mr. Bucey said that the Boeing Co. had been using welded bulkheads, but for various reasons had been compelled to adopt the forging method instead, and it had proved very successful. On the other hand, difficulties and delays in the making of precision forging dies, coupled with their high cost, would lead them back to the use of weld-fabricated parts. He thought that the method, originated in this country, of using stretch-levelled slabs, and machining components from them under numerical control, would soon be adopted in the U.S.A. Design changes could be made easily and quickly, and a numerically-controlled machine could probably be purchased for about the same outlay as a set of precision forging dies.

WELD FABRICATION

Much interest was shown in Mr. Burnard's descriptions of the use of weld-fabrication methods for the production of such large aircraft components as fuselage bulkheads, which he had noted on a recent visit to the U.S.A. Welding was carried out with electrodes which gave deposits that could be heat-treated to a strength of about 90 tons per sq. in. By good design, a structure could be obtained with a strength equivalent to that of the material from which it was made. Another interesting example was a large undercarriage component of wish-bone shape, made from three steel parts, which were machined to finished size before they were welded. Excess material was left at the welding positions and the parts were then butt-welded to the exact dimensions required.

Mr. Bradford said that he had investigated the problem of attaching 14-s.w.g. stringers to 16-s.w.g. skin panels by spot welding, and had found that a minimum flange width of 0.95 in. was specified for a circular spot-weld slug of 0.3 in. diameter. Since $\frac{1}{2}$ -in. diameter rivets at 1-in. pitch, with a 0.6-in. wide flange, would have been adequate, he thought that this width should also be suitable for spot welding. Was there any reason, he enquired why the electrodes should not be of elongated shape, measuring 0.2 by 0.4 in., so that the flange width could be reduced to 0.6 in. without any reduction in strength? Mr. C. A. Burton,

of Sciaky Electric Welding Machines, Ltd., said that it should be possible to obtain satisfactory welds of the form suggested.

Mr. Taylor described an interesting method of riveting skin panels, about $\frac{1}{4}$ in. thick, to other components in wing structures, which could have been used for making a leak-proof wing tank had their other efforts been unsuccessful. This method involved drilling holes in the skin of a depth equal to about two-thirds of its thickness and then machining a recess at the bottom of each hole.

Plain cylindrical rivets were used which were supported above the stringer surface during a preliminary upsetting operation. At this stage, the rivet was pushed in until the end spread sideways into the machined recess, the under-surface of the sheet being supported to prevent penetration. The support bush was then removed and the rivet head upset in the normal manner. This technique was available for anyone who wished to use it. A demonstration panel was shown which had been made in this manner described.

Trade Publications

BIRFIELD INDUSTRIES, LTD., Stratford House, Stratford Place, W.1.—Leaflet on the Multi-Constaflo control for water flow rates from 7 to 18 gal. per min. which has recently been added to the Birflo range.

THE WALTERISATION CO., LTD., Purley Way, Croydon. Folder devoted to the company's Fasbond paint-bonding process. The various treatments available are briefly described, and sections are concerned with pre-treatment, making up and operation, and plant required.

R. B. PULLIN & CO., LTD., Phoenix Works, Great West Road, Brentford, Middlesex.—Publications concerned with the company's electrically-actuated traffic barrier for control and safety on factory roadways and in similar situations. The construction is described in detail.

CASTING REPAIRS, LTD., 81 Saltergate, Chesterfield, Derbyshire.—Publication concerned with the metal stitching process for repairing cracked and broken castings. Illustrations are included of typical castings which have been repaired in this manner.

ROSE BROTHERS (GAINSBOROUGH), LTD., Bearings Division, Gainsborough, Lincs. Folder with illustrations of Heim and Rose spherical bearings and spherical bearing rods ends which will accommodate misalignment and provide for the transmission of motion at varying angles.

TELEPHONE RENTALS, LTD., Kent House, Rutland Gardens, Knightsbridge, London, S.W.7.—Folder drawing attention to the services offered by the company in connection with production control, internal broadcasting, and internal telephone systems.

CONSOLIDATED PNEUMATIC TOOL CO., LTD., 232 Dawes Road, London, S.W.6. Fully illustrated publication which constitutes the first section of the company's accessories catalogue, and covers an extensive range of hosepipes and hose fittings. Recommendations are included for various types and sizes of pneumatic tools.

R. H. COLE (OVERSEAS), LTD., 2 Caxton Street, London, S.W.1.—Booklet devoted to contact cooled selenium rectifiers made by Siemens & Halske. Primarily intended for radio and television applications, it is stated that these rectifiers, by reason of their small size and high output

current capacity, are proving of increasing interest to manufacturers of solenoid actuators and electro-magnetic valves.

LONDEX, LTD., Anerley Works, 207 Anerley Road, London, S.E.20. List No. 174 describes two types of electro-magnetic batch counters which are suitable for a variety of industrial applications.

HERBERT MORRIS, LTD., P.O. Box 7, Loughborough.—Catalogue (F175) of electric chain hoists which are available in various types with capacities of $\frac{1}{4}$, $\frac{1}{2}$, and 1 ton. Folder F176 is concerned with lever pull hoists in $\frac{3}{4}$, $1\frac{1}{2}$, and 3-ton sizes; and Folder F177 with triple gear pulley-blocks for working loads from $\frac{1}{4}$ to 20 tons.

BRITISH BITUMEN EMULSIONS, LTD., Dundee Road, Trading Estate, Slough, Bucks. Folder concerned with the company's Wearproof for reconditioning factory floors. This product is added to a concrete or cement mix. No hacking out is required, and the floor can be treated progressively, as space becomes available, with a minimum of interference with normal work.

DAWSON, McDONALD & DAWSON, LTD., Compton Works, Ashbourne.—Leaflet describing the type D series 2 and 3, oil-free, diaphragm, air compressors, which are directly coupled to electric motors. The series 3 unit can now be supplied with fan cooling whereby the running temperature is considerably reduced and diaphragm life increased.

MINIATURE BEARINGS, LTD., 39 Parliament Street, Westminster, London, S.W.1.—Catalogue of RMB miniature bearings made by Roulements Miniatures S.A., Bienne, Switzerland. Information is included on load capacity, friction torque, inspection tolerances, mounting and mounting fits, cleaning, lubrication, and angular contact. The various types of bearings are illustrated and particulars of the available sizes are conveniently tabulated. In addition details are appended of three new series of inch size bearings which are now in production or preparation. The agents point out that since the 1954 catalogue was issued, the production of Series E, O, and OT bearings has been discontinued. These bearings, however, will still be supplied until stocks are exhausted. A new series of NUS roller bearings has been introduced, which are similar to the NU series, but without inner races.

amount of coolant applied would result in shorter cutter life, and extractors had therefore been fitted. Mr. Purcell described an apparatus for measuring the amount of coolant that would be breathed in by an operator.

STANDARDIZATION

On the subject of standardization of design, Mr. Bucey commented that, at one time, it had been the practice of the Boeing Co. to place in a book a drawing of any clip or bracket which might be useful in another application. Eventually the number of books became so large that no one would consult them. It was now found to be quicker to design another component than to search for an existing design. Among the items that were standardized were bolts, screw and flange holes, tools, tube-bend radii and milling cutter sizes. Pulley brackets were normally made from standardized double extrusion material.

For tooling, Mr. Bucey outlined an elaborate system of consultation whereby everyone likely to be concerned with a tool was asked to make comments and suggestions. In this way, even badly-designed tools were made acceptable to the men in the shop. He also described a bonus system operated by the Boeing Co., whereby a percentage of profits was put aside and distributed at the end of the year, according to the quality of the work done by each individual employee. Part of this money was normally paid in the form of shares to foster an interest in the company, and this year it would all be in shares because of the need for re-equipment.

USE OF CASTINGS

Mr. J. W. Jones, of the College of Aeronautics, asked if any castings were employed in airframes in the U.S.A. and if any were used in the P.1, to which Mr. Bucey replied that inconsistencies in the physical properties of castings were limiting their application in America. Mr. Bradford said that some castings were used on the P.1, but since they often had to be machined all over they might prove uneconomic. Mr. Taylor indicated that he was very interested in the application of castings to airframe construction, and showed a photograph of a typical component, made by the shell moulding process, which had been produced to limits of 0.010 in. and required no machining. This part, a corner bracket, had been used in the Canberra. Another component, which was being cast, was incorporated in the front undercarriage, and investment castings in steel were employed for aileron hinges. The Investment-X process of investment casting (MACHINERY, 86/37—7/1/55), was being

investigated. Mr. P. V. Brown, of the Ministry of Supply, said that the Ministry was arranging for the installation of a vacuum furnace capable of melting and casting weights up to 600 lb., and important developments could be anticipated, since steel makers felt that they could achieve up to 85 tons ultimate tensile strength, with 7 per cent elongation. There was some doubt, however, about the reliability of the castings.

With reference to forgings, Mr. Bucey said that the Boeing Co. had been using welded bulkheads, but for various reasons had been compelled to adopt the forging method instead, and it had proved very successful. On the other hand, difficulties and delays in the making of precision forging dies, coupled with their high cost, would lead them back to the use of weld-fabricated parts. He thought that the method, originated in this country, of using stretch-levelled slabs, and machining components from them under numerical control, would soon be adopted in the U.S.A. Design changes could be made easily and quickly, and a numerically-controlled machine could probably be purchased for about the same outlay as a set of precision forging dies.

WELD FABRICATION

Much interest was shown in Mr. Burnard's descriptions of the use of weld-fabrication methods for the production of such large aircraft components as fuselage bulkheads, which he had noted on a recent visit to the U.S.A. Welding was carried out with electrodes which gave deposits that could be heat-treated to a strength of about 90 tons per sq. in. By good design, a structure could be obtained with a strength equivalent to that of the material from which it was made. Another interesting example was a large undercarriage component of wish-bone shape, made from three steel parts, which were machined to finished size before they were welded. Excess material was left at the welding positions and the parts were then butt-welded to the exact dimensions required.

Mr. Bradford said that he had investigated the problem of attaching 14-s.w.g. stringers to 16-s.w.g. skin panels by spot welding, and had found that a minimum flange spot width of 0.95 in. was specified for a circular spot-weld slug of 0.3 in. diameter. Since $\frac{1}{2}$ -in. diameter rivets at 1-in. pitch, with a 0.6-in. wide flange, would have been adequate, he thought that this width should also be suitable for spot welding. Was there any reason, he enquired why the electrodes should not be of elongated shape, measuring 0.2 by 0.4 in., so that the flange width could be reduced to 0.6 in. without any reduction in strength? Mr. C. A. Burton,

of Sciaky Electric Welding Machines, Ltd., said that it should be possible to obtain satisfactory welds of the form suggested.

Mr. Taylor described an interesting method of riveting skin panels, about $\frac{1}{4}$ in. thick, to other components in wing structures, which could have been used for making a leak-proof wing tank had their other efforts been unsuccessful. This method involved drilling holes in the skin of a depth equal to about two-thirds of its thickness and then machining a recess at the bottom of each hole.

Plain cylindrical rivets were used which were supported above the stringer surface during a preliminary upsetting operation. At this stage, the rivet was pushed in until the end spread sideways into the machined recess, the under-surface of the sheet being supported to prevent penetration. The support bush was then removed and the rivet head upset in the normal manner. This technique was available for anyone who wished to use it. A demonstration panel was shown which had been made in this manner described.

Trade Publications

BIRFIELD INDUSTRIES, LTD., Stratford House, Stratford Place, W.1.—Leaflet on the Multi-Constaflow control for water flow rates from 7 to 18 gal. per min. which has recently been added to the Birflo range.

THE WALTERISATION CO., LTD., Purley Way, Croydon. Folder devoted to the company's Fasbond paint-bonding process. The various treatments available are briefly described, and sections are concerned with pre-treatment, making up and operation, and plant required.

R. B. PULLIN & CO., LTD., Phoenix Works, Great West Road, Brentford, Middlesex.—Publications concerned with the company's electrically-actuated traffic barrier for control and safety on factory roadways and in similar situations. The construction is described in detail.

CASTING REPAIRS, LTD., 81 Saltergate, Chesterfield, Derbyshire.—Publication concerned with the metal stitching process for repairing cracked and broken castings. Illustrations are included of typical castings which have been repaired in this manner.

ROSE BROTHERS (GAINSBOROUGH), LTD., Bearings Division, Gainsborough, Lincs. Folder with illustrations of Heim and Rose spherical bearings and spherical bearing rods ends which will accommodate misalignment and provide for the transmission of motion at varying angles.

TELEPHONE RENTALS, LTD., Kent House, Rutland Gardens, Knightsbridge, London, S.W.7.—Folder drawing attention to the services offered by the company in connection with production control, internal broadcasting, and internal telephone systems.

CONSOLIDATED PNEUMATIC TOOL CO., LTD., 232 Dawes Road, London, S.W.6. Fully illustrated publication which constitutes the first section of the company's accessories catalogue, and covers an extensive range of hosepipes and hose fittings. Recommendations are included for various types and sizes of pneumatic tools.

R. H. COLE (OVERSEAS), LTD., 2 Caxton Street, London, S.W.1.—Booklet devoted to contact cooled selenium rectifiers made by Siemens & Halske. Primarily intended for radio and television applications, it is stated that these rectifiers, by reason of their small size and high output

current capacity, are proving of increasing interest to manufacturers of solenoid actuators and electro-magnetic valves.

LONDEX, LTD., Anerley Works, 207 Anerley Road, London, S.E.20. List No. 174 describes two types of electro-magnetic batch counters which are suitable for a variety of industrial applications.

HERBERT MORRIS, LTD., P.O. Box 7, Loughborough.—Catalogue (F175) of electric chain hoists which are available in various types with capacities of $\frac{1}{4}$, $\frac{1}{2}$, and 1 ton. Folder F176 is concerned with lever pull hoists in $\frac{1}{2}$, $1\frac{1}{2}$, and 3-ton sizes; and Folder F177 with triple gear pulley-blocks for working loads from $\frac{1}{4}$ to 20 tons.

BRITISH BITUMEN EMULSIONS, LTD., Dundee Road, Trading Estate, Slough, Bucks. Folder concerned with the company's Wearproof for reconditioning factory floors. This product is added to a concrete or cement mix. No hacking out is required, and the floor can be treated progressively, as space becomes available, with a minimum of interference with normal work.

DAWSON, McDONALD & DAWSON, LTD., Compton Works, Ashbourne.—Leaflet describing the type D series 2 and 3, oil-free, diaphragm, air compressors, which are directly coupled to electric motors. The series 3 unit can now be supplied with fan cooling whereby the running temperature is considerably reduced and diaphragm life increased.

MINIATURE BEARINGS, LTD., 39 Parliament Street, Westminster, London, S.W.1.—Catalogue of RMB miniature bearings made by Roulements Miniatures S.A., Bienne, Switzerland. Information is included on load capacity, friction torque, inspection tolerances, mounting and mounting fits, cleaning, lubrication, and angular contact. The various types of bearings are illustrated and particulars of the available sizes are conveniently tabulated. In addition details are appended of three new series of inch size bearings which are now in production or preparation. The agents point out that since the 1954 catalogue was issued, the production of Series E, O, and OT bearings has been discontinued. These bearings, however, will still be supplied until stocks are exhausted. A new series of NUS roller bearings has been introduced, which are similar to the NU series, but without inner races.

"National" Machines to be Built in this Country

Arrangements have recently been concluded whereby a range of forging, cold heading and precision nut tapping machines, also Reduceroil roll forging machines and Maxipres forging presses, developed by the National Machinery Co., Tiffin, Ohio, U.S.A., will be built under licence by W. H. A. Robertson & Co., Ltd., Bedford. Sales and service of the British-built machines will be handled by Buck & Hickman, Ltd., Otterspool Way, By-Pass, Watford, who will continue to distribute National machines made in the U.S.A.

Production of high-speed nut tapping machines has already started in this country, and delivery is expected to begin in about 6 to 8 months' time. It is anticipated that the full range of British-built National machines of different types and sizes will be available within the next two years.

The tapping machines, an example of which is shown in Fig. 1, are being made in four sizes with capacities for handling hexagon nuts of $\frac{1}{8}$, $\frac{3}{16}$, $\frac{1}{2}$ and $\frac{3}{4}$ in. sizes. Of the non-reversing type, these



Fig. 1. An Example from the Range of National High-speed Nut Tapping Machines




Fig. 2. National 4-in. Capacity Double-stroke Cold Heading Machine

machines are fully automatic in operation, and incorporate a number of advanced design features which enable accurate threads to be cut at high speeds. Bent-shank taps of a special design are employed, and a pitch control system is incorporated. Other features include safety stopping devices and a sorting unit. As an indication of the production rates obtainable, it may be noted that the smallest machine will handle 96 nuts with ANC threads or 72 nuts with ANF threads per min.

Solid die cold heading machines will be available in single and double stroke designs, and will include tubular, ball, and roller headers. Initially, the machines will be built in five sizes for handling stock of $\frac{1}{8}$, $\frac{3}{16}$, $\frac{1}{4}$, $\frac{5}{16}$ and $\frac{3}{8}$ in. diameter, although the range will be extended later to




Fig. 3. National 4-in. Capacity High Duty Forging Machine

include headers up to $\frac{3}{4}$ in. capacity. The double-stroke cold heading machine shown in Fig. 2, is intended for the production of machine bolts, carriage bolts and cap screws, for example, with shank diameters up to $\frac{3}{4}$ in. It incorporates recently-developed cut-off and transfer units and a new oscillating tool holder and dynamic counterbalance system which permit increased operating speeds. A new workpiece ejector is also fitted which ensures improved die life. The all-steel box-type bed is of exceptional strength to provide the necessary rigidity, and all moving parts are enclosed.

The machine will produce bolt blanks at the rate of 135 per min., and on the single-stroke header of similar capacity, the output rate is 160 blanks per min. On the $\frac{1}{2}$, $\frac{3}{8}$, $\frac{1}{4}$ and $\frac{3}{16}$ -in. double stroke machines bolt blanks can be produced at rates of 250, 225, 200 and 175 per min. respectively. The corresponding figures for the single-stroke machines are 400, 330, 275 and 225.

National high-duty forging machines will be built with capacities for handling bar stock of 1, 1 $\frac{1}{2}$, 2, 2 $\frac{1}{2}$, 3, 4, 5 and 6 in. diameter, and operating speeds ranging from 90 to 27 strokes per min. In Fig. 3 is shown the 4-in. capacity forging machine which has a working speed of 35 strokes per min. This machine has a short compact bed, and a long overarm heading slide which ensures accurate alignment of the punch and die. Other design features include a suspended gripper slide and an air-operated clutch with friction slip relief.

The Reduceroll roll-type forging machines will

handle bar stock of circular or square cross section, and are specially designed for pre-forming blanks that are to be subsequently formed to the desired shape in a forging press. The machines enable blanks of uniform shape to be readily prepared, and the subsequent press-forming operation can usually be performed without re-heating the work. These machines will be built in 6 sizes which are designated No. 1, 2, 4, 6, 7 $\frac{1}{2}$ and 10.

Maxipres high-speed forging presses are to be made in 5 sizes with capacities of 700, 1,300, 1,600, 2,000 and 2,500

tons. These presses have operating speeds of 90, 80, 70, 60 and 55 strokes per min., and ram travels of 8, 10, 11, 12 and 14 in. In Fig. 4 are shown, the Maxipres 700 ton press and the No. 4 size Reduceroll roll forging machine, set up for the production of wrenches.




Fig. 4. A Maxipres 700-ton Forging Press and a No. 4 Size Reduceroll Roll Forging Machine

News of the Industry

Yorkshire

GREENWOOD & BATLEY, LTD., Armley Road, Leeds, are experiencing a well-maintained demand for their various products. Standard-type cold heading machines of various sizes are in hand, also the high-speed, solid die, double-blow machines, up to $\frac{1}{2}$ -in. capacity. In addition, we may note orders for thread rolling machines, bolt head trimming presses, and screw nicking machines. Friction screw presses are another active line, and recent orders cover machines with capacities of 20, 125, 450 and 1,000 tons. Horizontal hot forging machines, for 1- and $1\frac{1}{2}$ -in. diameter bars, are also being built. Special equipment on order includes single- and double-spindle vertical profile milling machines; vertical double-action punching and cupping presses for cap shells, with double feed rolls and transfer mechanism; and horizontal, multiple-operation, toggle-type drawing machines with hopper feed. We may note recent export business with Canada, Australia, India, and Pakistan.

Greenbat fixed and elevating platform electric trucks, including fork-lift types, are in brisk demand, and a good business is reported in mining locomotives. Our attention was drawn to a 10-ton fixed platform electric truck with power-assisted steering, which has been built for the Atomic Energy Commission; and to a 5-ton, elevating-platform truck, with a hopper mounted on the platform, for carrying aluminium powder, which is blown from the hopper into the furnace. The latter vehicle is destined for an aluminium plant in Canada. We hope to make further reference to both these trucks in due course. We may note a recent order from the National Coal Board for a 14-ton battery locomotive of 90 h.p.

HAYES ENGINEERS (LEEDS), LTD., Gelderd Road, Leeds, inform us that there is a sustained demand for their Diemaster and Tracemaster precision vertical milling machines, some of which are being equipped with Hydrotracer hydraulic copying equipment, and jig boring and high-speed milling attachments. Recent developments include a fully-automatic machine for 3-dimensional copy machining of solid rotor blades; an automatic machine for sinking square cavities in turbine blades, and a special, twin rotary table, cam milling, machine. We hope to make further reference to these special machines at a later date. Tracer

valves, hydraulic pump units, and hydraulic profiling equipment for application to machine tools are in good request.

In the machine tool sub-contract section we noted a number of automatic tool and cutter grinding machines and die-casting machines in progress. Recent plant additions include a large Coventry thread-grinding machine, and Precimax 6- by 12-in. plain and 10- by 20-in. universal grinding machines. The firm's slideway grinding capacity has been doubled by the conversion of a planing machine for slideway grinding, by the application of a universal grinding head to the cross-slide and hydraulic transmission to the table.

MIDGLEY & SUTCLIFFE, LTD., Hunslet, Leeds, report a steady influx of orders for their various types of plain and universal horizontal and vertical milling machines, also for radial drilling machines up to 6 ft. radius. A new size of vertical milling machine, in course of development, will have a 48- by 11-in. table. This machine incorporates the table and knee of the latest No. 3 size plain or universal horizontal milling machine. We may also note that orders are in hand for turret-head type milling machines. Among plant recently installed we noted a Herbert No. 7 Preoptive turret lathe, an Abwood circular dividing machine, and a Herbert broaching machine.

CAMPBELLS & HUNTER, LTD., Sayner Road, Leeds, have some capacity available for cutting spur gears up to 8 ft. 6 in. diameter, and bevel gears up to 3 ft. diameter. Gears can be supplied complete or machined from customers' blanks.

SAMUEL DENISON & SON, LTD., Hunslet Foundry, Leeds, are well placed for orders for testing machines and weighing equipment from both home and overseas customers. On the testing machine side, in addition to standard-type dial machines, of various capacities, we may note creep testing machines and special-purpose types. Orders are also in hand for various sizes of weighbridges and for conveyor-type weighers.

FRANK WIGGLESWORTH & CO., LTD., Saltaire, Shipley, have supplied a leaflet describing their Texrope grommet V-belts, a development which has resulted from co-operative research by the Allis-Chalmers and B. F. Goodrich companies. Compared with normal V-belts, the grommet type is claimed to have from 20 to 50 per cent longer life, with cooler running, increased shock absorb-

ing capacity, much lower shrinkage and stretch, improved grip, and 20 per cent greater tensile strength.

TEXTILE MACHINERY CONTRACTS, valued at more than £700,000, were concluded with British firms by the Chinese textile machinery mission before they left Britain at the end of last year, according to the *China Trade and Economic Newsletter*. Deliveries are to begin in March and are to be completed before the end of 1958.

PRIESTMAN BROTHERS, LTD., Hull, have applied ten grabs for Colvilles' new ore discharging installation at the deep water berthage at General Terminus Quay, Glasgow. Four are of 170 cu. ft., four of 140 cu. ft., and two of 70 cu. ft., 4-rope Trojan type. Two "Cob" Mark V excavators, fitted with scraper plates to clear the ore into the squares of the hatches, were also supplied for work inside the ships' holds.

H. B.

Coming Events

INSTITUTION OF MECHANICAL ENGINEERS.—*Applied Mechanics Group*. January 22, at 6.45 p.m., at the Institution, 1 Birdcage Walk, London, S.W.1; discussion on "The Measurement of Noise and Vibration." *General Meeting*. January 24, at 4.30 p.m., at the Institution; paper on "The Management Control of Small Engineering Firms," by L. Fontaine, M.Sc., J. W. Walker, B.Sc. (Eng.); and W. R. Spencer.

INSTITUTE OF METAL FINISHING.—*South-West Branch*. January 21, at 6.30 for 7 p.m., at the Grand Hotel, Bristol; paper on "Hard Chromium Plating of Gun Barrels," by R. A. F. Hammond.

INSTITUTION OF ELECTRICAL ENGINEERS.—*South-Western Sub-centre*. January 23, at 3 p.m., at the Electricity Showrooms, Bedford Street, Exeter; paper on "Safety in the Use of Portable and Transportable Electrical Equipment in Industry," by J. W. Bunting.

INSTITUTION OF PRODUCTION ENGINEERS.—*Tees-side Section*. January 21, at 7 p.m., at the College of Further Education, Cleveland Avenue, Darlington; lecture on "Nuclear Power and its Effect on the Production Engineer," by I. Munro, B.Sc. *Derby Section*. January 24, at 7 p.m., at the College of Art, Derby; lecture on "We Build the Jig Mill," by S. C. Fenton. *Manchester Section*. January 27, at 7.15 p.m., at the Reynolds Hall, Manchester College of Science and Technology, Sackville Street, Manchester; lecture on "Plastics Material in Engineering," by A. P. Clark. *Stoke-on-Trent Section*. January 27, at 7.30 p.m., at the Grand Hotel, Hanley, Stoke-on-Trent; lecture on "Nuclear Power and its Effect on the Production Engineer," by I. Munro, B.Sc. *Oxford Section*. January 21, at 7.30 p.m., at S. Smith & Sons, Witney Airfield, Witney, Oxon.; lecture on "Copy-turning and Its Development," by a representative of Vaughan Associates, Ltd. A film will also be shown.

Melting Furnace Film

A 16-mm. sound film, concerned with the 6-cwt. capacity carbon-rod resistor furnace which is installed at the experimental foundry of the British Steel Castings Research Association, East Bank Road, Sheffield, 2, has been made by the Association's own film unit. Originally produced to illustrate the inaugural lecture of the recently announced exchange series between the B.S.C.R.A. and the Steel Founders' Society of America, this 15-min. film describes in detail the construction and operation of this steelmaking furnace which was the first of its type to be ordered for installation in this country. The film is available to non-members of the Association on payment of a hire charge of £5 5s. 0d., and application should be made to the Secretary of the Association at the above address.

Productivity Council Conferences

The British Productivity Council, North London Productivity Committee, has arranged the following conferences which will be held in the Council Chamber, Federation of British Industries, 21 Tothill Street, London, S.W.1.

Production Control, March 13. Subjects to be discussed include reduction of variety; streamlining small quantity, complex production; flow production; and computers in the service of production.

Work Study—the Universal Load, May 15. Aspects considered will include method study; organization and methods; fatigue study; work measurement; time study; analytical estimating; memo motion analysis; and predetermined motion line systems.

Further particulars may be obtained from the Hon. Secretary, Mr. Charles Cooper, M.I.Prod.E., A.M.I.I.A., 125 The Ridgeway, Enfield, Middlesex.

Women in Engineering

(Continued from page 119)

portion of women among students of technical subjects is estimated to be less than 1 per cent. For comparison, it may be noted that in the U.S.S.R. about 50 per cent of the students of engineering and technological subjects are women. While it is not suggested that we should emulate everything that is Russian, it does appear that the intake of women into our engineering and allied professions is disproportionately small. The handful of women engineers who have already achieved professional status in this country, and who are working as planning engineers, designers, aero-dynamicists, and development engineers, for example, have demonstrated that, given the requisite training, women can contribute as much as men to output and efficiency. Increasing facilities should be provided, therefore, for young women of ability and initiative to enter the engineering and allied professions, and they should be given every encouragement to play a fuller part in our industrial life than hitherto.

Industrial Notes

THE PULSOMETER GROUP inform us that their London office is now at Pulsometer House, 20-26 Lamb's Conduit Street, W.C.1. Telephone number, Holborn 1402.

G.A. PRECISION PRODUCTS, LTD.—The address of this company is now No. 2 Factory, Darkes Lane, Potters Bar, Middlesex (telephone number, Potters Bar 6895).

B.E.L.A. MACHINE TOOLS, LTD.—The head office of this company is now at Burton Chambers, Church Alley/Church Street, Liverpool, 1 (telephone number, Royal 7443; telegraphic address, Belaliv, Liverpool, 1).

WESTOOL, LTD., St. Helen's Auckland, Co. Durham, have begun publication of a house journal entitled "Expansion." The first issue includes an article on D.C. solenoid design, and notes on the new Westool factory.

THE 1958 ELECTRICAL ENGINEERS EXHIBITION will be held at Earls Court, London, from March 25 to 29. It will occupy an area of 450,000 sq. ft., and there will be approximately 400 exhibitors.

STANLEY WORKS (GREAT BRITAIN), LTD., Rutland Road, Sheffield, 3, have introduced a range of masonry drills with tungsten carbide tips in sizes from No. 3 to No. 30L. A resharpening service for these drills is maintained.

HIGH SPEED STEEL ALLOYS, LTD., Widnes, Lancashire.—A recent issue of the *Alloy Metals Review*, published by the company, contains an informative article on "molybdenum for high strength at high temperatures."

M. C. LAYTON, LTD., who have been established for 21 years, have opened a branch office at 23 Newton Street, Birmingham, 4, which is under the direct control of Mr. Layton. Mr. R. Mitchell and Mr. D. Warren have been appointed as additional representatives.

THE INDUSTRIAL WELFARE SOCIETY (INC.), Robert Hyde House, 48 Bryanston Square, London, W.1, are holding a conference at Brighton from January 24 to 27. At this conference, foremen and managers—attending in equal numbers—will consider problems of mutual importance.

PERMALI, LTD.—The address of the London office of this company, and of the associated companies, Hordern Richmond, Ltd., and Hydulignum-Jabroc (Tools), Ltd., is now 39 Victoria Street, S.W.1. The telephone number (Abbey 6494) has not been changed.

THE BRITISH MOTOR CORPORATION, LTD., Longbridge, Birmingham, report a production of nearly 450,000 vehicles in 1957, which represented an increase of 33½ per cent as compared with the 1956 total. Of last year's output, nearly 220,000 vehicles were exported, with a value, including service parts, of almost £100 million.

AN AUCTION SALE OF MACHINE TOOLS, clothing and miscellaneous stores from M.O.S. Sub Depot, Lily Lane, Byley, Middlewich, Cheshire, will be held at New Islington Public Hall, Ancoats, Manchester, on January 28 and 29.

The auctioneers will be J. H. Norris & Son (Dept. N), Albert Square, Manchester, 2.

THE DIAMOND SCREW & COTTER CO., LTD., Cherrywood Road, Bordesley Green, Birmingham, 9, recently celebrated the 50th anniversary of the establishment of the business. A jubilee folder, which has been issued, shows typical products including high tensile bolts and studs, gear levers and tapered parts, brass turned parts and inserts, and valve bodies and parts.

THE PROFESSIONAL AND EXECUTIVE REGISTER of the Ministry of Labour and National Service is now at City of London Employment Exchange, Atlantic House, Farringdon Street, E.C.4 (telephone number, City 5020). The register is intended not only to assist employers in filling senior executive and management posts, but also to help them in recruiting trainees for executive positions.

THE YORKSHIRE COPPER WORKS, LTD., Leeds, report that the negotiations for a merger of the business with the corresponding section of the METALS DIVISION of IMPERIAL CHEMICAL INDUSTRIES, LTD., have now been virtually completed, and the proposals will be submitted to shareholders for approval at an extraordinary general meeting on January 27.

EMPLOYMENT IN MANUFACTURING INDUSTRIES.—In October the number of persons employed in manufacturing industries rose by 20,000 from 9,217,000 to 9,237,000. In "engineering, metal goods and precision instruments" there was an increase of 7,000, in "vehicles" an increase of 3,000, and in "metal manufacture" an increase of 1,000.

LEEMANS BROS. (PTY.), LTD., Metal Lane (Bottom of Kloof Street), Cape Town, are interested in manufacturing, under licence, metal products for household, agricultural, and industrial purposes. They state that they have well equipped press and machine shops and tool-room. They would also consider the production and marketing, locally, of injection moulded plastics items.

AVONMOUTH ENGINEERING SERVICE, LTD., St. Andrews Road, Avonmouth, Bristol, are engaged in the construction of large steel structures and pressure vessels for oil refineries and chemical works. Since this company was formed ten years ago its activities have been expanded to embrace the production of component parts for a wide range of assemblies used in the construction of conveyors and elevators for handling various materials. The facilities include a well-equipped machine shop.

AN ULTRAPHOT II AUTOMATIC CAMERA MICROSCOPE, stated to be the first to reach this country, was recently delivered to Standard Telecommunication Laboratories, Ltd., Dowlish Ford Mills, Ilminster, Somerset. Made by Carl Zeiss, Oberkochen (Degenhardt & Co., Ltd., 32 Maddox Street, London, W.1), the camera has fully automatic exposure adjusting mechanism. It can be used for visual observations and microprojection, as well as for photo-micrography.

THE BRITISH ALUMINIUM CO., LTD., have recently put into operation, at their Falkirk works, a large integrated plant for the production of corrugated aluminium sheet from coiled strip. This plant will produce sheets up to 35 ft. long with thicknesses from 0.028 to 0.064 in. The economic advantages of long sheets are considerable, since the number of laps in a given roof area can be reduced with a consequent saving in material, and in handling and fixing costs.

INDUSTRIAL WELFARE SOCIETY, Robert Hyde House, 48 Bryanston Square, London, W.1. A week-end conference for foremen and shop stewards with the theme Conflict or Co-operation will be held from February 28 to March 3 at the Hotel Majestic, St. Annes-on-Sea. A course for junior executives and management trainees on the subject of Production through People will be held from March 3 to 7 at Robert Hyde House, London. Full particulars can be obtained from Mrs. O. K. Shelley, Administrative Officer, at the above address.

THE BRITISH INSTITUTE OF MANAGEMENT, Management House, 80 Fetter Lane, London, E.C.4, is organizing a 2-day course on "the art of selling" for salesmen and sales managers. It will be held at Caxton Hall, London, on March 13 and 14, and will be conducted by Mr. Heinz M. Goldmann, a leading European consultant in sales training. This course, it is suggested, will afford businessmen an opportunity of "preparing for the competitive atmosphere of the European common market and free trade area."

KAYSER, ELLISON & CO., LTD., are to open a new warehouse next month at Station Road, Coleshill (telephone number, Coleshill 2041-2). This warehouse will have an area of more than 3,000 sq. ft. with overhead crane facilities throughout, and will be insulated and centrally heated to provide conditions suitable for the storage of centreless ground as well as black bars. Initially the stock will comprise a range of the company's well known K.E. steels suitable for such applications as blanking and other press tools, gauges, die casting dies, plastics moulds, cold heading dies, punches, ejector pins, drill bushes and dowels, also tool bits.

THE INTERNATIONAL INSTRUMENT SHOW to be held at Caxton Hall during the week commencing March 24 will be nearly 30 per cent larger in floor area than the 1957 exhibition, and will occupy the Great Hall and Court Room.

It is expected that more than 60 firms from 10 countries will participate. Normal day opening hours will be from 10.30 a.m. to 6.30 p.m., but to facilitate the attendance of parties of students and apprentices, the Show will remain open until 9 p.m. on March 26, and until 12 noon on March 29. Tickets are available on request from the sponsors, B. & K. Laboratories, Ltd., 57 Union Street, London, S.E.1.

CANADIAN BRITISH ALUMINIUM CO.—It is reported that, less than 20 months after work began on clearing the site, the first metal was poured recently at the new aluminium smelting plant of the company at Baie Comeau in the Province of Quebec on the north shore of the St. Lawrence

River, 400 miles north-east of Montreal. This company is a subsidiary of the British Aluminium Co., Ltd., and was formed in partnership with the Quebec North Shore Paper Co.

The event marked the completion of the first of four production stages for the £50 million plant which will eventually have an annual capacity of 160,000 long tons of virgin aluminium ingot. It may be noted that this ultimate capacity represents two-thirds of the present annual consumption of virgin aluminium ingot in the United Kingdom.

THE IRON AND STEEL BOARD reports that steel production in 1957 is expected to have reached about 21.7 million tons compared with the estimate of 22.3 million tons for possible production made at the beginning of the year. The output should, however, be a million tons greater than in 1956.

The shortfall of 600,000 tons on the estimate is attributed to a drop in the demand for tinplate; running down of stocks; delay in bringing new finishing equipment into operation; and the strike in the engineering industry in the spring. There has also been a tendency for consumers, particularly of light sections, to reduce their commitments, possibly because of the higher interest rates now ruling.

Steel production in November averaged 429,200 tons a week, compared with 437,800 tons in October, and 426,400 tons in November, 1956. For the first 11 months of the year, production was 5.4 per cent above that of the corresponding period of 1956. Pig iron production in November was at the rate of 281,500 tons a week, as against 285,500 tons in October, and 262,700 tons in November, 1956.

The Price of a Subscription to MACHINERY is 52 Shillings per annum, post free, to any part of the world.

Subscribers are not bound for any definite period of subscription. We send MACHINERY, post free, each week until told to stop. Subscribers can pay yearly, half-yearly, or quarterly, pro rata. (Cash with order)

To MACHINERY, National House, 21 West Street, Brighton 1

Please send me/us MACHINERY every week until I/we tell you to stop, for which I/we enclose remittance of 52 Shillings per annum or pro rata

Name

Address

.....

* Position

* From

* For our mailing records only.

17/1/58

Personal

MR. A. V. IDDY, assistant secretary of Samuel Osborn & Co., Ltd., Clyde Steel Works, Sheffield, 3, has been appointed a local director of the company.

MR. K. L. STRETCH has been appointed director of the Central Engineering Establishment of the National Coal Board at Bretby, South Derbyshire. He was formerly deputy director of the Establishment and has been acting director since the death of Mr. L. H. Daniel in September.

DR. A. D. MERRIMAN, G.C., O.B.E., D.L., M.A., M.Ed., D.Sc., C.I.Mech.E., F.R.S.E., formerly secretary of the Institution of Metallurgists, has been appointed by Edgar Allen & Co., Ltd., Imperial Steel Works, Sheffield, 9, as consultant on scientific projects.

MR. W. FORD, since 1951 a sales engineer at the Swansea office of Brook Motors, Ltd., Empress Works, Huddersfield, has been transferred to the Birmingham office to succeed Mr. H. C. CURTIS, who has left the company to take up an appointment abroad.

MR. D. J. GUILD, A.M.I.B.F., has recently joined the staff of Armstrong Whitworth (Metal Industries), Ltd., Gateshead, and Jarrow Metal Industries, Ltd., Jarrow, as technical representative in the Midlands area, under the Midlands manager, Mr. J. Bell, Somerset House, Temple Street, Birmingham.

MR. A. P. GIBBS, hitherto North West area manager for Ransome & Marles Bearing Co., Ltd., Newark-on-Trent, has taken up an appointment at the company's head office. MR. H. V. WILLDER is now manager of the Manchester office assisted by Mr. E. L. PATON, and Mr. G. H. WALKER, formerly stores supervisor, is Liverpool sub-office manager.

MR. G. H. BUCHANAN, who for the past 14 years has been the representative in Scotland for Craven Brothers (Manchester), Ltd., Stockport, retired recently. He has been succeeded by Mr. H. PROBERT, who will also be in charge of the company's new office in Scotland at 157 West George Street, Glasgow, C.2.

MR. A. H. HIRD, A.C.G.I., B.Sc., M.I.Mech.E., has been appointed to the board of directors of Vickers, Ltd., Vickers House, Broadway, Westminster, London, S.W.1. He is a director of Vickers-Armstrongs, Ltd., and Metropolitan-Cammell Carriage & Wagon Co., Ltd., and chairman of several wholly-owned subsidiaries of Vickers, Ltd.

MR. JOHN DUNKERLEY, for the past two years manager of Henry Broadbent, Ltd., Sowerby Bridge, Yorks, a subsidiary of Kerry's (Great Britain), Ltd., has been appointed a director of the former company. Mr. Dunkerley was for 20 years associated with Textile Machinery Makers, Ltd., Oldham.

MR. T. WORSNUP, engineering department manager of Ransomes & Rapier, Ltd., Ipswich, has retired after 43 years' service with the company. After serving his apprenticeship with Joseph Booth & Bros., Rodley, near Leeds, he joined the engineering staff of Ransomes & Rapier in April, 1915. He has been responsible for the design and development of many types of Rapier cranes.

MR. W. A. C. MCINTYRE, formerly technical sales manager of Fielding & Platt, Ltd., has joined Reed Brothers (Engineering), Ltd., Replant Works, Woolwich Industrial Estate, London, S.E.18, as a director. He will be chiefly responsible for expanding the company's manufacturing programme of hydraulic presses in their new and larger works and machine shop.

MR. K. DRUCE, D.F.H., A.M.I.E.E., has been appointed manager of the Bristol office of the English Electric Co., Ltd., with responsibility for the South-West of England territory, in succession to Mr. T. Robinson. MR. H. GRANVILLE-BROWN, A.I.E.E., has taken charge of the Southampton office of the company, which has moved to new premises at 29 Shirley Road, Southampton. In this position he succeeds Mr. I. Mackintosh.

DR. C. HOELZER, senior partner and managing director of Th. Kieserling & Albrecht, Solingen, recently celebrated his 75th birthday. He has been associated with the firm for many years, and took over the technical management at the early age of 32. In recognition of his work as a designer he was appointed an honorary member of the Technological College of Hanover, and was awarded an honorary doctor's degree by the College of Darmstadt.

Just before the end of the war the company's premises were completely destroyed, and it was largely due to the energy of Dr. Hoelzer that they were rebuilt and equipped. Today more than 1,000 people are employed in the production of mechanical presses, special machines for the forging industry, bolt and nut machinery, and standard and special cold forming machines.

U.S. Machine Tool Exports

The following table gives the quantities and values of exports of various classes of machine tools from U.S.A. during April, 1957:

	Number	Value, \$
Engine and tool room lathes ..	73	212,881
Light duty and bench lathes ..	233	78,335
Turret lathes	16	220,074
Other lathes	106	1,610,942
Vertical boring and turning mills ..	1	63,848
Boring machines	37	1,145,728
Tapping and threading machines ..	132	282,712
Milling machines	79	701,539
Gear-cutting machines	64	922,390
Gear-grinding and finishing machines	17	258,528
Drilling machines	165	333,844
Planing, shaping and slotting machines	17	120,070
Surface grinding machines	52	255,135
Tool and cutter grinding machines ..	92	251,762
Other grinding machines	77	1,848,013
Honing and lapping machines	18	61,916
Broaching machines	9	203,115
Sheet and plate metal-working machines	415	3,568,964
Forging machines and hammers	43	1,081,611
Metal forming machines	—	978,785
Other machines	994	959,386

PRICES OF MATERIALS

All prices per ton except where otherwise stated.

Pig-Iron

Foundry and Forge
No. 3, Class 2

Middlesbrough zone
Birmingham £21 6 0
£20 18 3

Phos. 0.1 to 0.75%
Birmingham £23 17 0

Scottish Foundry
Grangemouth £25 3 6

Hæmatite

English No. 1

N.E. and N.W. Coast £25 6 6

Scotland £25 13 0

Sheffield £26 15 0

Birmingham £27 4 0

Welsh £25 6 6

Steel Products

Medium plates £46 1 6

Mild steel plates, ordinary* £42 12 0

Boiler plates* £45 2 0

† Flat bars 5 in. wide and under } £40 8 0

† Round bars under 3 in. } £33 1 6

Billets, rolling quality, soft U.T.

Phosphor Bronze

Ingot (2B8) (A.I.D.) d/d Nominal

Copper

Cash (mean) £173 7 6

Cold rolled and hot rolled Sheets

4 ft. by 2 ft. by 10 SWG £243 10 0—£243 15 0

Rods $\frac{1}{2}$ in. to $\frac{1}{4}$ in. diam. £261 5 0

Tubes, $\frac{1}{2}$ in. bore by 10 SWG, ton lots, per lb. 2s. 6½d.

Wire rod, black, hot-rolled ($\frac{1}{4}$ in.) £192 17 6

English

Zinc

Refined, minimum 98 per cent. purity,

current month (mean) £62 12 6

Brass

Tubes, solid draw, per lb. 1s. 5½d.

Strip 63/37, 6 in. by 10 SWG coils,

ton lots £209 5 0—£211 15 0

Rods, $\frac{1}{2}$ in. diam. (59 per cent copper) 1s. 8½d.

Yellow Metal

Condenser plates, per ton £147 0 0

Rods, per lb. 1s. 9½d.

Aluminium

Ingot min. 99.5 per cent

Canadian d/d £197 0 0

Lead

Refined, minimum 99.97 per cent

purity, current month (mean) £72 12 6

Tinplates

‡ U.K. Home trade:

Handmill f.o.t. makers' works £3 12 4½

Cold reduced, f.o.t. makers' works £3 8 0½

U.K. Export:

Hot rolled basis, f.o.t. 74s. 0d.—75s. 0d.

Cold reduced basis, f.o.t. 76s. 0d.—76s. 6d.

work's port

Gunmetal

Ingot, 85.5.5.5. ex works £166 0 0

* N.E. Coast, N. Joint Area, Central

Scottish Zone.

† U.T. soft basic.

‡ Official maximum price, after allowing for

adjustments for increase in price of tin.

MAKERS' PRICES

Hexagon Steel Bars¹

Sizes in inches from 0.7049 up to 2.21 and 2.41 s/f, ex works £43 4 6

Free cutting black £47 10 0

Reeled Steel Bars¹

Single-reeled $\frac{1}{2}$ in. upwards, f.o.t. works (+ usual extra for sizes) £43 17 6

Free cutting £48 2 6

High-Speed Steel

Black random length bar. All prices basic, per lb., subject to extras.

Molybdenum "66" 6s. 0½d.

Molybdenum "46" 5 10½d.

14 per cent tungsten 6s. 3d.

16 per cent tungsten 6s. 8½d.

18 per cent tungsten 7s. 0d.

22 per cent tungsten 8s. 3d.

5 per cent cobalt 10s. 2d.

4.75/5.25 per cent molybdenum + 6.0/6.75 per cent tungsten + 1.75/2.05 per cent vanadium (5-6-2) 6s. 2½d.

Precision-ground, High-speed Free-turning Brass Rod²

$\frac{1}{8}$ -in. dia. \pm 0.00025-in. 2-ton lots, per lb. 2s. 3½d.

Grey Iron Rod

Die Cast³ in random lengths 18 in. to 24 in. rough machined $\frac{1}{2}$ -in. above listed size. Extra for definite lengths, for hardenable alloy iron, and for orders of less than £50. Discounts for orders over £150.

Per cwt. net.

Mark I Mark III

$\frac{1}{2}$ or $\frac{3}{8}$ in. 255s. 6d. 318s. 10d.

1 or $\frac{1}{2}$ in. 204s. 4d. 251s. 10d.

$\frac{1}{4}$ to $\frac{1}{2}$ in. 143s. 0d. 171s. 2d.

$\frac{1}{4}$ to 2 in. 106s. 2d. 125s. 11d.

2½ to 3½ in. 91s. 6d. 106s. 4d.

3½ to 12 in. 86s. 6d. 99s. 2d.

Continuous Cast

10-ft. lengths, centreless machined $\frac{1}{2}$ to 3-in. dia. + 0.010 to 0.020 in., prices as quoted for die cast bars³

6-ft. lengths $\frac{1}{2}$ or $\frac{3}{8}$ in. 245s. 4d.

centreless ground 1 or $\frac{1}{2}$ in. 196s. 4d.

+ 0.010 in. Extra 1½ to 1½ in. 137s. 10d.

for hardenable alloy iron⁴ 1½ to 2 in. 106s. 2d.

Per cwt. net. 2½ to 3 in. 91s. 6d.

Stellite⁵

Welding Rods (plain)

$\frac{1}{4}$ in. dia. per lb. 30s. 0d.

Toolbits

$\frac{1}{4}$ in. sq. \times 4 in., each 22s. 3d.

Precision-ground Mild Steel¹

1-in. dia. \pm 0.00025-in. 121s. 6d.

4-ton lots, per cwt.

1 Colvilles, Ltd., Glasgow, and 17 Grosvenor

Street, London, W.1. 3 Pratt, Lavick & Co.,

Ltd., Chester. 3 Sheepbridge Alloy Castings,

Ltd., Sutton-in-Ashfield. 4 "Flocast," Harold

Andrews Sheepbridge, Ltd., Halesowen.

6 Deloro Stellite, Ltd., Highlands Road,

Shirley, Solihull.

BASIC PRICES FROM LONDON STOCK⁶

Free Cutting Steel

Bright cold drawn:

(Usaspeed) over $\frac{1}{2}$ to 2 in. £59 17 6

Lead bearing (Usaled) £63 17 6

Precision ground, $\frac{1}{2}$ in. £81 12 6

Bright Drawn

M.S. bars (M.M.C.) over $\frac{1}{2}$ in. to 2 in. £55 8 6

Square edge flats (Usafiat) £72 5 0

M.S. angles (Usaspeed) £99 10 0

Casehardening (EN) (Usacase) over $\frac{1}{2}$ in. to 2 in. £63 14 6

M.S. bars (EN3B) (Usamild) over $\frac{1}{2}$ to 2 in. £57 8 6

Carbon manganese semi-freecutting case hardening (EN202) (Usaspeed 202) over $\frac{1}{2}$ to 2 in. £71 14 0

35/45 ton tensile (EN6) (Usen) over 1 to $\frac{1}{2}$ in. £65 2 6

0.4 Carbon Normalised (Usaspad "40") over $\frac{1}{2}$ to 2 in. £67 4 6

Carbon manganese steel to Specification EN.16.T (Usaspeed 5565), per ton £127 10 3

Ground Flat Stock

18-, 24-, and 36-in. lengths (Usaspeed). List prices less 5 per cent.

Oil Hardening Cast Steel

Non-shrink (Usaspeed N.S.O.H.) $\frac{1}{2}$ in. to 2½ in., per lb. 1s. 11d.

Non-distorting heavy duty (Usaspad M.C.H.C.) $\frac{1}{2}$ -in. to 2½-in., per lb. 4s. 2d.

Silver Steel

(0.194-in. to $\frac{1}{4}$ -in.)

Genuine Stubs quality, per lb. 4s. 6d. less 27½%

M.M.C. quality, per lb. 2s. 5d. + 6½%

Boxes of 16 assorted sizes $\frac{1}{8}$ -in. to $\frac{3}{4}$ -in. dia. 7s. 6d.

Stainless Steel

K.E. 40.AM (Freecutting), per lb. 3s. 3½d.

Glacier Machined Bronze Bars

Phosphor bronze (2B8) } Prices on application

Lead bronze }

High-speed Steel

18 per cent. tungsten. Prices on application.

Toolholder bits:

Usaspeed "Super" } List price

" "Supreme" }

" "Cobalt 10" }

Shimstock

Steel assorted, per tin 3s. 6d.

Brass " " 7s. 3d.

6 Macrae's Metal Co., Ltd., Pantenville

Road, N.I. Subject to confirmation by

London Office. Delivered free by van in

London area.

ARNO**TYPE 3V
VERTICAL
MILLER**

Table w.s. 63" x 15"
Spindle speeds (20)
30—1,200 rpm.
Power traverses
5½" x 14½" x 21½"
Table feeds (16)
.281"—22" per min.
H.P. 17
Weight 7040 lbs.

- ★ Swivelling and sliding head
- ★ Power feeds in three directions
- ★ Rapid traverses with single lever control
- ★ Centralised grouping of control levers
- ★ Hardened and ground gears
- ★ Schlessinger limits

Sole Agents

PIDGEN BROS

LIMITED

HELMET ROW, OLD STREET
LONDON, E.C.1.

Telephone Clerkenwell 6481



*Re-surfacing
to Precision Limits*

OF
**SURFACE PLATES SURFACE TABLES
CAST IRON & STEEL STRAIGHT EDGES**

GRADE 'A' HAND SCRAPPED AND SURFACED TO WITHIN
0.0001in.—0.0003in. FROM A MEAN TRUE PLANE
OVER WHOLE SURFACE ACCORDING TO SIZE.

GRADE 'B' SMOOTH PLANED FINISH ACCURATE TO 0.001in.
—0.003in. ACCORDING TO SIZE.


WINDLEY BROS. LTD. CROWN WORKS CHELMSFORD

TELEPHONE: CHELMSFORD 2224

When answering advertisements kindly mention MACHINERY.

ELECTRO-MAGNETIC CLUTCHES

by *Burnand*




Designed to suit your requirements

For applications requiring continuous, accurate, reliable, smooth drives with frequent operation at any speed, the Burnand Electro-Magnetic Clutch is unequalled. It can be operated automatically, or by remote control and its simple construction makes it cheap to run and maintain.

The Burnand Electro-Magnetic Clutch is fitted by leading machine tool manufacturers and is used extensively for planing machine drives where a reversing clutch is required; it is also ideal for converting old planer drives to give faster operation.

Please write for further details

W. E. BURNAND & SON, LTD., 66-106, SHOREHAM ST., SHEFFIELD 1, ENGLAND.



All types of press work up to 150 tons—any metal


Deep draw work a speciality

**Also milling, drilling
capstans and assemblies**

Corfield & Buckle Ltd

TRAFALGAR WORKS • MERTON ABBEY • LONDON S.W.19
Telephone: LIBERTY 1144 (7 lines)





Drilling and counter-boring Nimonic 80 turbine blades on a Herbert two-spindle drill using "Ilocut" LA.30., at the de Havilland Engine Company's Leavesden works.

"ILOCUT"

NEAT CUTTING OILS

— used by **THE DE HAVILLAND ENGINE CO. LTD.**

"They possess exceptional cutting and surface finish properties . . . and cooling qualities which ensure long tool life between regrinding".

Those are the outstanding reasons for the pre-eminence of the "Ilocut" range of Neat cutting oils. In the de Havilland group the Engine Company and the Propeller Company both use "Ilocut". Also, in common with the de Havilland Aircraft Company, they use many of our other oils. May our technical engineers call, and tell you all about our production oils? Also available to your company, a complimentary copy of "Cutting & Metalworking Oils".



WAKEFIELD-DICK INDUSTRIAL OILS LTD. • 67 GROSVENOR STREET, LONDON, W.1

A MEMBER OF THE WORLD-WIDE WAKEFIELD CASTROL ORGANISATION

When answering advertisements kindly mention MACHINERY.

Captains of Industry

Industrialists and all businessmen must today accept and overcome rising basic costs in the face of increasing competition. To intensify mechanisation immediately is the bold but necessary decision of progressive management.

Whatever the purpose, whatever the field—production, distribution, transport or other allied services—appropriate and attractive credit facilities are available through EQUITY.

EQUITY caters for all programmes all-embracing or partial.

Enquire now about an EQUITY plan.

EQUITY CREDIT

COMPANY LIMITED

INDUSTRIAL BANKERS


24, Berkeley Square, London, W.1.
Telephone: MAYfair 9090.

Midlands Office:

88/89, Darlington Street,
Wolverhampton, Staffs.

Telephone:

Wolverhampton 26545.



**More accurate
than human skill
itself**-----



Hydraulic Control of motion

Paradoxically, the product of human skill is more accurate than human skill itself. This is particularly so in the case of Savery Hydraulic Pumps. Countless thousands of Savery Pumps are in use throughout the world working with precision that neither human skill nor other means can match. Next time you're considering control of motion, remember Savery Hydraulic Pumps first.

Savery Pumps can be supplied with fixed or variable delivery.

**FOR FURTHER DETAILS OF
SAVERY HYDRAULIC PUMPS**

WRITE TO
THOMAS SAVERY PUMPS LIMITED
BRACEBRIDGE STREET · BIRMINGHAM 6
Telephone: ASTon Cross 1316-7

'FLUON' increases production in the Chemical Industry—No.2

C.F. 2 Single Bellows Pump
Unit made by Crane Packing
Ltd. The bellows and other
components are made from
'Fluon' p.t.f.e.



New pump made with 'Fluon' can now handle highly corrosive chemicals

A PUMP which has to handle corrosive chemicals has special problems of design. 'Fluon' polytetrafluoroethylene was able to solve these problems. All points which come into contact with these fluids in this new bellows pump have been made from 'Fluon'. It can therefore handle all known chemicals and solvents except fluorine and molten alkali metals. The pump has been used for such highly corrosive liquids as mixed hydrochloric and nitric acid. It is also suitable for really pure liquids such as triple distilled water because the non-contaminating properties of 'Fluon' make it easy to keep clean.

This use of 'Fluon' p.t.f.e. exploits its chemical inertness, toughness and flexibility. Bellows made from 'Fluon' are suitable for use as flexible connectors for pipes, sleeves and shaft stands which

operate in contact with corrosive chemical solvents and lubricants. They have many uses in hydraulic power and control systems and in fluid pressure operated devices such as meters and governors.

'Fluon' is non-adhesive, non-wetting and has a remarkably low coefficient of friction. It is tough, resilient and flexible, with a very low permittivity and power factor and good dielectric strength. Its working temperature range is from $-80^{\circ}\text{C}.$ to $250^{\circ}\text{C}.$ 'Fluon' is every day finding new and invaluable uses in the chemical industry.

'FLUON'

'Fluon' is the registered trade mark for the polytetrafluoroethylene manufactured by I.C.I.



PF.32

IMPERIAL CHEMICAL INDUSTRIES LIMITED · LONDON · S.W.1


When answering advertisements kindly mention MACHINERY.

COOKE

OPTICAL CHINOMETER

The accuracy of this instrument is in no way dependent on screws, worms or racks. The graduations are carried on a glass circle and are read by a high power microscope giving a clear reading to one minute of arc against a brightly illuminated background. The cast iron base is of vee and plane construction.

Fully described in publication CE 600.



Cooke Troughton & Simms

LTD

Y O R K & L O N D O N

SUMMIT

MILLING CUTTERS · SLITTING SAWS
REAMERS · GEAR CUTTERS · HOBS
END MILLS · PARTING OFF TOOLS
CIRCULAR SHEARING CUTTERS
BEVEL KNIVES · CIRCULAR FORM
TOOLS

JOSEPH THOMPSON (SHEFFIELD) LIMITED

Townhead Street Engineering Works, Sheffield 1, England

Telephones: 24021 (Three lines)

Telegrams: "Summit, Sheffield"



why pick on us?

Lines Brothers hailed us aboard to pressure die cast their Tri-ang model outboard motor "Swordfish." By helping to simplify the design, we were able to do the job in five aluminium alloy castings, combining lightness and strength. Time, money and labour were saved—as they invariably are when you pick on us. We're ready to produce aluminium or zinc base alloy castings in almost any size or quantity... except, if you please, very tiny castings or very short runs.


the whole in one

BRITISH DIE CASTING AND ENGINEERING CO., LTD.

EDWARD ROAD · NEW BARNET · HERTS · TEL: BARNET 9211
ALSO AT WEST CHIRTON TRADING ESTATE NORTH SHIELDS
NORTHUMBERLAND · NORTH SHIELDS 2100



When answering advertisements kindly mention MACHINERY.



ONE OF MANY DIFFERENT TYPES OF MACHINES

SAVED!

by

BROCKHOUSE MACHINE TOOL REBUILDING SERVICE

Why not consult us about that one-time useful machine tool which is now standing idle? We have a comprehensive machine tool rebuilding service available for LATHES, AUTOMATICS, SHAPERS, PRESSES, and DIE CASTING MACHINES. Machines are completely stripped, parts replaced, and when rebuilt carry our six months' guarantee.

SEND FOR DESCRIPTIVE LEAFLET

BROCKHOUSE

J. BROCKHOUSE & CO. LTD.

Machine Tool Division

ELM WORKS, WOLVERHAMPTON

Tel.: 23801



The **SEGIC** DOUBLE ACTION BENDING MACHINE

Permits rapid economical forming and duplication of an almost infinite variety of components with consistent accuracy, to very close limits. Eliminates the expense involved in the preparation of conventional press tools.

Write for specification and prices to



MORTIMER
ENGINEERING CO.
PROPRIETORS: S. GUTTMAN & SONS LTD



Sales Office: 204-6 Acton Lane, Harlesden, N.W.10.

Telephone: ELGar 4833

HEAT TREATMENT



- * Capacity for case-hardening is now available in the most modern heat-treatment plant in London.
- * Gas or pack carburising with full metallurgical control over all operations.
- * Gleason quenching press equipment for pieces up to 36in. dia. plus wide experience in the control of distortion.
- * Flame-hardening of gears up to 10ft. dia. with latest electronically controlled equipment.

E.N.V. ENGINEERING COMPANY LIMITED


HYTHE ROAD, WILLESDEN, N.W.10

Tel: LADbroke 3622-3-4-5-6

APT9

When answering advertisements kindly mention MACHINERY.

12 1/2" heavy duty CENTRE LATHE




These notable features, allied with superior quality in every stage of design and manufacture have made Crowthorn lathes famous for high speed precision work under exacting conditions. Reasonable delivery times. Please write for illustrated literature.

CROWTHORN
HIGH CLASS MACHINE TOOL MAKERS

CROWTHORN ENGINEERING COMPANY LIMITED
REDDISH STOCKPORT ENGLAND
Phone: STOCKPORT 7271-23 Grams: CROWTOOL, REDDISH

GET 'COOLANT SMOG' OUT OF THE WORKS



- Gives positive control of oil mist and fume produced by high speed cutters and grinders.
- Reduces fire and health hazards.
- Completely self-contained; no expensive ducts needed.
- Collects up to 10 gallons of oil a day for re-use.
- Returns clean air immediately to work room without heat loss.



Electro-MIST

Electrostatic precipitator for the collection of oil mist and fumes.

For full details contact the sole manufacturing licensees in Great Britain for products of the American Air Filter Co., Inc.:-

AIR CONTROL INSTALLATIONS LIMITED

RUISLIP · MIDDLESEX · RUISLIP 4066

London
Birmingham
Manchester
Newcastle
Glasgow

"QUICKIE"

COLLET FIXTURE

9/16" CAPACITY
**RAPID CLAMPING -
FOR FAST PRODUCTION**

Manufactured by
ERMA LIMITED
MOUNT PLEASANT · ALPERTON · WEMBLEY · MIDDLESEX
Telephone: WEMBLEY 3691-5 Telegrams: ERMOBIL WEMBLEY

CUT COST - SAVE TIME - SPEED PRODUCTION

UNIVERSAL DRILLING JIG 'REGLUS'


THE 'REGLUS' Drill Jig is designed to simplify and rationalize present - day drilling practice.

The measuring, straightening and trial-drilling operations hitherto necessary, the marking-out and centre-punching of the work, and the production of expensive special-purpose jigs, are all dispensed with.

The 'REGLUS' can be adapted to any individual drilling job in a matter of seconds and may be set directly from any blueprint with the greatest of ease.

It can be used whether the workpiece is cylindrical, square, rectangular, multi-angular, spherical or flat. It enables accurate drilling on prototype, toolroom work and on batches of components.

The vernier settings ensure complete accuracy for a multiplicity of jobs which could otherwise only be obtained with individual special-purpose jigs.




FRED FERRARIS (CLERKENWELL) LTD. 14 NORTHAMPTON SQUARE, LONDON, E.C.1

Telephones: CLERKENWELL 2676-7

BROADBENT

SURFACING AND BORING

Lathes



17" to 36" SWING

The illustration shows a 32" to 36" swing machine ; other sizes are available from 17" to 28" swing.

This is only one of the fine range of robust heavy-duty Broadbent lathes, which have gained an unsurpassed reputation for reliability throughout the world.

Models can be supplied with any bed length required, with or without screw-cutting, hexagon, or square turret, and with special slides, to order.



HENRY BROADBENT LIMITED

SOWERBY BRIDGE, YORKS.

Telephone : HALIFAX 81331

BAS/HB/2

When answering advertisements kindly mention MACHINERY.



TYPE




WORM REDUCTION GEAR UNITS

WITH 3', 4', 5' & 6' CENTRES

These fan cooled 'S' Type Units are designed for maximum power capacity and rigidity in operation. Manufactured in 4 sizes and capable of transmitting up to 30 HP dependent upon input speed and ratio required.

Comprehensive literature and drawings supplied on request.



THE **MOTOR GEAR & ENGINEERING CO. LTD.**

ESSEX & CORONA WORKS • CHADWELL HEATH • ESSEX • Phone: SEVEN KINGS 3456-7745 (10 Lines)

THE IDEAL
POWER UNIT FOR
MODERN PLANTS



Cross

THE BRITISH
* **WIRE THREAD
INSERT**

MADE FROM D.T.D. 239 WIRE
HARDENED & TEMPERED

This material is suitable for use in parts made in all metals including aluminium or magnesium. We also make stainless steel inserts suitable for use in ferrous metal parts and bronze inserts for use where full non-magnetic properties are required.



CROSS MANUFACTURING CO. (1938) LTD.
BATH • SOMERSET



**Specialists in
Tooling Equipment
And Special
Purpose Machinery**

Jig-Boring, Press Tools,
Jigs and Fixtures;
Special Purpose Machines, etc.
Manufacturers of Small
Precision Mechanical Devices.
Precision Grinding, Internal and External
also
Patterns and Castings in any Quantities.



A.I.D. Approved



RIDGE ROAD CORNER,
STONECOT HILL, NORTH CHEAM
SURREY 9 • Phone: Fairlands 8861/2.

When answering advertisements kindly mention MACHINERY.

Milling diesel crankcases



AT
ARMSTRONG SIDDELEY
(BROCKWORTH) LTD.

Galtona
TRADE MARK

O-K

SERRATED BLADE CUTTERS

Bearing Cap Seatings are finished in one pass using a pair of "Galtona-O.K." 16½" diameter 1½" wide half side cutters fitted with H.S.S. blades operating at 18 R.P.M. with 1.33" feed giving 1/4" stock removal. The cutters are stepped to produce form as will be seen from the photograph. Between 500 and 700 components are completed between regrinds, once again proving the consistent economy of "Galtona-O.K." Cutters.




Richard Lloyd Limited

GALTON HOUSE, ELMFIELD AVENUE, TYBURN, BIRMINGHAM, 24


Telephone: Ashfield 1801, Telegrams "Cogs, Birmingham"

NORTHERN AREA OFFICE: A. V. Green, Britannia House, Wellington Street, Leeds 1 Phone: Leeds 21212
LONDON AREA OFFICE: A. J. Percy, 240 Romford Road, Forest Gate, London, E.7. Phone: MARYland 2564
NORTHERN IRELAND: Garage & Engineering Supplies Ltd., 78 Great Victoria Street, Belfast.
SCOTLAND: Stuart & Houston, 5 York Street, Glasgow C.2.


BEDFORD all steel factory equipment




2



3



BEDFORD




4

1. Bench
2. Stacking Trays
3. Tool Cabinet

4. Shelving, open and closed types
5. Pallets

5



JAMES BEDFORD & Co. (HALIFAX) Ltd
 Globe Works • Victoria Road
 Sowerby Bridge • YORKSHIRE



FOR HOLES AS
 SMALL AS 0.004in.
 YOU NEED—

THE B T & D CAPILLARY DRILL

THE ANSWER TO
 PRODUCTION
 ENGINEERS'
 'HEADACHES' ON
 FINE HOLE
 DRILLING

Holes 0.004in. to 0.0625in. diameter operated from the normal compressed air line—60lb. only per square inch required—inverted drill simple to operate and adjust by unskilled labour—fuel injection nozzle drilling worries entirely eliminated—work holder body swivels to angle required—drill body adjustable on horizontal slide. Price and delivery on application.

Demonstration by appointment.

We also design and manufacture Jigs, Fixtures, Press Tools, etc. A.I.D. and A.R.B. approved.

MEMBERS OF THE GAUGE & TOOL MAKERS ASSOCIATION
 SOLE MAKERS—


BIRFIELD TOOLS & DESIGNS LTD.

BORMIN ROAD, COVENTRY.

Phone: Walsgrave-on-Avon 2372



LATHE CABINETS



for English and Continental Machine Tools


Built to the highest standards of quality and workmanship by specialists in sheet metal work who, for nearly a quarter of a century, have built up a reputation for accuracy and good appearance.

Write for full particulars to

W PINDER & SON LTD KING ST PETERBOROUGH


P.4428

When answering advertisements kindly mention MACHINERY.



WOODWORKING

RADAR EQUIPMENT



WIRE FORMING

The application of pneumatic equipment in these and other industries
is described in the current issue of

The Journal of

APPLIED PNEUMATICS

A specimen copy is available from the distributors

Martonair Limited · Parkshot · Richmond · Surrey

AD23

When answering advertisements kindly mention MACHINERY.


Taking the measure of **HARDNESS**

The Vickers Portable Hardness Tester

The Vickers Portable Hardness Tester incorporates all the well-known features of the Vickers Pyramid Hardness Testing machine. The standard Vickers Pyramid Diamond Indenter is used in conjunction with the Micrometer Ocular, so that all readings obtained are the internationally recognised VPN. Combined with this accuracy is a portability which enables it to be used over an exceptionally wide range of applications, and it is particularly useful for large and heavy components which cannot be tested by the standard Hardness Tester.

The Vickers Pyramid Hardness Testing Machine—compact in size and comprehensive in service, it enables immediate and precise testing to be carried out at the place of production.

The Vickers Portable Gear Hardness Tester—similar in principle to the general purpose Portable tester, but specially developed to measure the hardness on the pitch line of gears.



Taking the hardness of a large-diameter shaft

Please send for a catalogue giving full details.

VICKERS - ARMSTRONGS (ENGINEERS) LIMITED

13 City Road · London E.C.1.

Tel: METropolitan 8877.

Grams: Vicksbox, Ave., London.

TGA. CH61

TOOLMAKER'S DRILL CHUCK



**FOR GREATER
ACCURACY
*in less time***

MAY WE TELL YOU MORE
ABOUT IT?



MACHINE SHOP EQUIPMENT LIMITED
Spenser Street, London, S.W.1.
Telephone: VICToria 6086




Gravity
is **FREE**
set it to work with
METALRAX
GRAVITY CONVEYOR
TRACK




Write for details
METALRAX (CONVEYORS) LTD.
BORDESLEY GREEN RD., BIRMINGHAM, 9
Telephone: VICToria 4121-2. Telegrams: Metalrax Birmingham

J 3319

When answering advertisements kindly mention MACHINERY.



Save money— make **TAPER-LOCK** your standard method of fixing to shafts



Use a TAPER-LOCK Bush and fix your pulley to its shaft in less than a minute. TAPER-LOCK Bushes are interchangeable too; you can fit them to any diameter shaft. They cut out keywaying, save space and have no dangerous projections.

TAPER-LOCK Bushes are off-the-shelf stock at 19 Fenner Branches. Many Distributors at Home and overseas also stock them.

J • H • FENNER & CO • LTD • HULL

BRANCHES AT: BELFAST, BIRMINGHAM, BRADFORD, BRISTOL, BURNLEY, CARDIFF, GLASGOW, HULL, LEEDS, LEICESTER, LIVERPOOL, LONDON, LUTON, MANCHESTER, MIDDLESBROUGH, NEWCASTLE-ON-TYNE, NOTTINGHAM, SHEFFIELD, STOKE-ON-TRENT.

LARGEST MAKERS OF V-BELT DRIVES IN THE COMMONWEALTH

*When answering advertisements kindly mention **MACHINERY**.*

130 SHAFTS FACED AND CENTRED PER HOUR

Facing $\frac{1}{8}$ " off each end and drilling $\frac{7}{16}$ " centres in $2\frac{1}{2}$ " diameter Electric Motor Shafts in a floor to floor time of 27 seconds, is typical of the high production which can be achieved on the —


HEY No. 3 DOUBLE ENDED CENTRING & FACING MACHINE

- Perfect alignment of centres
- True faces and accurate lengths
- Turned finish on faces
- Eliminates subsequent facing down to centres or recentring



ENGINEERING CO. LTD.
COVENTRY

PHONE: COVENTRY 88641



We also manufacture Rotary Cam and Profile Milling Machines, Short Thread Milling Machines, Multiple Drilling Heads and Machines, Tapping Machines, Gear Tooth Rounding Machines, Special Machine Tools for High Production.


Faces 3' diameter. Standard Vices have maximum bar capacity of $6\frac{1}{2}$ " diameter. Minimum length handled 6'. Standard bed lengths to take work up to 24', 48' or 72' long.

TINIUS OLTSEN
MANUFACTURED UNDER LICENCE

BALANCING MACHINES

The E.O. Type machine illustrated quickly indicates combined static and dynamic unbalance and the angle.

Standard machines are built in a range covering components weighing from 3 ozs. to 1,500 lbs.




Write for detailed catalogue to English makers:

EDWARD G HERBERT LTD ATLAS WORKS · LEVENSHULME · MANCHESTER 19


Deep marking or knurling **TOUGH** materials . . .



THE FUNDITOR ROLLING PRINCIPLE



Each round part is located in a cradle and is raised under pressure against a flat die carried in the head. The die then traverses and the impression is made in the part smoothly and evenly.



Each flat part is located in a holding fixture and is raised under pressure against a round die carried in the head. As the die traverses, it rotates, making the impression in the part. In both cases a small portion of the die only is in contact with the piece and positive pressure ensures a consistently clean mark. Shock impact is practically eliminated.

... needs a

Funditor Heavy Duty Marking Mc.

This semi-automatic hydraulic machine has been specially designed for deep marking tough materials without effort. Its rolling action and controlled heavy pressure results in impressions of consistent clarity. By use of the appropriate dies and fixtures deep marking or knurling can be performed with ease and high rates of production obtained by unskilled female operators.

● Send us particulars of your marking or knurling requirements. Write for our latest Marking Machine Manual with over 100 illustrations.


Funditor Ltd

Phone : Clerkenwell 6155 (3 lines). 3, WOODBRIDGE STREET, LONDON. E.C.1

When answering advertisements kindly mention **MACHINERY**.

RECORD

MACHINE VICE



- ★ No Lift,
- ★ Reversible, Precision Ground Jaws,
- ★ Guaranteed Strength and Workmanship

Full details of these Machine Vices and other
RECORD TOOLS Free on request to Dept. M

MANUFACTURERS

designed for
Production Engineers
by
Production Engineers


Width of Jaws	Weight Lbs.	List Price
3"	12½	140/-
4"	26½	190/-
5"	40½	250/-

C. & J. HAMPTON LTD., RECORD TOOL WORKS, SHEFFIELD 2

small bores are our business

ELLAY
Tubes
LTD.

Ellay Tubes Limited,
Cox Green Works,
Maidenhead, Berks.
Tel: Maidenhead 3303



We positively enjoy it. We are specialist manufacturers of small diameter non-ferrous metal tubing anywhere in the ⅛ in. to ⅝ in. o.d. range. We can fabricate, bend, turn and press to your exact specifications. Our thoughts range from ⅛ in. to 20 ft. in length and from 0.006 in. to 0.064 in. wall thickness—in aluminium, brass or copper (Commercial grades, h.c. and o.f.h.c.). Our tolerances can be precise, close or simply general purpose.


In fact, we insist on only three things; absolute consistency, low cost and the right tubing for the job.

Try us out on your baby.

Precision fabricated tubular products in non-ferrous metals to customers' specifications.

ELLAY TUBES LIMITED

When answering advertisements kindly mention MACHINERY.



Don't buy oil seals haphazardly. Get Pioneer Oil Seals.

Pioneer representatives are factory trained men who can deal with any oil-sealing problem on the spot and recommend the seal you need.

Pioneer Personal Oil Sealing Service means not only studying a customer's individual needs; it also means recommending the right oil seals and personal inspection when they are in use.

Buy Pioneer and make sure your oil-sealing problems are solved for all time.

Write now for the most comprehensive catalogues in the trade on Oil Seals and O-Rings and for your copy of the OIL SEAL JOURNAL


PIONEER

Oilsealing & Moulding Co. Ltd.

A DIVISION OF J. H. FENNER & CO. LTD.

Factory & Head Office: Cottontree Works, Colne, Lancashire • Telephone: Wycoller 471 (8 lines)

When answering advertisements kindly mention MACHINERY.




THE NEW DUNBAR & COOK COLLET CHUCK

Designed for use with "Ward" 3.A or "Herbert" 2.D and 4. Senior Capstans, this new oversized collet chuck enables second operation work up to four inches diameter to be accommodated, but retains all the benefits of a ball chuck.

Specialists in the manufacture of
**SPECIAL PURPOSE
MACHINES,
JIGS & FIXTURES**

For full details write to Dept. M.
DUNBAR & COOK LTD.
NEW JOHN ST., BIRMINGHAM, 6
Phone: ASTon Cross 2571/2/3. Grams: "Cubar" B'ham

FIRST CLASS MACHINE TOOLS deserve
DONOVAN ELECTRIC CONTROL




This **THREAD GENERATOR & SPLINE MILLING MACHINE** by James Archdale & Co. Ltd., is a typical example of high-quality Machine Tools that rely on **DONOVAN** electric control gear for uninterrupted production and to reduce hold-ups or damage to expensive tools.

We are Specialists in design and manufacture of electric control gear for—

**MILLING MACHINES,
LATHES, SAWING
MACHINES, PRESSES,
DRILLING MACHINES,
GRINDING MACHINES**
etc. etc.




THE DONOVAN ELECTRICAL CO. LTD. · GRANVILLE ST., BIRMINGHAM 1
LONDON DEPOT: 149-151 YORK WAY, N.7 · GLASGOW DEPOT: 22 PITT STREET, C.2
Sales Engineers available in LONDON, BIRMINGHAM, MANCHESTER, GLASGOW, BELFAST, BOURNEMOUTH.




What sorts of springs do you need?




No. 760. 3 doz.
Assorted Light Com-
pression Springs. 1"
to 4" long, 22 to 18
S.W.G., $\frac{1}{4}$ " to $\frac{1}{2}$ "
diam. 6/6 each.



No. 757. Extra Light
Compression, 1 gross
Assorted, $\frac{1}{4}$ " to $\frac{1}{2}$ ", $\frac{1}{4}$ "
to 2" long, 27 to 20
S.W.G. 15/- each.



No. 758. Fine Ex-
pansion Springs. 1
gross Assorted $\frac{1}{4}$ " to
 $\frac{1}{2}$ ", $\frac{1}{4}$ " to 2" long, 27
to 20 S.W.G.
15/- each.



No. 98A. 3 doz.
Assorted 1" to 4"
long, $\frac{1}{4}$ " to $\frac{1}{2}$ " diam.
19G to 15G.
5/6 each.



No. 388. $\frac{1}{2}$ gross
Assorted Small Ex-
pansion Springs. $\frac{1}{4}$ "
to $\frac{1}{2}$ ", 18G to 21G.
9/6 each.

Compression? Expansion?

Long? Short? Light? Heavy? Let
Terry's BOXES OF ASSORTED SPRINGS
settle the question. Just the job for you
experimental people—a simply unlimited
assortment from our tremendous range of
springs of every variety. The 8 boxes shown
here are only a few—but why not let us send
you a full list—post free.

Really interested in springs: The 1957 edition of
"Spring Design and Calculations" — post free 12.6

TERRY'S ASSORTED SPRINGS

HERBERT TERRY & SONS LTD · REDDITCH · WORCS.
(Makers of quality Springs, Wireforms and Presswork for over
a century)


Cut production costs with Terry Wire CIRCLIPS



We can supply from
stock in sizes from
 $\frac{1}{4}$ " to $\frac{1}{2}$ ".



No. 466. $\frac{1}{2}$ gross
Assorted Small Ex-
pansion Springs $\frac{1}{4}$ "
to $\frac{1}{2}$ " long, $\frac{1}{4}$ " to
 $\frac{1}{2}$ " diam., 21G to
24G. 6/6 each.



No. 753. 3 doz.
Assorted Light Ex-
pansion $\frac{1}{4}$ " to $\frac{1}{2}$ "
diam., 2" to 6" long,
22 to 18 S.W.G.
10/6 each.




No. 1024. 20 Compression
Springs 12" long, $\frac{1}{4}$ " to $\frac{1}{2}$ " diam.,
24G to 18G, suitable for cutting
into shorter lengths; and 30
Expansions $\frac{1}{4}$ " to 12" long, $\frac{1}{4}$ "
to $\frac{1}{2}$ " diam., 22G to 16G.
24/- each.

HT21B

When answering advertisements kindly mention MACHINERY.

"T" TWIST DRIVE



QUICK CHANGE

DRILL CHUCK

PROVIDES A POSITIVE DRIVE FOR STRAIGHT SHANK DRILLS, ELIMINATING EXPENSIVE SMALL TAPER SHANK DRILLS AND REDUCES EQUIPMENT COSTS ON DRILLING MACHINES, TURRET LATHES AND AUTOMATICS.

SAFE-POSITIVE-FOOLPROOF!

With full floating action "T" Twist Drive chucks give the closest possible centre to centre set-ups, plus quick-change and positive drive—Five sizes cover drills and taps up to 2" dia.

Drill and collet in chuck body showing Turret Drive principle for straight shank drills.

Turret lathe chuck, showing adjustment screw in shank.

Send for Details to Dept. M2.

TOOL CHANGES
MADE AT FULL
OPERATING
SPEED



HENRY CHALLIS LTD

DEVONSHIRE HOUSE · VICARAGE CRESCENT, LONDON, S.W.11. PHONE: BATTERSEA 9581

"Duplex"

HEAVY DUTY PRECISION GRINDING UNITS

5 & 7½ H.P.

20" x 1½" WHEELS

These units are an addition to the 15 sizes of Tool Post Grinders made by us with wheels from 3" up to 20", and internal units with speeds up to 40,000 r.p.m.

May we send you our catalogue?

DUPLEX ELECTRIC TOOLS LTD.

WOBURN WORKS : HIGH STREET : PURLEY : SURREY

Phones: UPLands 3731 and 8621




When answering advertisements kindly mention **MACHINERY**.

another application for the

Kopp

GEARLESS GEARBOX

*here shown on a sequence switching
machine made by the Belmos Company Ltd*



Stepless speed variation over a 9 to 1 output speed range (1/3 to 3 times the input speed).

Constant horse-power transmitted throughout the speed range.

Flange mounted motors (when required) giving output speeds from 320 to 2880 r.p.m., and from 480 to 4320 r.p.m.

Low output speeds down to 1 to 9 r.p.m., or lower, obtained with reduction gears, flange mounted to the Variator.

Exceptionally light, sensitive and accurate control of speed setting.

Co-axial input and output shafts which rotate in the same direction.

Service reliability resulting from a simple design manufactured to high precision limits.

Compactness, with consequent ease of mounting as an integral part of a machine.

Vibrationless and silent performance.

Standard range 1/33 h.p. to 15 h.p.

ALLSPEEDS LIMITED, Oakenshore Works, Clayton-le-Moors, Accrington, Lancs
Telephone: Accrington 5441 (4 lines)

REGIONAL OFFICES:

LONDON: 59 Park Road North, Acton, W.3. Tel: Acorn 7150

SCOTLAND:


P.O. BOX No. 1, Clarkston, Glasgow . . . Tel: Busby 2738

MIDLANDS: Much Park Street, Coventry. Tel: Coventry 63091

YORKSHIRE:

46 Park Square, Leeds, 1 Tel: 3-1146, 3-0285/6

*When answering advertisements kindly mention **MACHINERY**.*



SPECIALISTS in used and reconditioned machine tools

USED MACHINE TOOLS FOR IMMEDIATE DELIVERY ★

ACME-GRIDLEY $\frac{1}{2}$ in. Six-Spindle Bar Automatics.
ACME-GRIDLEY 2 in. Six-Spindle Bar Automatics.
ACME-GRIDLEY 2½ in. Six-Spindle Bar Automatics.
ACME-GRIDLEY 6½ in. Six-Spindle Chucking Automatics.
B.S.A. ACME-GRIDLEY 5½ in. Six-Spindle Chucking Automatic.
B.S.A. 1½ in. Single-Spindle Automatic Screw Machine.
B.S.A. 1½ in. Single-Spindle Automatic Screw Machine.
B.S.A. 9 in. Single-Spindle Chucking Automatic.
B.S.A. Multi-Tool Lathes 6 in. x 12, 20, and 28 ins.

B.S.A. LANDIS 6 in. x 30 in. Type C. Plain Grinders.
B.S.A. 50H Honing Machine.
BRADFORD Lathe.
BRIDGPORT Milling Machine.
CINCINNATI 1/18 S. Milling Machine.
HERBERT Single-Spindle Drillers.
HERBERT Double-Spindle Drillers.
HOLROYD Double-Spindle Profiling Machines.
HULLER No. 5 Tapping Machines.
KELLY 24 in. Shaping Machine.
PRECIMAX 5 in. x 18 in. MPH Plain Grinder.
POLLARD Double-Spindle Drillers.

★ Offered subject to prior sale
 All machines motorised suitable for
 400-440 volts, 3 phase, 50 cycle supply.


We offer good prices for your surplus plant. Send us details—we will inspect immediately and make a firm offer. Write, wire or phone . . .

BGMACHINERY
 (B.S.A. TOOLS GROUP) LTD.
 MONTGOMERY STREET
 BIRMINGHAM, 11.
 Phone: VICTORIA 2351-9 Grams: "REBUILT"

When answering advertisements kindly mention MACHINERY.

POWER

WHEN...
WHERE
and HOW
YOU NEED IT!



with

GEARED MOTOR UNITS FROM STOCK


Since 1902 S. E. Opperman Ltd. have gained unique practical experience in the manufacture of a wide range of Geared Motor Units covering a vast field of uses and applications. First class design, top grade materials and fine workmanship have continuously been employed, giving high efficiency, smooth and cool running and long life. Geared Motor Units are available from stock fitted with electric motors made to the latest specification by Britain's leading motor manufacturers.

S. E. OPPERMAN LTD.
BOREHAM WOOD, HERTS ELSTREE 2021

When answering advertisements kindly mention MACHINERY.

for **ACCURACY** plus **SERVICE**

specify



NORRIS

HOBBS
and
CUTTERS

NORRIS ENG. CO., LTD., NORRIS ROAD - STAINES - MIDDX.

ASK FOR ILLUSTRATED BROCHURE

TELEPHONE: STAINES 244 & 4644

Criss-Cross Grinding

by combined longitudinal and cross feed

ON THE SWISS

TRIPET MHP

Hydraulic SURFACE GRINDER

Combined feeds produce maximum flatness with fine surface finish and the diamond pattern retains oil. Automatic infinitely variable hydraulic feeds. Micrometer setting of finished dimensions to fixed stops.

TRAVERSES	MHP.350	MHP.500
Longitudinal	14"	20"
Transverse	7.2"	7.2"
Vertical	12"	12"

With dust extractor or wet grinding equipment.

SOLE U.K. DISTRIBUTORS:




DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14

Telephone WESTERN 8077 (8 lines)

Telegrams ACCURATOOL HAMMER LONDON



See this machine in our Showroom or write for the illustrated brochure.

130

When answering advertisements kindly mention MACHINERY.



*Moving
Only in
the Best
Circles...*

The
QUALCUT
TWIST DRILL

*THE POLISHED DRILL WITH
THE POLISHED PERFORMANCE*

LOOK FOR THE




QUALCUT TOOLS LIMITED WORKSOP ROAD
SHEFFIELD 9

Telegrams and Cables: "QUALCUT", Sheffield 9 Telephone: Sheffield 41023/4

London Office: 4/8 Putney High Street, London S.W.15. Telephone: Putney 7251 (3 lines)

When answering advertisements kindly mention MACHINERY.



VISION UNIVERSAL

TOOL & CUTTER GRINDER

ILLUSTRATION SHOWS THE STANDARD
MODEL **CAPACITY 11" × 18"**
COMPLETE WITH FULLY MOTORISED
WORKHEAD

PRICE £470

.... also available with capacity of
11" × 24" wet grinding equipment, internal
grinding attachment, collet attachment,
dividing head, chucks, long surface grind-
ing quill, dead centre grinding attachment,
etc.

MADE BY **D. VINELL & SON LTD.**
TONBRIDGE, KENT, ENGLAND
Telephone: Tonbridge 2476

MARK YOUR NAMEPLATES

— MORE RAPIDLY AND EFFICIENTLY


THE NEW STANDWELL

MODEL 'K' BENCH MOUNTING

DIAL TYPE MARKING MACHINE

Unique Features Include:—

- Vertical adjustment to marking head.
- Rapid positioning for marking.
- Automatic spacing of characters.
- Perfect alignment of Type.
- Choice of character sizes.
- Special marks as required.
- Marks articles up to 3/4 in. thick.



THE STANDWELL EQUIPMENT CO. LTD.


CAMBRIDGE GROVE ROAD, KINGSTON - ON - THAMES

Phone: Kingston-on-Thames 4566 (3 lines)


Grams & Cables: Impress, Kingston-on-Thames

KERRY

RANGE OF DRILLING MACHINES




'Super 8'
 $\frac{3}{4}$ " capacity
Bench, pillar or
line production
models



'Drillmaster'
 $\frac{1}{2}$ " capacity
Bench, pillar or
line production
models



'100'
1" capacity



'150' AG
all-gear head
'150' IV
infinitely variable
 $1\frac{1}{2}$ " capacity



'125'
 $1\frac{1}{4}$ " capacity

Kerry's
(Engineering) Co Ltd

The Radial Drill illustrated on the left is available in 2 models. The R3 has a swing of 36", the R4, 48". Both models have a capacity of $1\frac{1}{4}$ " in steel and $1\frac{1}{2}$ " in cast iron. 9 spindle speeds, ranging from 90 to 1120 r.p.m. Quick hand traverse, fine hand feed and three rates of power feed. The range of Kerry drilling machines includes bench, pillar and line production models with drilling capacities from $\frac{1}{2}$ " to $1\frac{1}{2}$ ".

Full details from your Machine Tool Merchant or our
Sales Office: Warton Road, Stratford, London, E.15 Phone: MARYland 6611

When answering advertisements kindly mention **MACHINERY**.

The
OSMOND

**HIGH SPEED
ABRASIVE WHEEL
CUT-OFF
MACHINES**

A & S OSMOND LTD
254-6, HOTWELL ROAD,
BRISTOL, 8

Phone: BRISTOL 27604 (2 lines)



Comprehensive range of bench and stand models from 1 to 25 h.p. for the machine shop, fabricating shop and foundry.

BARS, ANGLES, TUBES, ETC., HARD OR SOFT CUT IN SECONDS.

For precision made **JIGS & TOOLS**

SHEET METAL WORK · METAL SPINNINGS

PRESS AND PLASTIC MOULDING TOOLS etc.

We have "an infinite capacity for taking pains"—a wealth of skill and knowledge—one of the finest Tool Rooms in the country, and every facility to give you a unique, high precision engineering service. We number among our customers most of the best-known names in the aircraft, motor and other industries, and would like to include yours in this list—may we have the opportunity to be of service to you?






...consult
CORNERCROFT LTD.
...the precision engineers



THE CORNERCROFT GROUP OF
COMPANIES
ACE WORKS—COVENTRY
Telephone: Coventry 40561-5
and at 32 CLARGES ST., LONDON W.1
Telephone: Grosvenor 1646

NC 186

When answering advertisements kindly mention MACHINERY.



Drop Forgings



Talk to engineers
about drop forgings and they think of
Daniel Doncaster & Sons Ltd.
Whether it be the aircraft industry,
the motor industry or
any other user of drop forgings,
all agree that "for drop forgings
of top quality, in large or
small quantities, it is best to go
to Doncasters."



DANIEL DONCASTER & SONS LIMITED • SHEFFIELD
FORGINGS • DROP FORGINGS • TOOL STEELS • HARDENED STEEL ROLLS

When answering advertisements kindly mention MACHINERY.

F52

○

NOW *Teddington*

offer a complete range of
pneumatic gauging equipment


The importance of the announcement that Teddington are manufacturing, in technical collaboration with Moore Products of Philadelphia, a range of pneumatic gauging equipment lies in the fact that for the first time British industry is offered a complete range covering manual and automatic gauging and complete automatic machine control. The major advantages of speed, accuracy and robustness are common to each application.

In brief...

- * magnifications up to 12,500
- * great accuracy — repeatability within 1% of scale range
- * positive operation — high pressure system unaffected by dirt or coolant on the work
- * high wear tolerance — up to 0.003" without affecting accuracy.

MANUAL

Single and multiple gauging of diameters, taper, thickness, straightness and other dimensions.



AUTOMATIC

High speed multi-dimensional gauging machines with automatic segregation of work and feed-back signals for machine control.

MACHINE CONTROL

"In process" or "post process" gauging with 5 stage feed-back signalling.

Write for further details available in leaflet A & I/M 1101.


TEDDINGTON INDUSTRIAL EQUIPMENT LTD
SUNBURY-ON-THAMES, MIDDLESEX

Telephone: Sunbury-on-Thames 600 (9 lines)
Growth & Cable: Teddequip, Sunbury-on-Thames, Telex. Telex: 22742 Teddeconbury.



TIE 58

RAYNER POWER DRIVES



"2 H.P."
40 to 200 r.p.m.

**COMPACT PURPOSE-MADE
POWER DRIVES ARE OUR BUSINESS
PETER RAYNER LTD**

121 WHITEHALL RD · LEEDS 12 TELEPHONE: LEEDS 33844

REMEMBER!

TAL

for

**PRESSURE
DIECASTINGS**


ZINC B.S. 1004 OR ALUMINIUM
LARGE OR SMALL

Enquiries to

T.A.L. DEVELOPMENTS LTD.

BROADWATER WORKS, GARMAN ROAD, TOTTENHAM, N.17
TELEPHONE: TOTTENHAM 2732/3

CERTIFIED ZINC ALLOY
ZASCA
DIE CASTERS



The principle of barrelling may be the same today as thirty years ago, but the application of the principle is vastly different. Roto-Finish precision barrelling techniques can produce surface finishes of an accuracy even up to 5 micro-inches and go on producing a uniform result, batch after batch. One of the operative factors in Roto-Finish barrelling is the controlled Cascade

Action. This process depends upon the rotation of the barrel so that the contents are carried round in a position of repose until the point is reached where the mass commences to slide, all components passing, as a result, through a continuously sliding top layer. The speed of the barrel's rotation, which determines the briskness of the Cascade Action, is one of the seven variables which must be controlled exactly to produce precise and uniform results.


Long painstaking research has produced the Roto-Finish range of barrelling machines for deburring, descaling, radiusing, polishing, britehoning and colouring metal parts at the lowest possible cost.

ROLLS ROYCE are among the leading British firms to use Roto-Finish

To be precise — Roto-Finish

ROTO-FINISH LTD., DEPT. M, 5 MARK ROAD, HEMEL HEMPSTEAD, HERTFORDSHIRE. BOXMOOR 4600 (PBX)

When answering advertisements kindly mention MACHINERY.

GRIMSTON**8' Carbide and H.S.S. Grinders**

★ A low priced machine
capable of first class results

★ Fully adjustable tool rests

Drive through $\frac{1}{2}$ h.p. motor with high tensile steel shaft on dust sealed, grease packed ball bearings. Available for bench or pedestal mounting.

GRIMSTON ELECTRIC TOOLS LTD.
DEPT. M2, PROGRESS WAY, CROYDON, SURREY
Tel : Croydon 0131 Grams : Grimtool, Croydon

Speed Production with... **MALCUS****UNIVERSAL
TOOL HOLDERS**

Time taken in changing and adjusting the tool is reduced to a few seconds when using a Malcus Universal Tool Holder.

An ordinary lathe equipped with a Malcus Universal Tool Holder will in many cases perform the same work as a turret lathe, and consequently, the purchase price of the holder will be repaid in a very short time. Easily fitted to any lathe.

Distributors and Stockists for the United Kingdom



MORTIMER
ENGINEERING CO.
PROPRIETORS: S. GUTTMAN & CO. LTD.



SHOWROOMS & SALES: 204-6 ACTON LANE, HARLESDEAN, LONDON N.W.10.
Telephone: ELGar 4833

BOSTON direct on drum
REVERSING SWITCH

A.C.
Max. 3HP
D.C.
Max. $\frac{1}{2}$ HP
Standard model
PRICE 27/-

Spring return to neutral (or to other special requirements) can also be supplied at small extra cost.

Generous terms to merchants and manufacturers.

For full particulars write to:

KINGS LANGLEY ENGINEERING CO. LTD.

KINGS LANGLEY, HERTS. TEL: KINGS LANGLEY 2215-9.



**YEARS
AHEAD
IN
DESIGN!**

**ACROW
DEMAG**

**WORLD'S MOST RELIABLE
HOIST BLOCKS**

Send for illustrated brochure 203

ACROW (Engineers) Ltd., South Wharf, London, W.2.

AMBassador 3456 (20 lines)

SOLE AGENTS FOR THE UNITED KINGDOM

Model
EUK 30
-21/F
3-ton
Electric
Travel
with
Creep
Speed
One
example
of our
wide
range

When answering advertisements kindly mention MACHINERY.

For your technical Library

A new series of Brochures on

SPECIALISED LUBRICANTS

Publication No. 1

ANTI-SCUFFING PASTE AND ANTI-SCUFFING OIL

Anti-Scuffing Paste is the most effective means of applying Molybdenum Disulphide for dry lubrication. Used where ordinary oils and greases cannot be applied. Withstands immense heat and pressures, and has remarkable anti-seize properties. Approved

under D.T.D. 900/4284. Anti-Scuffing Oil enables Molybdenum Disulphide to be used in circulating systems, oil lubricators and so on.

Publication No. 2

R.T.D. COMPOUND

The modern cutting medium for severe metal operations. Consists entirely of

additives, and counters the effects of high pressure and frictional heat in drilling, reaming and tapping stainless steel, alloy steels, nickel and titanium. Has lengthened tool life up to 30 times.

Publication No. 3

MOLYBDENISED LUBRICANTS

The remarkable anti-friction and pressure resisting properties of Molybdenum Disulphide have been incorporated in a wide range of specialised lubricants, which are dealt with in this Brochure.

Publication No. 4

WATCH AND CLOCK OILS

A complete range for the Horological and Instrument Engineer, based on the best Continental blends and improved by up-to-date refining methods. Includes a series of synthetic oils which remain fluid down to -65°C; and Molybdenised Oils in all viscosities.

Publication No. 5

KILOPOISE LUBRICANTS

Extreme viscosity lubricants to damp free motion and ensure a slow, even action in such components as optical focusing movements, variable condensers and potentiometer spindles. Widely used throughout the optical, instrument, radio and electronic industries. Special grades available for use as Core Locking Compounds on I.F.T.'s, and other Electronic assemblies.

Publication No. 8

MOLYTONE GREASE

Actually a series of specialised lubricants combining Rocol Bentone Grease and Molybdenum Disulphide. These greases have no melting point and are effective from below zero to 430°F. They withstand tremendous pressures and provide positive lubrication even in "starved" conditions. They possess outstanding anti-friction properties.

Write to **ROCOL** about LUBRICATION


These Brochures are available from:

ROCOL LTD

IBEX HOUSE, MINORIES, LONDON, E.C.3. Telephone: ROYAL 4372.

or ROCOL HOUSE, SWILLINGTON, Nr. LEEDS.

Telephone: Garforth 2261/2. |



ABC MARK II OFFSET BORING HEAD



Capable of boring from
 $\frac{1}{4}$ in. dia. to 5 in. dia.

Micrometer feed is provided.

Size of head:
 $2\frac{1}{4}$ in. dia., $2\frac{1}{4}$ in. long.

Equally efficient
in lathe, drill
press, milling
machine.

Shanks
interchangeable.

SOLE MANUFACTURERS
A. B. CREED LTD.
4, LITTLE ILFORD LANE
LONDON E.C.12

ILFORD 0455

LINK-V



FASTENER

Is suitable for
ROLLS OF SOLID CONSTRUCTION V-BELTING
Patent No. 749362 and others


- ★ M, A, B, C, P & D sections available.
- ★ BELTING supplied in 50ft. and 150ft. rolls.
- ★ QUICKLY FIXED. Any size of belt made up in a few minutes.
- ★ EASILY DETACHABLE. Belt can be shortened and fastener used again.
- ★ STRONG JOINT. Indefinite life of joint by replacing oil impregnated bronze bushes.

Write for
fully descrip-
tive leaflet.

FLEXICON LTD.

NORTH WING MILLS · BRADFORD · Y OR
FHCNE: 23941

Anderton



A.I.D. A.R.B. I.F.V. approved.

Write for DATA SHEETS to Dept. A6


ANDERTON SPRINGS LTD., BINGLEY
Tel.: Bingley
2388, 2351, 2226
'Grams':
'CIRCLIPS' · BINGLEY

TYPE
1300

TYPE
1400

TYPE
1500

CIRCLIPS



absterge (to clean by wiping)

Austins supply the best cleaning rags for every purpose. Some jobs call for coarse, heavy fabric, some for soft, closely woven materials—we can meet all requirements with carefully selected rags that are thoroughly washed and sterilized in our own plant. Orders of all sizes are handled with promptness and reliability. Please let us quote you for regular supplies.

AUSTINS industrial cleaning rags

E. AUSTIN & SONS (LONDON) LTD. GUN WHARF
Gunmakers Lane · London · E.3 · Tel ADVance 1211




A.W. NEWMAN & SONS LIMITED

Prompt
REPAIRS

TO ENGINEERING
MEASURING AND
TESTING
INSTRUMENTS

Phone: PARK 6946
152a Holland Park Ave., London, W.11

When answering advertisements kindly mention MACHINERY.



Steels for Press Tools

"476." For tools operating under severe conditions of wear and abrasion or when maximum runs are desired. Air hardening, machinable. Applications include dies and punches for blanking steel sheet and plate, high silicon transformer materials, stainless steel and iron, brass, copper, zinc. Also for deep drawing dies, cupping dies, forming dies.

"L.T.A.H." Deep hardening in air at 840 deg. 860 deg. C. with minimum distortion. Tough and abrasion resistant. Low decarburization. Machinable. Specially for tools of heavy or intricate section, heavy forming dies, blanking dies, trimming dies, notching dies, heavy duty punches, spindles, stripper plates, bending tools.

"S.C.V." A hard, tough steel which resists sinking. For cutting dies, drawing and rivet dies, stamping and blanking dies, pressing dies, coining dies.


"NEWHALL." An oil hardening non-deforming steel. Has a wide range of applications in press tool work when it is not desired to use more highly alloyed steels.

"PAX No. 2." Shock resisting steel with high impact strength and good wear resistance. For punches and dies used on thick gauge materials and subject to heavy shock.

'SABEN' HIGH SPEED STEELS, HOT WORK STEELS

SANDERSON

A
SABEN
PRODUCT




SANDERSON BROTHERS AND NEWBOULD LIMITED, ATTERCLIFFE STEELWORKS, P.O. BOX 6, NEWHALL ROAD, SHEFFIELD 9

When answering advertisements kindly mention MACHINERY.

OUTSTANDING IN VALUE AND PERFORMANCE

Table - 25in. by 6in.
Table travel - 15in.
Cross feed - 5in.
Vertical feed - 11in.
12 spindle speeds from
50 to 1,660 r.p.m. Full
range of accessories
can be offered.

Price including stand-
ard motor, Brook
Push-button starter,
suds pump and cutter
tribor - £316



'SENIOR' MODEL MI. MILLING MACHINE

- For full particulars write to manufacturers.
- T. SENIOR, ATLAS WORKS, LIVERSEDGE, YORKS

CAM BLANKS

For:
Brown & Sharpe Index, B.S.A. Tarax.
C.A.V. Manurhin, Wickman, Tornos,
Petermann and Bechler Automatics.
CAMS DESIGNED & MACHINED.

MOSER CAMS & TOOLS LTD.

465, HORNSEY ROAD, LONDON, N.19.

Tel.: ARCHWAY 1766.

These PARALLEL ACTION Pliers are FIRM FAVOURITES with all TRADESMEN

END CUTTING
NIPPER
No. 301



FLAT NOSE
PLIER
No. 486



SIDE CUTTING
PLIER
No. 495



CLAMPING
PLIER
No. 479



SNIPER NOSE
PLIER
No. 433



MAUN INDUSTRIES LIMITED MANSFIELD, NOTTS.

STEEL FABRICATION SPECIALISTS

—GUILLOTINING—ROLLING—
—PROFILING—WELDING—
—MACHINING—

C.F. IDE
ENGINEERING LTD.

EMPIRE WORKS, RICHMOND ROAD,
KINGSTON-ON-THAMES

Telephone: KINGston 6820

"COVENTRY"

WET TOOL GRINDER

Specially designed for tungsten carbide tools. One
wheel for roughing and one for finishing. Large
diameter ball-bearing spindle. Sturdy construction
throughout, with self-contained motor drive as shown.

Write for full details.

CENTAUR TOOL WORKS

EYRE ST., SPRINGHILL BIRMINGHAM
Phone: EGGASTON 1118/9, Grams: CAPSTAN BIRMINGHAM



When answering advertisements kindly mention MACHINERY.



MACHINERY'S

BOOKS ON MATHEMATICS

MACHINERY'S HANDBOOK

(Latest Edition - Thumb-Indexed)

Presents in one complete volume all the essential data for the entire field of shop practice and machine tool design. Amply illustrated by diagrams accompanied by proven data, the latest printing of this world-famous book gives not only all the old, tried and proved features of earlier editions but, in addition, the most useful, recent and complete collection of data, standards, formulae and practical information.

Price 72s. cash and C.O.D. Instalments 80s., payable 13s. 4d. in 10 days, 13s. 4d. monthly. Overseas, cash with order, plus 2s. postage.

ARITHMETIC FOR ENGINEERS—Charles B. Clapham

Revised edition of a well-established text. It covers: vulgar and decimal fractions; symbolic representation; simple equations; logarithms; mensuration; graphs; the slide-rule; and trigonometry.

Price 21s. cash and C.O.D. Instalments 23s., payable 9s. in 10 days, 7s. 6d. monthly. Overseas, cash with order, plus 1s. 6d. postage.

MANUAL OF PRACTICAL MATHEMATICS

—Frank Castle

This manual was designed as an introduction to the methods of higher mathematics for students who do not propose to specialise in mathematics. Covers trigonometrical equations, indices and logarithms, mensuration of solids, vectors, differentiation, successive differentiation and Taylor's and Maclaurin's theorems, integration, moment of inertia, Fourier's theorem and differential equations. 624 pages.

Price 15s. cash and C.O.D. Instalments 16s. 6d., payable 5s. 6d. in 10 days, 5s. 6d. monthly. Overseas, cash with order, plus 1s. postage.

MATHEMATICS AT WORK—Holbrook L. Horton

Contains over 700 pages, describes in detail the practical applications of arithmetic, algebra, geometry, trigonometry and logarithms in step-by-step solutions of mechanical problems, with formulae commonly used in engineering practice. Standard reference tables and a concise review of basic mathematical principles.

Price 60s. cash and C.O.D. Instalments 66s., payable 11s. in 10 days, 11s. monthly. Overseas, cash with order, plus 1s. 6d. postage.

SHOP MATHEMATICS—F. D. Jones and E. Oberg

Applied mathematics dealing with various machine-shop and tool-room problems and containing numerous examples illustrating their solution and the practical application of useful rules and formulae such as solution of triangles, milling machine indexing, change gearing for screw thread cutting, etc.

Price 36s. cash and C.O.D. Instalments 40s., payable 7s. 6d. in 10 days, 6s. 6d. monthly. Overseas, cash with order, plus 1s. postage.

FREE APPROVAL NO DEPOSIT INSTALMENTS

To MACHINERY, National House, 21 West Street, Brighton, 1.
Please send me Book's marked X above.

For CASH herewith or by C.O.D. or

ON APPROVAL when I will either return in 5 days, or
pay FULL CASH, or by INSTALMENTS as stated above.

Name Position

Address Firm

Write for Book Catalogue and details of Instalment Terms.

When answering advertisements kindly mention MACHINERY.


○★



UNIVERSAL JIG & FIXTURE SYSTEM

PRODUCES ACCURATE AND COMPLETELY RIGID JIGS AND FIXTURES WITHIN 0.0003in. WITH NO MACHINING NO EXTRA MATERIAL AT LOW LABOUR COST FOR LONG OR SHORT RUN WORK

Illustration shows set-up for milling gear selector fork on a 12in. by 10in. base—with exploded illustrations of certain component elements
Send for literature showing complete range of equipment and typical applications, illustrating versatility of system



WHARTON & WILCOCKS LTD.,

20 BULL PLAIN · HERTFORD · ENGLAND

TELEPHONE : HERTFORD 4041

Indexing

**AUTOMATIC
MULTI-SPINDLE
DRILL
HEAD**

SIZES

5"
16
1"
2
5"
8

4, 5 and 6 Tool Stations
Collets, Chucks, Tapping Head, Turret Depth Stop, Pre-selector Variable Speed Drive

EMBASSY MACHINE & TOOL COMPANY LTD.
248, Watford Way, Hendon, London, N.W.4.
Telephone: SUNburyhill 2829.

-but engineers use **BRAUER**

TOGGLE CLAMPS
BRITAIN'S WIDEST RANGE
DIRECT FROM THE MAKERS

Send for catalogue to...
F. BRAUER LTD.
Grove Rd. Harpenden
Herts.
Tel. Harpenden 3603

REBUILDING

We now have facilities for rebuilding lathes of our manufacture. Machines made to original limits of accuracy. Inspection at your Works by our Representatives.


S&B

SMART & BROWN (Machine Tools) LTD.
25, MANCHESTER SQUARE, LONDON, W.1.
Telephone: WELbeck 7941/6

When answering advertisements kindly mention MACHINERY.

Dubied SELF-GRIPPING automatic WORK DRIVER

$\frac{1}{4}$ " to 6" capacity covered by only 3 sizes



- ★ Simple loading and unloading of workpiece (by hand rotation of knurled ring).
- ★ Irregular or eccentric blanks gripped with even tension.
- ★ Gripping pressure increases in proportion to cutting forces.
- ★ Vibration minimised by interior counter-balance weights.
- ★ No danger to operator, due to absence of protruding parts.
- ★ Intermediate blank flanges can be supplied in various sizes, and to suit type of lathe.

MACHINE SHOP EQUIPMENT LTD. Spenser St., London, S.W.1. Tel. VIC 6086



Write NOW to DEPT. AM for particulars of complete range of Dial Gauges and Comparators, also Foot Lever presses and High-Speed Drilling Machines etc.

OLDAK DIAL GAUGES

ACCURATE · ROBUST · DEPENDABLE

Compare

THESE PRICES
0.0005in. or 0.01mm.
from £2.17.3
0.0001in. or 0.002mm.
from £5.4.6.

GENEROUS TERMS
TO
MERCHANTS

THESE FEATURES
Stainless steel rack and pinions
Rotatable bezel
Revolution counter
Continuous and balanced readings on the same scale ring
Stainless steel hardened case stem

AND, of course, BSI accuracy and dimensions
MANUFACTURED SOLELY BY:

ENGINEERING PRODUCTS LIMITED

GLENBROOK WKS., LITTLERS CLOSE, MERTON ABBEY, LONDON, S.W.19

TELEPHONE: LIBERTY 1085 & 1086

When answering advertisements kindly mention MACHINERY.

IT'S STRONGER — LASTS LONGER

The latest and greatest of a long and famous line is

GRIPOLY

Nylon BELTING

THE AMAZING PROPERTIES OF NYLON
ITS HIGH-TENSILE STRENGTH
ITS RESISTANCE TO FATIGUE
ITS ELASTICITY

are incorporated by a special weaving technique
which involves pre-stressing the nylon core and
locking it by means of a thin cotton envelope
of high frictional properties.

Sole Manufacturers:



LEWIS & TYLOR LTD

Power Transmission Engineers
GRIPOLY MILLS — CARDIFF

Branches

LONDON, MANCHESTER, GLASGOW, and Agencies all over
the world

Makers of the world famous Patent GRIPOLY Hair Belting, GRIPOLATA
Rubber and Canvas Ply Belting, GRIPOLASTIC Endless Belts and many
other GRIPOLY products.



TRANSMITS MORE POWER — DOES NOT STRETCH

CUT COSTS IN KEYWAYS

MARLCO

KEYWAY BROACHES

Cut perfect taper or parallel Keyways with any type of hand press, without skilled labour or elaborate set up. No. 1 set for $\frac{1}{8}$ "- $\frac{3}{4}$ ", with guide diameters $\frac{1}{8}$ "- $\frac{1}{2}$ ". No. 2 Set for $\frac{3}{8}$ "- $\frac{3}{4}$ ", with guide diameters $\frac{1}{4}$ "- $\frac{1}{2}$ ". Broaches and guides are interchangeable for non-standard Keyways.




W. H. MARLEY & CO. LIMITED
NEW SOUTHGATE WORKS, 105 HIGH RD., LONDON, N.11

TELEPHONE: ENTERprise 5234, 5578

Press! and it's SECURE Flip! and it's FREE!

When you require speedy
positioning, holding down
and final release on all
machining and assembly
operations—either for small
batch, or long run work—
like hundreds of other firms
throughout the country,
you will find
the answer
in



THE MULDEAN
PATENT
Camclamp

SIZE 0	SIZE 1	SIZE 2
20/-	28/6	37/6

Manufactured by
DEAN & MULHALL LTD.
17 SIDNEY STREET, SHEFFIELD, 1
TEL.: 23071
Tracing templates
supplied by request

When answering advertisements kindly mention MACHINERY.

BLANKS WITHOUT DIES

If you need small* quantities
of blanks, pierced or otherwise,
in metals or non-metals,
use the . . .

CROSLAND BLANK & PIERCE SERVICE

which offers you prompt delivery
of well finished blanks produced by
its unique and surprisingly
inexpensive tooling and production
technique. Forget about dies and
simply send your drawings
and specifications to . .

William Crosland Ltd.

* as small as
you like !

BREDBURY, Nr. STOCKPORT, CHESHIRE.

Telephone : Woodley 2621 (3 lines)

ESTIMATES SENT BY RETURN



Small Bore Gauge



HIGH PRECISION MECHANICAL FINE MEASURING TOOLS

Small Bore Gauge

Range 2 mm. to 11 mm.

Passameters

Supplied in four sizes
0 to 4 inch

Universal Tool Holder

Orthotest High Precision Indicator

Reading to .00005 inch

External Micrometers

Supplied in four sizes
0 to 4 inch, all with
Tungsten-Carbide tips

Indicating Micrometers

Supplied in two sizes
0"-1" and 1"-2"



Passameters



External
Micrometers



Universal Tool
Holder



Indicating Micrometers



GEORGE COHEN

SONS AND COMPANY LIMITED

Catalogue on request

JOINT SOLE DISTRIBUTORS:

The Selson Machine Tool Co. Ltd

41-45 Minerva Road, N. Acton, London, N.W.10

Tel: ELGar 4000 (10 lines)

BULWER STREET, LONDON, W.12

Tel: SHEpherds Bush 2020




When answering advertisements kindly mention MACHINERY.

Cut SET-UP COSTS



ALL SIZES
DELIVERED
EX-STOCK



Change to ROCKWELL HELICAL CLAMPS

BRITISH PATENT

Why waste time building up rickety, makeshift clamps with anything that's handy? Get on the phone today and ask for full information about Rockwell Helical Clamps. These ingenious clamps have been designed for simple quick and positive mounting, with negligible clamp projection over work piece. Each clamp is a complete unit, with no parts to lose.

• WRITE OR PHONE FOR LEAFLET GIVING PRICES
SIZES AND FULL TECHNICAL DETAILS
-TODAY!

WELSH HARP, EDGWARE ROAD,
LONDON, N.W.2. GLADSTONE 0033

ROCKWELL
MACHINE TOOL CO. LTD.

Also at Birmingham — Springfield 1134/5. Stockport — Stockport 5241
Glasgow — Merrylee 2822

SC5

CAM ACTION MACHINE VICE


Width of Jaws
(Large Model) 5½ in.
(Small) 3½ in.
Jaws open (Large model)
2½ in. (Small) 2 in.



- Meehanite castings
- Quicker loading
- Totally enclosed cam unit
- Jaws can be easily replaced by special soft jaws.
- Leverage by cam handle gives extra clamping power

PEACOCK & WALLER LTD
HINCKLEY, LEICESTERSHIRE, ENGLAND

AID/ARB Approved
Telephone: 11



"BESSBORO" TYPE 'MG' SELF-CONTAINED MOTOR DRIVEN ROTARY TABLES

VARIOUS SPEEDS OBTAINED BY CHANGE GEARS
RAPID TRAVERSE IN REVERSE — COMPLETE
WITH DIVIDING MECHANISM — DIVIDING
ACCURACY ± 1 MIN-OF-ARC.

• IN SIX SIZES 10" — 32" DIA.

STANTON MACHINE TOOLS LTD.

Bessborough Wks., Molesey Rd., West Molesey, Surrey

PHONE: MOLESEY 6635

PRECISION TOOLMAKING & ENGINEERING



SHIRLEY

TOOLS & ENGINEERING
LIMITED


*Immediate Capacity
Prompt Delivery*

1-3 ELGIN ROAD
SOUTHAMPTON
Telephone: 21881

SPECIAL
PURPOSE
MACHINES
JIGS · FIXTURES
PRESS TOOLS
MOULDS
DIES
GAUGES

When answering advertisements kindly mention MACHINERY.

Teething Troubles?




ABRAMS ENGINEERING

can supply the answer to your gear manufacturing problems

- WORM & WHEEL REDUCTION GEARS
- STRAIGHT BEVEL GEARS
- SPIRAL & ZEROL BEVEL GEARS—on the latest Gleason System
- SPUR & HELICAL GEARS

Our expert service is backed by many years of experience


We should be pleased to forward you, on request, our illustrated brochure and quote you for your particular requirements.



ABRAMS ENGINEERING

SYD ABRAMS LTD., Waterloo Rd., Manchester 8
Telephone: BROUGHTON 4321 (7 lines).

ENGRAVING *as easy as* ABC




MODEL 848 ENGRAVING MACHINE

Reduction range 1:2 to 1:4
Vertical adjustment to suit workpiece height.
Area for 1:2 reduction 5in. by 3in., for 1:4 reduction, 2 1/2in. by 1 1/2in.


£90 Complete

MODEL 713 ENGRAVING MACHINE

Reduction range 1:2 to 1:8, with engraving at near writing speeds. Balanced pantograph has ball pivots and adjustable tension. Area for 1:2 reduction, 15in. by 10in., for 1:8 reduction, 15in. by 4in.



£165 Complete



MODEL 858 ENGRAVING CUTTER GRINDER

Simplifies the grinding of special cutter forms. Universal cutter head with bold graduations and adjustable stops for profiles, compound angles, radii, blends, etc.

£83 15s. 0d.
Complete

David Dowling

ENGRAVING EQUIPMENT

... moderate in price
high in performance


MANUFACTURED BY

DAVID DOWLING LTD.

ROEBUCK RD., HAINAULT, ILFORD, ESSEX. Tel: HAINAULT 4121/3
STOCKISTS THROUGHOUT THE WORLD: London • Belfast
Birmingham • Liverpool • Leicester • Glasgow • Manchester
Toronto • Sydney • Melbourne • Johannesburg • Madras
Rotterdam • Stockholm • etc.

When answering advertisements kindly mention MACHINERY.

QUALITY CONTROL of pressure die castings



Maintaining the correct chemical analysis of die casting alloys, particularly with regard to impurity limits, is of paramount importance in the production of high quality die castings. Our Laboratory is equipped with one of the few *direct reading spectrographs* in use in this country.

As a result the requirements of the B.S.I. Certification Scheme for zinc alloy die castings are far exceeded. Every melt is analysed and the holding furnace of every machine is checked for impurities at least once per shift, enabling any variance from specification to be quickly identified.

With the utmost confidence, we can therefore claim to supply castings of the highest quality. *Quotations, without obligation, from drawings, specifications or samples.*

**PRESSURE DIE CASTINGS
IN ZINC, ALUMINIUM AND SOFT ALLOYS**

SPARKLETS LIMITED
TOTTENHAM, LONDON, N.17

JIGS
And FIXTURES
Designed & Manufactured by
PINSDALE ENGINEERING CO. LTD.
LEEDS PLACE, TOLLINGTON PK. LONDON N.4

A.I.D. Member of the Gauge & Toolmakers Association A.R.B.

- **MOULDS** Compression and Injection Plastic
- **MOULDS** Pressure Diecasting
- **MOULDS** Rubber and Gravity
- **JIGS & FIXTURES**
- **PRESS TOOLS**
- **PRESS WORK** up to 25 tons
- **AUTOMATIC & CAPSTAN TURNED PARTS**

TO BE PRECISE IT'S

Camdentools

21-22, HONYWOOD ROAD,
BASILDON, ESSEX.

Phone: Basildon 20506/7.

PRESSWORK

SMALL AND MEDIUM
(Including Deep Drawing)

We can provide:

**MATERIAL · TOOLING · METHOD
PRODUCTION & FINISHING**

Free Delivery Greater London Area
A.I.D. Approved.

**H. G. SANDERS & SON.
LIMITED.**

Gordon Road, Southall, Middlesex.
Telephone: SOUTHall 5611

**PRESSWORK
PRODUCTS LTD.**
Specialists in Accuracy



WRITE OR PHONE US AT

**LIGHT PRESSINGS ·
DEEP DRAWING ·
SPRING
PRESSINGS ·**

**STATION WORKS
LUDLOW ROAD
MAIDENHEAD · BERKS**

Phone: Maidenhead 700 (3 lines)

When answering advertisements kindly mention **MACHINERY**.

CLASSIFIED ADVERTISEMENTS

RATES: PLAIN ADVERTISEMENTS except "Situations Wanted" (ALL TYPE): 2/2 per line. MINIMUM 8/8 (4 lines) OR £1 8s. 2d. per inch (13 lines per inch). Box Nos. 1/3 extra per insertion. SITUATIONS WANTED: 1/8 per line. MINIMUM 6/8 plus 1/3 Box No. SPECIAL DISPLAY TYPE (with or without Blocks): 1/2 p. £1 10s.; 1/4 p. £3; 1/8 p. £6 or £2 per inch (min. 1/2 in.). Series rates on request.

CONTRACT WORK

DESIGNS

PRECISION PRODUCTS (ROMFORD) LTD.

TOOL DESIGNERS
AND MANUFACTURERS

*For all
your needs*

IN
JIGS · FIXTURES
GAUGES · PRESS TOOLS
FORM TOOLS AND
SPECIAL MACHINES



Viking Works, London Rd.,
Romford, Essex. Tel: Romford 61991/2

Established Design Organisation
have capacity available for Production
planning and detailed design of Press Tools,
Jigs and Fixtures, Special Machines, etc.—
NORRIS BROS., LTD., 55, Victoria St.,
S.W.1. Phone: ABey 6132 and Brighton 55566.

ENGINEERING DESIGN SERVICE

DAVID J. EVANS/Research LTD
55 Kingsway, London W.C.2
Holborn 4969

DESIGNING OF
GENERAL & SPECIAL
MACHINES
DRAFTING
DETAILING
DEVELOPMENT
AND
PROTOTYPE WORK

CHIS 5842. **R. E. CARDER LTD.** CHIS 4611.
1 & 2, Chiswick Common Road, London, W.4

JIGS — TOOLS — AND PRESS TOOLS
UNIVERSAL GRINDING
—JIG BORING GENERAL
GOOD CLASS MACHINING WORK—
DESIGN OFFICE & DEVELOPMENT WORK

**In all
Directions**

DESIGNEX
(CONTROL)

can help
Phone 64049

PRESS TOOLS
LAMINATIONS—COMBINATION—PROGRESSION, ETC.
JIGS—FIXTURES
PROTOTYPE MACHINING
Designing—Short Order Work—Sub Assemblies Completely Toolled
JIG BORING AND PRECISION GRINDING
LANDEN (ENGINEERS) LTD.
1a, Aubert Park, Highbury, London, N.5
Phone: CANbury 1075

A Design

and

Manufacturing

Organisation

Employing upwards of sixty Designers and Draughtsmen invites enquiries for Design and Manufacture of all types of Special Purpose Equipment, Jigs, Fixtures, Press Tools and Gauges.

Comprehensive facilities available for development or projects from initial conception to final manufacture.

RATES

Design and Drawing: 12/6d. to 14/- per hr.
Depending on nature of work
Tracing: 6/6d. per hr.

Replies to Box T839 MACHINERY,
Clifton House, Euston Road, N.W.1

● **ENGINEERING BUYERS NEED MACHINERY'S ANNUAL BUYERS' GUIDE**

When answering advertisements kindly mention **MACHINERY**.

TOOL DESIGNERS & MANUFACTURERS

JIGS FIXTURES
PRESS TOOLS
SPECIAL MACHINES
JIG BORING
AND PROTOTYPE WORK

**WILLIAM ATKINS
(COVENTRY) LTD.**

Specialists in
Turbine Blade
Tooling
Layout
and Lofting




203/269
Foleshill Road
Coventry
Tel: Coventry 62568

THE ABBEY TOOL CO. LTD.

Let us absorb your Peak
Design load for you!

Specialists in design of Transfer
machines · Special purpose machines
Auto Tooling · Jigs and Fixtures
Press Tools and Tracing · Manu-
facturing Service available.



SOUTHBANK RD · KENILWORTH · Tel: Kenilworth 990

••• GEARS •••

GEARS We are specialists


Experienced gear cutters at your service
No need to let a gear problem stump you
Expert knowledge is on hand
Rapid delivery from customers' own blanks
All gears cut, or made complete to your requirements
Trust your gear-cutting to us (over 30 years' experience)
Every satisfaction assured
Do send your enquiries, large or small, prompt attention given

F. M. ILLICH (GEARS) LTD.

4A, JAMESTOWN ROAD, LONDON, N.W.1

Tel: Gulliver 5046

SPIRALS · SPURS WORMS & WHEELS · BEVELS · SPROCKETS
CAPACITY LIST ON APPLICATION



GEARS

ALL TYPES OF SMALL GEARS
UP TO 8in. DIA. 10 D.P.
ESTABLISHED IN 1880

G. W. EVERY & SONS, LTD.
49, THORNHILL RD, LONDON, N.1. Phone: NORTH 1827.

ESTD
1889

R-STEPHENS & SON LTD

115 CHURCH ROAD
UPPER NORWOOD
LONDON S.E.18

**PRESS TOOLS · JIGS
FIXTURES · MOULDS
GAUGES · DESIGNS**

PHONE
LIVINGSTONE
2265-6

WE DESIGN AND MANUFACTURE PRESS TOOLS AND DO THE PRESS WORK

A.I.D. & A.R.B. APPROVED
NAISH BROS. & CO. LTD.
124, CHELTENHAM ROAD,
BRISTOL. Tel.: 25532-3

GEARING FOR INSTRUMENTS

CUSTOMER'S OWN BLANKS ACCEPTED


Capacity shortly available for:—
HIGH PRECISION · GEAR CUTTING
 (Max. O.D. 5in. Min. D.P. 120)
 Bore/P.D. Concentricity .0005"
· THREAD MILLING
 (Up to 1 1/2in. dia. by 2 1/2in. long)
 (Over 1 1/2in. dia. by 4 1/2in. long)
· BENCH LATHE TURNING
F. BROWN (ESTABLISHED 1890)
 150, Upper Street, Islington, N.1. CAN 4287

Gear Cutting, Auto Turret, Capstan
and Centre Lathe Turning, Milling,
Planing, Hardening and Grinding,
Profile Cutting and Welding.

**SMITH & NETHERWOOD,
LTD.**
Tanyard Road, Quarmby,
HUDDERSFIELD.
Phone: MILNSBRIDGE 1868.



GEARS—PRECISION
AND INSTRUMENT MACHINE CUT
Max. capacity 12 D.P. 8in. dia.
Blanks turned and cut.
SETON CREAGHE ENGINEERING LTD.,
TRADING ESTATE, PARK ROYAL ROAD, N.W.10
A.I.D. 'Phone: ELGar 3356/7 A.R.B.



A.M.D. for
HIGH CLASS WORKMANSHIP
RELIABLE DELIVERY DATE
ECONOMIC PRICES

Send for
 copy of
 special brochure

A.M.D. ENGINEERING CO LTD · BEAUFORT ROAD · EAST TWICKENHAM
 Telephone: POPESGROVE 2877/8

COMPLETE ASSEMBLIES
JIGS AND TOOLS
GEAR CUTTING
SHEET METAL WORK
GENERAL MACHINING

Complete production of
GEARS
 SPURS · SPIRALS · BEVELS
 WORMS · WHEELS · RACKS
 SPROCKETS & CLUTCHES

Extra rapid delivery
 from Customers own Blanks

A.I.D.
 APPROVED

COMPLETE
 GEARED
 ASSEMBLIES

THE DAVALL GEAR COMPANY LTD.
 GEARWORKS · HIGH STREET · POTTERS BAR · MIDDLESEX
 Telephone: POTTERS BAR 2382-3



GENERAL ENG'G. ● ● SERVICES ● ●

PROTOTYPE & PRODUCTION

ELECTRONIC WIRING, COIL WINDING,
 INSTRUMENTATION & TESTING
SETON CREAGHE ENGINEERING LTD.,
 G. W. Trading Estate, Park Royal Road,
 N.W.10.
 A.I.D. ELGAR 3356/7 A.R.B.

STAINLESS STEEL SPECIALISTS

Fabrication, welding and X-ray
 inspection, pressings and machined
 parts.

THE TAYLOR RUSTLESS
 FITTINGS COMPANY, LIMITED.
 Ring Road,
 Lower Wortley,
 Leeds, 12

Capacity Available in All Depart-
 ments of light engineering works, with
 General machine shop and woodworking plant.
 Channel and angle framework, Tubular Con-
 struction, Fitting, Welding, Stove Enamelling,
 Painting and Spraying, Assembly and Wood-
 work Shops:

CARTERS WORKS,
 Great Western Trading Estate,
 Park Royal Road, London, N.W.10.
 Phone: ELGAR 6404.

Welding & Engineering Specialities

- | | |
|---------------|----------------|
| • TURNING | • GRINDING |
| • PRESSWORK | • WELDING ALL |
| • PROFILE | • METALS |
| • CUTTING | • JIG BORING |
| • TOOL MAKING | • MILLING |
| • SHEET METAL | • CAPSTAN WORK |
| | • WORK |

Your enquiries will receive our
 immediate attention

25 BELL LANE, HENDON, N.W.4
 Tel: Hendon 9553

Classified Advertisements (CONTRACT WORK, contd.)

CAPACITY AVAILABLE

in

IRONFOUNDRY

Low Phosphorous Iron Castings in Grades 12, 14, 17, 20, 23 and 26.

Machine Moulding up to box size 34in. by 28in. by 14in.

Floor Moulding up to 3 tons.

MACHINE SHOPS

Vertical boring up to 6ft. dia. swing.

Horizontal boring on Kearns and Richards No. 2 Machines, with 3in. spindles and facing heads.

Surface grinding up to 6ft. dia. swing.

Planing up to 3ft. by 3ft. by 8ft.

Milling (vertical and horizontal) up to No. 4 machine capacity.

Turning up to 12½in. height of centres. Capacity 8ft. between centres.

No. 8 Ward combination Turret Lathes.

STEEL FABRICATING SHOP

Your Enquiries are invited

ROBERT CORT & SON LIMITED

READING

Telephones: Reading 55046 (5 lines)

NITRAM METAL TREATMENT & ENG. CO. LTD.

SILVERDALE RD., HAYES, MIDDLESEX. HAYES 5111/2

A.I.D. A.R.B.
APPROVED

HEAT TREATMENT Specialists

*** 24 HOUR SERVICE**
WE COLLECT AND DELIVER

**BRIGHT ANNEALING
COPPER BRAZING**

**INDUCTION HARDENING
UP TO 15 K.W. CAPACITY**

PPD

BATH

TOOLMAKERS AND PRECISION ENGINEERS

Early capacity available.

WADKIN ROUTING

LARGE MILLING AND CYLINDRICAL GRINDING
SURFACE GRINDING AND PLANING UP TO 6FT. BY 3FT.

AYALON WORKS • LOWER BRISTOL ROAD • BATH

Telephone: 7654-5

IDEAL

HARDENING CO., LTD.

DAVIS ROAD, CHESSINGTON, SURREY

**HEAT TREATMENT
SPECIALISTS
HARDENING OF
EVERY DESCRIPTION
AND SANDBLASTING**
Tel.: ELMBRIDGE 6556-6567

REPAIRS

By **WELDING**

**BROKEN MACHINE TOOL PARTS
& DAMAGED PLANT IN ALLOY STEELS,
CAST IRON & NON-FERROUS METALS
SPECIALLY REPAIRED BY WELDING**

ESTABLISHED OVER 40 YEARS

THE BLAKER MOTOR WELDING CO. LTD.

Welding Engineers

DUKES RD. PARK ROYAL, LONDON, W.3.
Phone: ACORN 4811. Grams: Eickelweid. Eilat London

INTERNAL GRINDING SPINDLES RECONDITIONED.

Prompt Service by Specialists.

TOWER ENGG. CO. (Northwood) LTD.

Ferndown, Joel Street,
Northwood, Middlesex.

Phone: Northwood 1372

General and Precision Machinists, medium turning, milling, grinding, slotting, drilling and assembly work. A.I.D. A.R.B. approved. Prompt deliveries, keen prices.—ADLARDS MOTORS, LTD., 51, Upper Richmond Road, Putney, S.W.15. Vandyke 5123.

Luton Engineering Pattern Co.

are prepared to undertake the manufacture of all classes of wood and metal patterns and accuracy and prompt delivery guaranteed.—Send your enquiries to 80A, Princes Street, Luton. Phone 961.

WOOD & METAL PATTERNS

HAND MACHINE OR SHELL MOULDING
Keen Quotations Good Delivery

B. LEVY & Co. (Patterns) Ltd.
1-5 OSBERT ST., LONDON, S.W.1.

Telephone: VICTORIA 1073 & 7496.

**CROYDON TOOL
AND CASE HARDENING SPECIALISTS**
EXPERTS IN ALL HEAT TREATMENT OF METALS
CYANIDE HARDENING • ANNEALING • SHOT BLASTING
KEEN PRICES • WE COLLECT AND DELIVER
UNION ROAD, WEST CROYDON. PHONE: THORNTON HEATH 5222

L. ADAMS LIMITED
Specialists in Quality Production

of Light Engineering Products. Precision Instrument type of work. Mechanical and Electrical-Mechanical Assemblies. Tested Complete to specification Requirements.

COMPLETE FACILITIES. Development - Design - Tooling to Assembly and Testing. A.I.D. and A.R.B. approved.

MINERVA ROAD, CHASE ESTATE,
LONDON, N.W.10 'Phone: ELGar 5046-7.
ESTABLISHED 40 YEARS.

A.I.D. — **THE** — CUN 5195
HEAT TREATMENT
PEOPLE OF LONDON
G.R.M. SERVICES LIMITED, PADDINGTON, W.9.

Hill Engineering (Catford) Ltd.

Precision machining capacity

- ▶ CENTRE LATHE TURNING OF SMALL, MEDIUM AND LARGE PARTS UP TO 44in. dia. by 12in. OR 20in. dia. by 100in.
- ▶ OPTICAL MILLING, (VERTICAL AND HORIZONTAL)
- ▶ SHAPING, RADIAL DRILLING, TAPPING, etc., etc.
- ▶ ELECTRIC ARC AND OXY-ACETYLENE WELDING

Special purpose machines and prototype assemblies up to 2 tons
Complete design and detailing facilities

324-328 LEWISHAM HIGH STREET, S.E.13 Phone: LEE 9211 (5 lines)

**PROTOTYPES & SPECIAL
PURPOSE MACHINES**
REPAIRS & SALVAGE BY DEPOSITION
MACHINING, FORGING & FABRICATING
GEORGE MILLS (ENGINEERS) LTD.
BECKENHAM, KENT. TEL: SYDENHAM 5255

Semi-automatic pinion cutting capacity
immediately available.
Large range of hobs held in stock.
Also capacity on Mikron 79s.
ROBERT PRINGLE & SONS
36-42, Clerkenwell Road, London, E.C.1
Telephone: CLERKENWELL 2341

ABBAY HEAT TREATMENTS LTD.
PLAZA WORKS, HIGH STREET, MERTON, S.W.19
FOR ALL TYPES OF HEAT TREATMENT.
WE COLLECT - WE DELIVER
TELEPHONE: CHERRYWOOD 2291

Immediate Capacity Available,
castings, non-ferrous, die, shell moulded,
sand, etc. Also machining and stove-enamel-
ling.—**MILLS ENGINEERING PRODUCTS,**
LTD., BARNET. 'Phone: Barnet 6741.

•• **MACHINING** ••

AUTO TURNED PARTS

FINE TOLERANCES. MAX. DIA. 1 1/2 in.
INDEX 35 & GRIDLEY MULTI AUTOS
THREAD CHASING. MANUFACTURE
ROLLER BOX TOOL HOLDERS.
BENTON ENGINEERING CO. LTD.,
Tombridge Road, Harold Hill, Essex.
Ingravebourns 4213

Thread Milling for the Trade
up to 6in. O.D. and 5in. I.D. Any thread
any quantity. Keen prices for long runs.
Satisfaction guaranteed.

UNICORN PRODUCTS, LTD.,
119-121, Stanstead Road, Forest Hill, London,
S.E.23. Telephone: Forest Hill 7688 (3 lines).

**SHEARING, BENDING,
ROLLING, STAMPING,**

up to 3/4 in. plate. Rotary coil slitting and
allied services. Sheets and plate in stock.
SHELMERDINE & MULLEY LTD.
EDGWARE ROAD, CRICKLEWOOD,
N.W.2.

GLAdstone 7677-8-9.

FINE LIMIT GRINDING
MILLING, TURNING, DRILLING.
Complete Service Offered.

SETON CREAGHE ENGINEERING LTD.,
Trading Estate, Park Royal Road, N.W.10
A.I.D. ELGar 3356/7 A.R.B.

Precision

Light to Medium-Heavy

Machining capacity available for:

- **HORIZONTAL MILLING**
- **VERTICAL MILLING**
- **GEAR CUTTING**
- **VERTICAL BORING**
(up to 7ft. Capacity Table)
- **CYLINDRICAL GRINDING**
(up to 15ft. between centres)
- **JIG BORING**
(up to No. 3B Pratt & Whitney)
- **RADIAL DRILLING**
(4ft. 6in. Arm)
- **MEDIUM HORIZONTAL BORING**
(up to table size 7ft. by 47in.)
- **CAPSTANS AND CENTRE LATHES**

A.I.D. and C.I.A. Approved
Contractors to Her Majesty's Government

F.N.F.

Machinery Manufacturing Co. Ltd.
Burton-on-Trent

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

PRECISION TURNED PARTSA.I.D., A.R.B., C.I.A. & I.F.V. APPROVED.
AUTO and CAPSTAN QUANTITIES.Send your specifications to:
**AYLESBURY TURNED PARTS
(True Screws) LIMITED**
Britannia St., Aylesbury, Bucks.
Tel.: Aylesbury 2424 (3 lines)**E. R. LATTIMER LTD.**

SHAKESPEARE STREET, SOUTHPORT

'Phone: Southport 4245

Offer a very comprehensive service for
Small to Medium Component and Sub-
Assembly Manufacture incorporating:

- Capstan, Auto & Centre Lathe Turning
- Horizontal, Vertical & Profile Milling
- Centreless, Surface & Internal Grinding
- Lapping and Honing
- Drilling, Tapping & 2nd Operation Lathe Work
- Mazak Pressure Die Casting up to 6 oz. weight.

Our new and extended Toolroom is now
in operation with full facilities for TOOL
DESIGN AND MANUFACTURE.

We are fully approved by A.I.D. and A.R.B.

AIRCRAFT UNIT**ENGINEERING CO.**

A.I.D., A.R.B. APPROVED

CAPSTAN CAPACITY A. 3A. 7A. WARDS,
MILLING, DRILLING, PROFILING, CENTRE,
TURNING, BRAZING AND ASSEMBLY WORK

CLOSE LIMITS AND GOOD STANDARDS

18-19, Greenhill Parade,
NEW BARNET, HERTS.

'Phone: BAR 6471/5772

PLOUGH GRINDING

2 1/2 hr. Service

High Speed Service Tool Co. Ltd.
Maple Road, Surbiton, Surrey.
E1mbridge 1135-6-7.**IMMEDIATE CAPACITY AVAILABLE**

- GEAR CUTTING to 24in.
- THREAD MILLING 4in. by 40in.
- PLANING 6ft. by 2ft. 6in.
- BROACHING

MAURALL ENG. CO.38-40, Upper Clapton Road, E.S.
Telephone: AMHort 6163.**PRECISION & GENERAL
MACHINING**

including

Thread Milling • Radial Drilling
Metal Spinning

A.I.D. and I.F.V. Approved. Enquiries invited.

Surplice & Tozer Eng. Co., Ltd.
Acres Works, Windsor
Windsor 1657 & 1844A.I.D. & A.R.B.
APPROVEDTELEPHONE:
CRAWLEY 25211/8**The Alka Company**

(Proprietors: Wicanders (Great Britain) Ltd.)

PRECISION MACHINING CAPACITY

- COMBINATION LATHES AND CAPSTANS
- CENTRE LATHE TURNING UP TO 36in. SWING
- UNIVERSAL, HORIZONTAL, VERTICAL MILLING
- GRINDING, DRILLING, HEAT TREATMENT
- JIG AND FIXTURES
- SPECIAL PURPOSE MACHINES AND ASSEMBLIES UP TO 4 tons.

MAXWELL WAY, GATWICK RD., CRAWLEY, SUSSEX

WE WOULD WELCOME YOUR ENQUIRIES FOR:—

- MILLING—Horizontal & Vertical.
- CENTRE LATHES to 38in. Dia.
- CAPSTANS to 2 1/2in. Dia.
- PLANING TO 6ft. x 3ft. x 3ft.
- BORING—Horizontal & Vertical.
- Cylindrical Grinding to 20in. Dia. x 84in.
- Surface Grinding to 24in. x 8in.
- Drilling and Thread Tapping.

A.I.D. APPROVED

BOWES ROAD ENGINEERING CO. LTD.
BOWES ROAD, NEW SOUTHGATE, N.11. 'Phone BOW 2284/5/6**Automatic and Capstan**Capacity Available up to 2in. dia.—
WILLIS ENGINEERING, 65A, High Street
Hampton Hill, Middlesex. 'Molesley 4273.**Automatic Turned Parts, Press**Work, Press Tool Making, Capstan and
Centre Lathes, Milling, Drilling, Thread Milling.
Capacity available.—PARKER ENGINEERING
(KINGSTON), LTD., 200-202, Cambridge
Road, Kingston-on-Thames. KIN. 5501.**Planing Capacity, Heavy or Light**Turning up to 5ft. diameter.
Special machines to customers' design.
F. ATKINSON & SONS, London, Ltd.,
65, King's Cross Road, W.C.1. Terminus 4050.**Immediate Capacity Turning,**capstans, milling, drilling, die and tool
making.—MILLS ENGINEERING PRO-
DUCTS, LTD., Barnet. Tel.: BARNET 6744.**Metal Spinings. Immediate**capacity for metal spinings, sheet metal
work, welding and stove enamelling.—
HIGBURY METAL SPINNING CO. (1955),
Ltd., 20, Highbury Place, N.5. CANbury 2096.**Horizontal Production Milling**for the trade. Slots, flats, squares, etc.,
of all descriptions milled on latest plant. Keen
prices for long runs, satisfaction guaranteed.—
UNICORN PRODUCTS, LTD., 110-131, Stan-
stead Road, Forest Hill, London, S.E.23.
Telephone: Forest Hill 7688 (3 lines).**ROSSER & RUSSELL LTD.**Queen's Wharf, Hammersmith,
LONDON, W.4.

Telephone: RIVerside 4161.

**GENERAL ENGINEERS
AND
MANUFACTURERS OF
SPECIAL MACHINERY
TO
CUSTOMERS' DESIGN****Automatic Work Up to 1 1/2in.**Immediate capacity available—
TRUE ENGINEERS, LTD.,
Wharf Lane, Bourne End, Bucks. 'Phone 1316.**Capstan and Turret Lathe**Capacity available up to 4 1/2in. diameter
bar and 22in. diameter chucking. Castings and
Forgings a speciality. Milling, drilling and
centre lathe turning. High class work with
prompt delivery. Enquiries invited to:—
WHITWAM & ELEY,
20/22, Stafford Road, W.3. Acorn 8364.**Automatic Capacity Available**on Index single spindle autos, up to 2in.
dia.—ARTHURS ENGINEERING, Hershaw
Trading Estate, Molesley Road, Hershaw,
Surrey. 'Phone: Walton-on-Thames 5119.**Capstan Capacity Immediately**available, 8 B.A.—1 1/2in. Steel or Brass.
Large stocks of raw materials:—
SACRON, LTD.,
7, Chiswick High Road, W.4. Tel. CHISwick 3596.**Capstan Capacity Immediately**available, 10 B.A. to 1 1/2 diameter in R.M.S.
Brass, High Tensile, Stainless, etc. All sizes of
material actually in stock.—CHISWICK ENGI-
NEERING, LTD., Pluckington Place, King
Street, Southall, Middx. Tel.: Southall 2247.**High Precision Grinding of**Tungsten Carbide and Steel Tools.
Accurate profile grinding and progression tools
a speciality.—S. T. LTD., 22-26, Upper Mulgrave
Road, Cheam, Surrey. 'Phone: Virilant 0074/5**Delivery Guaranteed and a First**class job produced. We invite your
enquiries for Centre Lathe, up to 9in. centres,
plus gap, by 5ft. Milling, Grinding, Slotting,
Drilling and Assembly work. Quotations by
return.


"MITEMCO,"

35-51, Hanger Lane, W.5.
PERivale 8133.**Spur Gear and Sprocket Cutting**from blanks supplied or machined com-
plete. 'Phone: EUSTon 1854.

TURNER BROS.,

10, Pratt Mews, Camden Town, N.W.1.

When answering advertisements kindly mention MACHINERY



ZEPHYR
Engineers Ltd

cam
CUTTING

PRECISION TRACK MILLING OF FACE BOX
& CYLINDRICAL CAMS UP TO 30" DIAM.

24/32 EUSTON BUILDINGS, LOND. N.W.1

TELEPHONE: EUS. 7624

Auto Capacity + Hydraulic Copying


J. M. HARGREAVE & CO. LTD.

Central Avenue, West Molesey, Surrey. Tel: Molesey 3180/2707

Our newly installed Tares Type 64 autos include Hydraulic Copying and can produce to close limits components not usually made by Automatic Methods

Chucking: 7" Swing (6" in Chuck) Bar (including Black) Up to 2 1/2"

AUTOMATIC TURNED PARTS



WEST ST. REIGATE 3177
AMBRESSEY
ENGINEERING CO. LTD.

CENTRELESS GRINDING

ALL TYPES OF FORM, THROUGH AND PLUNGE

A.I.D. & A.R.B.
APPROVED

BAR GRINDING Tel.: POP 6157 & 7088

1/8 in. TO 5 in. DIA. UP TO 15 ft. LONG
IMMEDIATE CAPACITY ON CAPSTAN, MILLING
CENTRE LATHES, AUTO AND ALL TYPES OF GRINDING

REDCAR ENGINEERING CO. LTD.,

HOLLY ROAD WORKS, TWICKENHAM, MIDDLESEX

MACHINING

ECLIPSE

METAL INDUSTRIES LTD.
Sedgley Rd. West Tipton • Staffs.

GENERAL ENGINEERING WORK
PRODUCTION OR PROTOTYPE
JIGS • FIXTURES • ASSEMBLY
Pressure diecasting in zinc or lead

PLANING 12ft. 0in.

HORIZONTAL BORING	VERTICAL BORING	RADIAL DRILLING	CENTRE LATHES
COMBINATION TURRET LATHES	HORIZONTAL MILLING	VERTICAL MILLING	
GRINDING	DRILLING	WELDING	PROFILING
			HONING

D. A. GUNN (ENGINEERING) LTD

32, Park Road North, W.3 Tel.: ACorn 4841/4

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (CONTRACT WORK, contd.)

MACHINING CAPACITY AVAILABLE

PHONE: KIN 7627

CAPSTAN
TURNING
MILLING
DRILLINGSEND US
YOUR
ENQUIRIESTURRET LATHES
CENTRE LATHES
ALL GRINDERS
ETC.GOOD DELIVERIES — QUALITY — KEEN PRICES
W. G. MARSDEN ENG. LTD. 30 FIFE ROAD, KINGSTON, SURREY**GRINDING**IMMEDIATE CAPACITY AVAILABLE
CYLINDRICAL • INTERNAL • SURFACE
LATEST TYPE MACHINES
PLOUGH GRINDING — 24 HOUR SERVICE
alsoGeneral Machining, Fitting and Complete Assemblies
Special Purpose Machines Designed and Built
to SpecificationWe shall be pleased to advise on your Grinding and
Machining Problems**HOLLAND & CAESAR LTD**
ENGINEERING CONTRACTORS
GRINDING SPECIALISTSORKEY WORKS, 3-5 LEIGHTON PLACE,
LONDON, N.W.5

Est. 1836

Telephone: GULiver 3047 and 6444

INSTRUMENT
MACHINING
SERVICEMINT ST. LONDON S.E.1.
Tel: HOP 4333
A.I.D. APPROVEDImmediate Capacity Available for:
Capstans 10 BA to 2" • Centre
Lathe 26" gap x 6' 6" CentresMilling • Grinding etc
Stainless Steel a Speciality**RESEARCH**ENGINEERS LTD.
FOR**SUPER ACCURATE CAMS**SEE "MACHINERY" 22nd JANUARY 1954 FOR
METHOD OF CUTTING. REPRINTS AVAILABLE

NORTHAMPTON GROVE, CANONBURY, LONDON N.1


Telephone: CANONBURY 4244 (4 lines)

Telegrams: WILMAKET, NORDO, LONDON

When answering advertisements kindly mention MACHINERY.

CENTRELESS GRINDING
PLAIN & SURFACE GRINDING
CASE-HARDENING
Prompt Deliveries. A.I.D. Approved.**SCREW MACHINE PRODUCTS LTD.**
WOGBURN GREEN, HIGH WYCOMBE, BUCKS.
Telephone: Bourne End 111.**CAMS**APPROX.
48
HOURS
DELIVERYFOR
ALL
SINGLE
SPINDLE
AUTOS**EDWARDS BROS.**ST GEORGE LANE, SOUTH WOODFORD, E.11
TELEPHONE: WAREHAM 1000

CUTTING TOOLS AND PRECISION GRINDING

**TECHNITOOLS LIMITED**

432, WINDMILL ROAD, WEST CROYDON, SURREY

TELEPHONE AND INLAND TELEGRAMS: THORNTON HEATH 4751

CAPACITY AVAILABLETRADE WORK DIVISION
PRECISIONMACHINING of most
descriptions
GENERAL ENGINEERING
and
MANUFACTURING
A.I.D. and A.R.B. approved**S. M. STUART-TURNER & CO.**
(SURREY) LTD. FAIRVIEW ROAD, NORBURY
LONDON S.W.16 TEL POLLARDS 2231-2
GRAMS, "AEROQUIP" STREATH, LONDON

**PLASTIC MOULDS
JIGS & FIXTURES
DIE-CASTING TOOLS
PRESS TOOLS**

Comprehensive Design Facilities

**SPECIAL
TOOLS**



UNIVERSAL TOOLS LIMITED · TRAMWAY PATH · MITCHAM · SURREY Tel: MITcham 6111

PLANING CAPACITY

available

Up to 17 feet long 5 feet square

Early delivery of precision work

At most competitive prices

Rose, Downs & Thomson, Hull. Tel. 33874

W. D. HORNE & CO., MILLING LTD. TURNING DRILLING CAPSTAN CAPACITY AVAILABLE

Woodbridge House, Aylesbury Street
London, E.C.1
CLerkenwell 6668 & 6980

CYLINDRICAL GRINDING CAPACITY

External up to 12in. dia. by 36in.
Internal up to 7½in. by 8½in.

MARSDEN & SHIERS, LTD
Davis Road, Chessington, Surrey.
A.I.D. & A.R.B. A.N.R. Approved.
Telephone: ELMbridge 5333 & 5334

Multi-spindle and Single-spindle

Auto Turning up to 2in. bar capacity, capstan turning from the bar up to 2½in. dia., chuck work up to 1½in. dia., thread milling, milling, shaping, drilling, etc., capacity available. Any tolerance and quantity. Satisfaction absolutely guaranteed.—UNICORN PRODUCTS, Ltd., 119-121, Stanstead Road, Forest Hill, S.E.23. Phone: FOREst Hill 7688 (3 lines)

Capstan Capacity Available.
1in. to 4½in. Stainless High Tensile B.M.S. etc., no quantity too small or too large, stocks all materials.—ACME WORKS,
Pluckington Place, King Street,
Southall, Middx. Tel.: Southall 2247.

Fine Limit—Auto Turned Parts.

We would welcome your enquiries for Automatic Turned Parts. Immediate Capacity available on large Multi-spindle Autos up to 1½in. dia., also chucking work up to 5in. dia.—DENIS FERRANTI METERS, LTD., Bangor, North Wales.

Horizontal and Vertical Milling

Capacity Available. Modern Plant. A.I.D. approved.—WARD ELECTRIC CO. (NORWOOD), LTD., 44, Chapel Road, West Norwood, S.E.27. GIPsy Hill 1620.

METAL SPINNING OUR SPECIALITY, up to 9½. dia. (HYDRAULIC AND FLOWTURNING)

**POWER PRESSWORK to 250 tons capacity, including Hydraulic.
GENERAL SHEET METAL WORK ARC & OXY-ACETYLENE WELDING**

SHAWE METAL SPINNING WORKS, Swinton St., London, W.C.1
Phone: TERminus 7432 3. Grams: ALIPYDE PHONE LONDON

When answering advertisements kindly mention MACHINERY.

Metal Spinnings Produced to
your requirements. Economically. On Time. A.I.D. Approved.—MARTIN-GOLOD, LTD., Maybury Gardens, N.W.10. WIL 3888.

• PRESS WORK •

Presswork Up To 50 Tons. Including deep drawing. Long or short runs. Customers' tools and materials acceptable. Tooling and designing available.—BIRCH & JACQUES (TOOLMAKING), LTD., Hersham Trading Estate, Walton-on-Thames. Telephone: Walton-on-Thames 5379.


Pressings and Stampings, Ltd.,
Eccleston Road, West Ealing, W.13. Presswork up to 150 tons. Double action deep drawing—guillotine 8ft. by 10 S.W.G. Spot welding—Assembly. Tool making and electroplating.—Phone: Ealing 3667-8.

Press Work Up to 20 Tons in
any material. Own tools made. Accurate work. Good deliveries. Also Capstan and reversion machine work. A.I.D. approved.—ROYCE ENGINEERING Co., Victoria Street, Braintree, Essex. Telephone: Braintree 1234.

Presswork Up to 40 Tons, Circu-
lar and surface grinding on latest J & S machines. Tools designed and made for the trade, or your article produced throughout in our works. A.I.D. Approved. Enquiries welcomed.—WEMBLEY TOOL CO., LTD., 2, Bridge Road, Willesden, N.W.10. WIL 6667/8.

SUB-MINIATURE PRESSINGS
and multi-stage precision press work
in all materials
PROMPT DELIVERIES

G. A. PRECISION PRODUCTS LTD.
202, High Road London, N.22
BOWes Park 6557



THE FIRM WITH HALF A DOZEN JIG BORERS for PRESS TOOLS etc.

HIGH SPEED SERVICE TOOL CO. LTD.
Maple Road, Surbiton, Surrey. Hantsbridge 1125-6-7
STUDER PROFILE GRINDING A SPECIALITY.

Pressings in All Metals Up to 60 tons. Press tools manufactured in our own toolroom. Light assemblies. Domestic, Electrical and Mechanical. All finishes. A.I.D. and A.R.B. approved. Advice and estimates given free.—Inquiries to:—

METAL COMPONENTS, LTD.,
Dolphin Road, Shoreham-by-Sea, Sussex.
Telephone: Shoreham-by-Sea 2224/5.

Press Tools, Press Work, Jigs
Fixtures, Capstan and Auto. Turning, Special H.S. Cutters. Components manufactured and assembled to spec.—I. PERSON & SON, 63, Shaftesbury Street, N.1. CLE. 7139.

Capacity Available Press Tools,
Jigs, Fixtures, Production of Metal Pressings, Prototypes and Jobbing. Light Assemblies.

ELLIOTT & WEST,
487, Liverpool Road, N.7. Phone: NORTH 2366.

• TOOLMAKING •

JIG BORING
ON SIP JIG BORERS
EDMONTON TOOL & ENG. CO. LTD.
141, WERTFORD ROAD, EDMONTON N.9
TELEPHONE: EDMONTON 4412/3
SPURS, SPIRALS, BÉVELS, WORMS
& WORMWHEELS
GEAR CUTTING

HIGH CLASS TOOLING
JIGS and FIXTURES
PRESS TOOLS
GAUGES
EDS
Co. Ltd.
BEEHIVE LANE WORKS • BEEHIVE LANE
CHELMSFORD • ESSEX • Phone: 55351

DORMER & WADSWORTH LTD.
PLASTIC
MOULDS
PRESS TOOLS
JIGS
FIXTURES, ETC.
31-33
BICKERSTETH RD.,
MITCHAM RD.,
TOOTING,
LONDON, S.W.17
TELEPHONE BALHAM 1006 (2 LINES)

Press Tools,
JIGS
FIXTURES
GAUGES
MITCHAM JIG & PRESS TOOL Co. Ltd.
BENEDICT RD., MITCHAM, SURREY
Telephone: Mitcham 3635

MacDowall

JIGS, FIXTURES
PRESS TOOLS &
GAUGES
PRECISION ENGINEERS
SPECIAL MACHINERY

MACDOWALL EQUIPMENT COMPANY LIMITED
NORTH STREET ROMFORD ESSEX

ROMFORD 61981.

Tungsten Carbide Tools

Manufacturers of standard and special form tools in high speed steel and Tungsten Carbide.

Our range includes reamers, cutters, workrest blades and wear-resistant parts.

Carbide supplied to customers' specification and express service given for emergency tooling.

DIAGRIT GRINDING CO., LTD.,
Marden, Kent.

Phone: Marden 362.

PRECONOMY CO LTD
PRECISION Moulds and Press tools
Jigs and Fixtures
ECONOMY
Eastfield Side, Sutton-in-Ashfield, Notts

When answering advertisements kindly mention **MACHINERY**.

LENCHS

(BIRMINGHAM) LTD
TOOLMAKERS
Barr St., BIRMINGHAM 18.

Tel:

Northern 8421 (4 lines)

Sole Manufacturers of:

OAKALOY

CEMENTED CARBIDE TOOLS & TIPS

JIGS · PRESS TOOLS · FIXTURES

details on request

COVENTRY GRINDERS LIMITED

Phone: 60736, 60174

FORM GRINDING SPECIALISTS

OPTICAL FORM GRINDING UP TO 48ins. LONG


A complete Gauge and Tool Room at your service including 50 Grinding Machines. Send us your enquiries for all types of Gauges, Tool, Jigs and Components.

TOOLROOM AND PROFILE
GRINDING CAPACITY
AVAILABLE
FORM CUTTERS A SPECIALITY
PROTOTYPE WORK
GOOD DELIVERIES:
FIRST CLASS WORK

S. E. WAKELIN & CO. LTD.,
204, Birchfield Road,
Birmingham, 19.

EST. 1893 'Phone No. 8201/3

BELL PRECISION



OF CRAWLEY, SUSSEX.

Design and Efficient Production of
JIGS · FIXTURES · GAUGES · MOULDS
DIE CASTING DIES · SPECIAL MACHINES
to your requirements:

FORM GRINDING · JIG BORING WITH G-SIP JIG BORERS
SEND US YOUR ENQUIRIES

BELL PRECISION ENGINEERING CO., LTD.
VICTORIA WORKS · HIGH STREET · CRAWLEY
SUSSEX

Grams: JIGS-CRAWLEY Phone: CRAWLEY 25757-8



WORK TO PLACE.

Machining Capacity Required

by large London firm. All classes of machining required mainly in small quantities. Material supplied. Long-term orders available for good class machining work at reasonable prices.—Write giving full particulars of plant, normal rates per hour and hours available, etc., to BOX 0998, MACHINERY, Clifton House, Euston Road, N.W.1.

PHOTOGRAPHY

Miles & Kaye, Ltd., 102, Southampton Row, London, W.C.1. Holborn 6858. Specialists in commercial and industrial photography for over 60 years. All branches of photographic work undertaken.

Photographs by MACHINERY

set the standard in engineering publicity. Our studio is one of the best equipped in the country. Ideal for really good photographs of tools, attachments and portable equipment. Mobile units available for taking photographs in black and white or in natural colour in your own or your customers' works. Specimens of work submitted on request.—Full particulars from the SERVICE MANAGER, MACHINERY PUBLISHING COMPANY, LTD., National House, West Street, Brighton, 1

MISCELLANEOUS FOR SALE

For Sale, Patterns, Drawings.

and Goodwill of Two well-known Machines: (1) Keyseating or Slot-drilling Machines from 1in. or less by 6in. up to 34in. by 54in. Ten machines. (2) Swarf or Chip Crushing Machines in three sizes: 2 cwt. per hour, 10 cwt. per hour, 20 cwt. per hour.—BOX V114, MACHINERY, Clifton House, Euston Road, N.W.1.

PRESS TOOLS STAMPINGS

JIGS, FIXTURES,
PRESSURE DIES,
GENERAL MACHINING,
JIG BORING, PRESS WORK,
ETC.

Please send your enquiries to

THE MIDDLETON TOOL & ENG. CO. LTD.
ALEXANDRA RD., PONDERS END, MIDDX.

Telephone: HOWARD 2452/3/4



TIME RECORDERS — Sales —
Rental Service. Tel.: HOP 2239.

TIME RECORDER SUPPLY &
MAINTENANCE CO., LTD.,
157/59, Borough High Street, London, S.E.1

The "Coxeter" Revolving
Centre, from 76s. All sizes from stock.—
REVOLVING CENTRES, LTD., Oxford.

When answering advertisements kindly mention MACHINERY.

SPECIALITIES

MCCROSKY
(BRITISH MADE)

**INSERTED BLADE
MILLING CUTTERS**
Easy accurate setting with
unique Jack-Lock wedge
Sample cutter on request



Write for full details to Small Tools Department.
GEORGE H. ALEXANDER MACHINERY LTD.
82, 83, 84, COLESHILL STREET, BIRMINGHAM 4.

**TAPERLOCK & TRILOCK GAUGE HANDLES
& BLANKS**

Engraving Service Complying to B.S. 1044
Blanks in soft or annealed condition. Handles anodised to your specific colour



BRILHART LTD · HATFIELD · DONCASTER · Tel: Stainforth 595

MINISCREWS


Ex-Stock Delivery Most Sizes 8-14 B.A.
Cut-thread Steel Screws and Nuts.
Swiss Made—Highest Quality.
All Standard Sizes Available.
Automatic Capacity.
HOLBORN 2851.

MINISCREWS Ltd.,
20/21, Took's Court, London, E.C.4.



**Universal
Ball Bearing Co.**
111-115 Hammersmith
Grove, London, W.6
**FACTORS
MANUFACTURERS
AND REPAIRERS**

Phone: Grams: "Universal Bearing
Riverside 3262-3-4. Hammersmith"

**KENNAMETAL**

The Super Grade
Carbide of World
Wide Reputation


**GEORGE H. ALEXANDER
MACHINERY LTD.**

Guns Lane, West Bromwich, Staffs.
Telephone: West Bromwich 1931 (5 lines)
Telegrams: "Viking, West Bromwich"

**'SUPER'
PIPE UNIONS**

with Patent Conical joint.
Can be used on Super-
heated steam.

WALTER SLINGSBY & CO., LTD.
WASK WORKS · KEIGHLEY

SPRINGS

**CLIPS, PRESSINGS & WIRE
FORMS** in all metals

**DENIS FERRANTI METERS
LIMITED**

Bangor, North Wales.
Telephone: Bangor 3232

**FLEXIBLE
METALLIC CONDUIT**
and solderless couplings

For protecting cables leading to
motors, switchboards,
starters, etc.


All sizes from 1/4 in. to 3 in.

THE DONOVAN ELECTRICAL CO. LTD.

(Wholesaling Division)

GRANVILLE STREET · BIRMINGHAM 1

FOR RAPID
SETTING UP OF
ANGULAR
WORK ON ALL
MAGNETIC
CHUCKS



FIMAX
TILTING

ADAPTOR BLOCK is the answer
SPECIALS MADE TO ORDER

PANTON & WEBB

Lavender Hill, Tonbridge, Kent.
Tonbridge 4222

**BRAND NEW BALL & ROLLER BEARINGS**

OVER 4,000,000 IN STOCK IN MORE THAN 4,000 TYPES

BRITAIN'S LARGEST STOCKS

STOCK LIST AVAILABLE

CLAUDE RYE BEARINGS

895-921 FULHAM RD., LONDON S.W.6
RENOWN 6174 (EXT. 24) TELEX 2-3453



When answering advertisements kindly mention **MACHINERY**.

Classified Advertisements (SPECIALITIES, contd.)



THE TOWNSEND RIVETER

Over 1,000 users in the United States of America and Gt. Britain


Illustrated here is the No. 2 Standard Vertical machine $\frac{1}{4}$ " to $\frac{3}{8}$ " diameter of rivet. Production is as fast as operator can handle work.

Please send for catalogue of all models to Dept. M.T.

GEORGE H. ALEXANDER MACHINERY LTD.
82-84 Coleshill Street, Birmingham 4, England.

Albion

COUNTING INSTRUMENTS



(Patented design)
Send for Catalogue
to Instrument Division

B. & F. CARTER & Co. LTD.
BOLTON 19 Bolton 344 (3 lines)

A. E. GALE LTD.
ARCHER ST. WORKS
ARCHER STREET
SHAFTESBURY
AVENUE,
LONDON
W.I.

STEEL STAMPS

FOR MARKING
ALL METALS
WOOD & PLASTICS
PROMPT DELIVERIES
Phone. GERRARD 5051

SERIES III NUCLEAVE PRESS



CROPS
RIVETS
PUNCHES

ASK YOUR TOOL DEALER
Or send for details to:—
Sole Manufacturers

FITZNER LTD.
KINGS RD., KINGSTON, SURREY

JAMES M. SIBTHORP LTD.
Springs and machined parts

100, CECIL ST.
WATFORD, WERTS.
Tel. WATFORD 5388

PACKING AND SHIPPING

R. & J. Park, Ltd., Dominion
Works, Chislewick, England. Export
packers, shippers and forwarding agents.
Specialists in packing heavy machinery.

ANNOUNCEMENTS

BUSINESS OPPORTUNITIES

Sheffield Engineering Firm with comprehensive engineering plant and extensive experience in the design and production of all types of machinery, including special purpose plant, wishes to undertake the manufacture of complete or part assemblies, including assembly line production. Own Drawing Office and Pattern Shop. Technical Representatives in all areas.—BOX 1771, MACHINERY, Clifton House, Euston Road, N.W.1.

CANADIAN and U.S. COMPANY

wishes to associate itself with established British Machinery Sales Company. The purpose of the association would be to market imported machinery in Great Britain and to buy machinery in Great Britain for export to North America.

Interested companies with existing U.K. sales organisation should apply giving short description of present operations.

BOX V202, MACHINERY
Clifton House, Euston Road, N.W.1

FACTORY FOR SALE

Engineers' Factory in Slough area for sale as a going concern. Price £1,500, low rent, 576 sq. ft. floor area, 3 lathes, mill, drill, grinder, benches and small tools.—Write BOX V179, MACHINERY, Clifton House, Euston Road, N.W.1.

PREMISES FOR SALE

Business Premises (Factory) for SALE. Compact, Freehold, Well Lighted Factory of approx. 2,700 sq. ft. Easily increased, near Lewes, licensed light industry includes recently decorated offices and workshops, directors' office, exceptional central heating from solid fuel fired boiler, 3-phase power supply, fluorescent lighting. Development of larger site nearby permits early vacant possession. London buses pass entrance.—BOX V145, MACHINERY, Clifton House, Euston Road, N.W.1.

MATERIALS FOR SALE

STAINLESS STEELS FROM STOCK
THE MULBERRY CO
23A, Sekford Street, London, E.C.1.
CLE 8356. (P.B.X.)

E. Stephens & Son, Ltd., Bath
Street, London, E.C.1. CLE 1721. Tube, Rounds, Flats, Hex. Cut to size. Quick delivery.

K.E. Silver Steel: $\frac{1}{4}$ in., $\frac{1}{2}$ in. and $\frac{3}{4}$ in. square section, full lengths.—SHAW BROS., 6, Bridge Street, York. Tel. 54156.

MATERIALS WANTED

Steel, Aluminium, Brass, Sheets, and Offcuts, 10 to 24g. Small or large quantities. Cash payments.—DYAR & FOWLE 41, Loudoun Rd., N.W.8. MAIDA Vale 2711, 5477.

BRITAIN'S BIGGEST BUYERS

WANT
NEW BALL & ROLLER BEARINGS
OF ALL TYPES & SIZES
CLAUDE RYE BEARINGS
895-921 FULHAM RD. LONDON, S.W.6
RENDOWN 6174 (EXT. 24) - TELEX 2-3453

When answering advertisements kindly mention MACHINERY

PLANT WANTED

WANTED.

WARD NO. 3A CAPSTAN. IN NEW CONDITION, for bar work, with automatic traverse to saddle. With air collet chuck. Motorised 415 volts, 3 phase, 50 cycles.—Please write to BOX V203, MACHINERY, Clifton House, Euston Road, N.W.1.

Wanted, Plain Hydromatic Milling Machine, in good working order. No. 3 or No. 4. Spindle 80 r.p.m., 58in. table traverse, hydraulic feed. Electric 420/3/50. Rebuilt or reconditioned machine preferred.—Full particulars and price to BOX V221, MACHINERY, Clifton House, Euston Road, N.W.1.

Wanted. New Drills, Reamers, Milling Cutters, Lathe Tools, Taps, Die-head Dies, Precision Measuring Tools, Chucks, etc. Also new or slightly used Turret Lathe Tooling, Dieheads, Dividing Heads, Circular Milling Tables, etc.—WEST MIDLAND EQUIPMENT COMPANY, 10, Hagley Road, Stourbridge, Worcs. Stourbridge 4187.

CENTAUR TOOL WORKS, Birmingham, 18, pay best prices for good modern secondhand Machine Tools by first-class makers. Write or phone and our representative will call. Phone: EDGBASTON 1118 and 1119. Grams: Capstan, Birmingham.

WANTED.....

MODERN MACHINE TOOLS OF ALL TYPES

Prompt inspection arranged
Write or 'phone:

NEWMAN INDUSTRIES LIMITED
YATE • BRISTOL

Telephone: CHIPPING SODBURY 3311

Branches:
London Birmingham Manchester Glasgow

WILLIAM
URQUHART

Proprs: Exors.
M. & R. Urquhart

MODERN MACHINE TOOLS
of all types.

GOOD PRICES. Send details to
WM. URQUHART,
1023/27, Garratt Lane, London, S.W.17
Tel: BALHAM 8661

WANTED
ALL TYPES OF MODERN
MACHINE TOOLS

Please write or phone details to:—
THE MIDLAND MACHINE TOOL CO.
BRADLEY, BILSTON, STAFFS.
Tel.: Bilston 41953

*Wanted
Urgently*

Late Type Machine Tools
Best Prices are offered for
latest types of Machine Tools.
Send us details of what you
have and our representative
will call to inspect.

J. B. MACHINE TOOL CO. LTD.
312 BRADFORD ST., BIRMINGHAM 5
Telephone: MIDland 4375



**WE ARE KEEN BUYERS
OF GOOD MODERN
MACHINE TOOLS.**

**INSPECTION WILL BE
ARRANGED AT ONCE.**

M. C. LAYTON LTD.
96-98 VICTORIA STREET,
LONDON, S.W.1

Telephone: VICtoria 7778/9.

WANTED!
USED MACHINE TOOLS

We offer generous prices for your plant or
accept in part exchange for modern equipment

E.H. JONES
MACHINE TOOLS LTD
15 COLINDALE AVENUE LONDON N.W.9

Telephone: COLindale 5681-2-3
Midland 5993 Birmingham.

A. LAWRENCE & CO. (MACHINE TOOLS) LTD.

will be pleased to purchase
your surplus Modern
Machine Tools either on a
cash or part exchange basis.
Ask our representative to
call and inspect.

**Welsh Harp, Edgware Road,
London, N.W.2**

Telephone: GLAdstone 0033

SURPLUS MACHINE TOOLS REQUIRED

OFFER YOUR MACHINES TO

J. E. RAISTRICK LTD.

POYLE TRADING ESTATE
COLNBROOK, SLOUGH,
BUCKS.

TEL: COLNBROOK 421

WANTED GOOD MACHINE TOOLS

Offer your Surplus Tools
to us. We pay a good price

M. WARD
(MACHINE TOOLS) LTD.
1, KILBURN HIGH ROAD,
LONDON, N.W.6

MAIDA VALE 1195-96
Telegrams: Emwarner, Kil., London
One minute from Kilburn Park Station
Bakerloo Railway
2 us.

WANTED MODERN MACHINE TOOLS

We pay cash for single machines
or complete plants

SEND US DETAILS
IMMEDIATE INSPECTION ARRANGED

**SOUTHERN ENGINEERING
AND MACHINERY CO.**

CONNAUGHT BUILDINGS
TANNERS BROOK, MILLBROOK
SOUTHAMPTON

Telephone: Southampton 72325 and 73101

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT WANTED, contd.)

HIGHEST PRICES PAID...

... FOR YOUR SURPLUS MACHINE TOOLS
WHOLE PLANTS OR SINGLE MACHINES
WRITE OR TELEPHONE FOR OUR REPRESENTATIVE TO CALL
DISTANCE NO OBJECT

LITTON'S MACHINE TOOL CO. LTD.
372 OLD STREET, LONDON, E.C.1

Telephone: SHOREDITCH 4814/5

RE-BUILDING MACHINE TOOLS

Have your machines rebuilt out of revenue and save capital outlay. Immediate capacity available. Work guaranteed to Manufacturer's limits.

MUNNGLEN ENGINEERING LTD
258, Grays Inn Rd., W.C.1. TEL. 9879

Harry Kirk Will Purchase modern quality machine tools for cash. Whole plants or individual items.—Full details to:—

HARRY KIRK ENGINEERING, LTD.,
Machine Tool Division,
Brandon Road Works,
Brandon Road, Coventry.
Telephone: Walsgrave-on-Sowe 2213/4.

B.G. MACHINERY, LTD.
Montgomery Street, Sparkbrook, Birmingham, 11, will pay good prices for Machine Tools of first-class make and in good condition.—Phone: VICTORIA 2351/9.

Wanted. Machine Tools of All Types, especially later war and post-war models.—Please send details to: **H. BELL (MACHINE TOOLS), LTD.,** Walter Street, Leeds, 4. Tel.: 63-7398.

Required, One Reed Prentice No. 2V Vertical Milling Machine, in good condition.—Reply giving details and price to **BOX V206, MACHINERY, (Clifton House, Euston Road, N.W.1).**

Die Casting Machines Wanted. IMP. 98, M55A and M56 or larger.—**BOX V85, MACHINERY, (Clifton House, Euston Road, N.W.1).**

Vertical Drill with Adjustable multi-head, 14 spindles, No. 2 M.T. Vertical Drill, No. 4 M.T., 12in. stroke. Production Vertical Mill, about 8 h.p. Spindle. Condition and full details to **BOX V246, MACHINERY, (Clifton House, Euston Road, N.W.1).**

Machine Tools and Sheet Metal Working Machinery, modern items of all types required.—**CHARLES E. MATTHEWS (MACHINE TOOLS), LTD.,** 84, Gladstone Road, Croydon. (Thornton Heath 1783.)



WHETHER BUYING OR SELLING
USED MACHINE TOOLS

Contact:—
K.E.N.T. MACHINERY & ENG. CO.
Datchelor Place Mews, London, S.E.5.
Telephone: ROD 4149.

Wanted. Reasonably Modern machine tools and sheet metal working machinery. Best prices paid.—**W. FORREST & CO., LTD.,** Industry Works, Sylvester Gardens, Sheffield, 1. Sheffield 23314/5.

Norman E. Potts (B'ham), LIMITED, will pay cash for Surplus or Redundant Machines. Full details to: 130, Moseley Road, Birmingham, 12. Telephone: VIC. 1278, 1279, 1270, 0856.

Wanted: Cylindrical Grinding Machine, 20in. by 120in. approximately. Make—Immaterial. One requiring repairs accepted if price satisfactory.—**FRED GILBERT (CARDIFF), LTD.,** Canal Parade, Cardiff.

Wanted, Medium Sized Vertical Milling Machines, full details to—**A. McNAMARA & CO.,** New Line, Bacup, Lancs. Phone: Bacup 946.

Wanted, 3rd Slide and Other equipment for 1in. Butterworth Automatic, also Centrifugal oil separator and ratio scales. **LIB 4103.—LONGFIELD PRECISION, 14B, Merton Park Parade, S.W.19.**

Perspex Sheets Wanted. 6in. corrugations, ex. Govt. or clearance stock.—**BOX V244, MACHINERY, (Clifton House, Euston Road, N.W.1).**

WANTED
GOOD CLASS MACHINE
tools and sheet metal
machinery.

EDWIN MILLEN
78 Clerkenwell Road, London, E.C.1
Phone: CLERKENWELL 4664

Private Buyer Wishes to Purchase Copy Lathe, Ward 2As, 3As, No. 7 C.Ts. and Cincinnati No. 2 and 3 Dial Type Plain Millers, approx. 2 off each machine wanted. Condition immaterial. Also Plain Grinder approx. 12in. by 60in., modern machine only acceptable.—Please send full details, specifications and prices to **BOX V136, MACHINERY, (Clifton House, Euston Road, N.W.1).**

Wanted, Secondhand Dead Length Collet Chucks to suit 28 Herbert Capstans. Please state price and where seen.—**BOX V141, MACHINERY, (Clifton House, Euston Road, N.W.1).**



We invite particulars of your surplus machines
SOAG MACHINE TOOLS LTD.
7, JUXON ST., LAMBETH, LONDON, S.E.11
Phone: RELIANCE 7301.
Grams: 'Soagtooling' London.

Machine Tools, Power Presses and Sheet Metal Machinery. Single machines or complete plants purchased. Immediate inspection.—**ALBERT EDWARDS (MACHINERY), LTD.,** 79/89, Pentonville Road, London, N.1.

TENDERS

NOTTINGHAMSHIRE COUNTY COUNCIL.
Tenders are invited for the provision of machinery and certain small tools required for Mansfield College of Further Education. Items required include hydraulic surface grinders, millers and lathes.—Further details and Tender Forms obtainable from the SUPPLIES OFFICE, County Hall, West Bridgford, Nottingham, and completed tenders should be returned to the undersigned by 15th February, 1958.

A. R. DAVIS,
Clark of the County Council.
Shire Hall,
NOTTINGHAM.

For further "Plant Wanted" and "Tender" Advertisements, see end of "Plant for Sale" section.

When answering advertisements kindly mention MACHINERY.

PLANT FOR SALE

HENRY BUTCHER & CO.

Specialists in the

• VALUATION AND SALE OF FACTORIES, PLANT AND MACHINERY •

73 CHANCERY LANE, LONDON, W.C.2

TEL: HOLBORN 8411 (8 lines) GRAMS: PENETRANCY, HOLB., LONDON

Craven 6ft. Double Upright Vertical Boring and Turning Mill with two saddles on the cross slide. Motorised 400-440 volts, 3 phase, 50 cycles A.C. supply. NEW. Immediate Delivery. — W. E. NORTON (MACHINE TOOLS), LTD., Grosvenor Gardens House, Grosvenor Gardens, London, S.W.1. Phone: Tate Gallery 0633/4. Cable: Norbros, London.

A Good Number of High-class Machine Tools always in stock.—ELLIXON, Cook Street, off Chapel Street, Salford 3, Lancs.

A SELECTION OF FIRST CLASS MILLING MACHINES AVAILABLE FOR IMMEDIATE DELIVERY

MILWAUKEE 2H Vertical 35/1,400 r.p.m. **MAS No. 2 Universal**, 29/750 r.p.m. Table 50in. x 12in.

MAS No. 2 Vertical, swivel and sliding head. Table 50in. x 12in.

CRAVEN S.2 Universal Rigidmill with auxiliary spindle and Vertical head.

RICHMOND 03SD Universal, dividing head, etc.

PARKSON No. 14 Face Miller. Table 82in. x 20in.

CINCINNATI No. 2 Vertical, and Horizontal.

BIERNATZKI No. 4 Vertical. Table 62in. x 14in.

EDGWICK No. 1 Keyseater.

HERBERT No. 1 Automatic Cycle Millar.

PALLAS No. 2 Horizontal, table 30in. x 7in.

WICKMAN-MOULTON No. 1 Thread Miller.

W. FORREST & CO. LTD.
INDUSTRY WORKS,
SYLVESTER GARDENS,
SHEFFIELD, 1.

'Phone: Sheffield 23314/5.

Holbrook 6½in. A.G.H. Mot. Tool-room Lathe, Norton gearbox, taper turning and collets.

COVMAC 6½in. A.G.H., mot. G.B. Lathe, good equipment.

COLCHESTER 6½in. Master Lathe. Good equipment.

SMART & BROWN "Sabel" 4½in. Lathe. Norton gearbox, collets, steadies, chucks, on bench.

EDWIN MILLEN,
70, Clerkenwell Road,
London, E.C.1.
'Phone: Clerkenwell 6064.



RUNNING SHORT?

REMEMBER...

WARDS might have it!

THOS. W. WARD LTD
ALBION WORKS, SHEFFIELD

Bradford 16in. Centre Lathe, 2ft. 6in. bed length. 3 cone pulley and back gear. Built on motor drive and countershaft, 2 speed motor, 3 h.p., 3 phase, 1420/710 r.p.m., 3-1 reduction to countershaft. Full screwcutting range. With switchgear and push button starter, 6in. dia. 3-jaw chuck, 8½in. Taylor chuck, 9in. and 16in. faceplates and 3-point steady, 4-way toolpost and collet adaptor. BOX V184, MACHINERY, Clifton House, Euston Road, N.W.1.

One Avery Two-spindle Pedestal

Drill, Serial No. 18284. High speed sensitive drill, Spindle speeds 4,100-9,600 r.p.m. Rise and fall table. Table working surface 12in. by 23in. Motor speed 2,880 r.p.m., 400-440/3/50.—BOX V351, MACHINERY, Clifton House, Euston Road, N.W.1.

Incandescent Heat Gas-fired Air

Re-circulating Tempering Furnaces for sale. Fitted with lift-out baskets and Pyrometric control by Cambridge and Electroform Recorder Instruments. Pyrometric recording of top and bottom areas in furnace. Temperature range of 0-750 deg. C. is regulated by the Cambridge recorders through an electrically controlled Satchwell Gas Valve. Outside dims.: 56in. dia. by 55in. high. Inside dims.: 25in. dia. by 31in. deep. Container: 22in. dia. by 21in. deep.—BOX T668, MACHINERY, Clifton House, Euston Road, N.W.1.

Reconditioned 300 Watt Dialectic Heater Unit for sale

approx. 6 amps. Suitable for wood glueing or plastic welding. Reconditioned.—BOX T618, MACHINERY, Clifton House, Euston Road, N.W.1.

LANG 13½in. S.S. & S.C. Straight Bed Lathe, 6 ft. between centres, motorised 400/3/50.

PARKES (MACHINE TOOLS) LTD.

WITTON ROAD, BIRMINGHAM, 6.
Tel: EAST 1742.

Denbigh (New) Type CVSR4

Semi-Universal Milling Machine, quick return table 46in. by 10in., motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Reconditioned Wild-Barfield

Furnace. High speed hardening and tempering furnace. 0-1,400 deg. C. hardening; 0-1,000 deg. tempering. Hardening 18 kW 415/3/50, 6in. by 18in. by 6in. high. Tempering 3.6 kW 415/3/50, 7½in. by 18in. by 5in. high. With wire resistance control. Gas and air flow meters for hardening. Built-in contactor unit. Air cooled transformer.—BOX T698, MACHINERY, Clifton House, Euston Road, N.W.1.

William Allday Oil-fired Fur-

nace complete with fuel tank and injector No. E4792. Inside dims.: 12in. wide by 6in. high by 20in. deep.—BOX T681, MACHINERY, Clifton House, Euston Road, N.W.1.

SHEET METAL MACHINERY · MACHINE TOOLS · WOODWORKING MACHINERY

A large range of all types IN STOCK—both NEW and USED. Send for particulars

F.J. Edwards Ltd

When answering advertisements kindly mention MACHINERY

EDWARDS HOUSE,
359-361, EUSTON ROAD,
LONDON, N.W.1.
Phone: Euston 4631 & 3771
and at LANSDOWNE HOUSE,
41, WATER STREET,
BIRMINGHAM, 3.
Phone: CENTral 7606-8

Cashmores

Selection of Machine Tools
from Stock.

CENTRE LATHES.
COLCHESTER MASCOT 8 1/2 in. S.S. & S.C. Lathe, to admit 4 ft. 6 in. between centres, motorised 400-440/3/50 cycles.
New MITCHELL OF KEIGHLEY 12 1/2 in. S.S. & S.C. Lathe, to admit 8 ft. 9 in. between centres, motorised 400-440/3/50 cycles.
VOLMAN 8 in. S.S. & S.C. Gap Bed Lathe, to admit 4 ft. 6 in. between centres, motorised 400-440/3/50 cycles.
New MITCHELL OF KEIGHLEY 10 1/2 in. S.S. & S.C. Lathe, to admit 7 ft. 5 in. between centres, motorised 400-440/3/50 cycles.
F.L.C.B. 13 in. S.S. & S.C. Heavy Duty Lathe, to admit 17 ft. between centres, 2 saddles. Motorised 400-440/3/50 cycles.
7 1/2 in. LE BLOND S.S. & S.C. Lathe, 16 in. swing with steadies, chucks, etc. Motorised 400-440/3/50 cycles.

CAPSTAN LATHES.
WARD 3A Capstan Lathe, with collet chuck and bar feed, 1 1/4 in. capacity, motorised 400-440/3/50 cycles.

WARD No. 7 Capstan Lathe, with covered bed, arranged for chuck work, 2 1/4 in. hollow spindle, motorised 400-440/3/50 cycles.

WARD 2A Capstan Lathe, with collet chuck and bar feed, 1 1/4 in. capacity, motorised 400-440/3/50 cycles.

UNIVERSAL GRINDING MACHINE.
LANDIS 16 in. by 36 in. Universal Grinding Machine, with hydraulic feed. Motorised 400-440/3/50 cycles.

DRILLING MACHINE.
KITCHEN & WADE 4 ft. 6 in. Radial Drilling Machine, elevating arm, with nose bar bed, two-motor type, 450-400/3/50 cycles.

PLAIN GRINDING MACHINE.
CHURCHILL 10 in. by 36 in. Hydraulic Plain Cylindrical Grinding Machine, 400-440/3/50.

MILLING MACHINES.
HERBERT Milling Machine, 23V Vertical, 68 in. by 17 in. table, motorised 400-440/3/50.

CINCINNATI No. 3 Dial Type Vertical Milling Machine, 62 1/2 in. by 15 in. table, motorised 400-440/3/50 cycles.

ARCHDALE 18 in. Vertical Milling Machine 38 in. by 10 in. table, motorised 400-440/3/50 cycles.

CRAVEN "Rigidmill" Production Milling Machines, working surface of table 39 in. by 13 in., spindle speeds 25-400 r.p.m., motorised 400-440/3/50 cycles. Two machines available.

EDGWOOD 18 in. Production Milling Machine, working surface of table 26 in. by 12 in., motorised 400-440/3/50 cycles.

NEW VICTORIA U1, U2 and U3 Universal Milling Machines, motorised 400-440/3/50.

ADCOCK & SHIPLEY No. 1 Plain Horizontal Milling Machine, 26 in. by 7 in. table, motorised 400-440/3/50 cycles.

ARCHDALE 20 in. Horizontal Plain Milling Machine, 40 in. by 10 in. table, motorised 400-440/3/50 cycles.

RICHMOND Model VHM Vertical Milling Machine, 26 in. by 8 in. working surface of table. Power feed to table. Motorised 400-440/3/50 cycles.

CUTTAT HYPERMIL Production Milling Machine, 43 in. by 10 in. working surface of table, with 4 automatic cycles to table. Motorised 400-440/3/50 cycles.

SAWING MACHINES.
RUSSELL 26/30 in. and 20/24 in. Cold Circular Sawing Machines, with hydraulic clamping to vice, motorised 400-440/3/50 cycles.

NOBLE & LUND 11/16 in. Cold Circular Sawing Machine, motorised 400-440/3/50 cycles.

SLOTING MACHINE.
BUTLER 8 in. Stroke All Geared Slotting Machine, with circular table, power feed to all motions, motorised 400-440/3/50 cycles.

SURFACE GRINDING MACHINES.
SNOW 92LE Vertical Spindle Rotary Table Surface Grinder, 48 in. diameter table, motorised 400-440/3/50 cycles.

SNOW P24 Hydraulic Horizontal Spindle Surface Grinder, 24 in. by 8 in. capacity. Motorised 400-440/3/50 cycles.

JOHN CASHMORE LTD.

NEWPORT 1, MON.
Tel.: Newport 6941 (5 lines).
(Also at Great Bridge, Staffs.)

MACHINERY

Classified Advertisements (PLANT FOR SALE, contd.)

Southwark No. 2 Capstan, Series

630. 4 speed motor combined with 3 cone pulley and high and low clutch lever gives 24 speeds from 25 to 2,560 r.p.m. 6 Power feeds to turret. Back and front toolposts. Fitted to take air chuck. Extension bottle. Suds pump and tank.—BOX V191, MACHINERY, Clifton House, Euston Road, N.W.1.

492 IN STOCK...

MACHINE TOOLS

New Used and Rebuilt Machine Tools in stock. Comprising: Autos, Boreers, Broaching, Drills, Gear Cutters, Grinders, Capstans, Combs., Millers, Planers, Presses, Sheet Metal Machines. U.K. Agent for H.M.V. (Swedish) Universal Borer (one month delivery), Scott Sheet Metal Tools, C.V.A. Chucks and Bullochs Compressors all ex-stock. Write for our priced Brochure covering the complete stock held at.



Precision Rebuilders to the grade, Admiralty & Atomic Energy Authority
MARTIN BROS. (Machinery) LTD.
CORNBURK, MANCHESTER 16
Phone: Trafford Park 1091/2

Walcott 9 in. by 5 ft. Lathe. Series

AJFM9940. Swing 16 1/2 in. dia. over bed. 44 h.p. 2-speed motor, 3 cone pulley built on counterhaft, with back gear gives 12 speeds. Top speed approx. 500 r.p.m. Pick-off gearbox for feeds and screwcutting gives 48 selections from 2 to 112 t.p.i. With 12 in. dia. 4-jaw chuck, 16 in. dia. faceplate, 3-point and travelling steady.—BOX V197, MACHINERY, Clifton House, Euston Road, N.W.1.

Two Walter Palser Gas-fired

Muffle type Furnaces by Incandescent Heat Co. Fitted with Nickel chrome slippers and a gas purge at mouth, which is shrouded to control the atmosphere. Both furnaces are electronically controlled by Cambridge Recorder instruments. 0-1,000 deg. C. Approx. outside dims.: 48 in. wide by 52 in. deep by 37 in. high. Mounted on stand. Inside dims. of the muffle: 20 in. wide by 9 in. high, 2 ft. 6 in. front to back. The throat of the muffle has been reduced to 6 in. high by 18 in. wide.—BOX T672, MACHINERY, Clifton House, Euston Road, N.W.1.

Ballinger Abrasive Cut-off Machine

for sale. Type A1193. Motorised 415/3/50, 5 h.p. Fitted with wheel load indicator meter, safety time switch to wheel guard. Foot operated stop clamp.—BOX T679, MACHINERY, Clifton House, Euston Road, N.W.1.

Internal Grinder, Automatic

cycle. Churchill model H.B.A. Rebuilt 12 1/2 in. dia. faceplate, 4 speeds 98-350 r.p.m. Hydraulic powered traverse, 18 in. variable feed. Work head swings 30 deg. and moves 18 in. laterally. Swivel 18 in. Built-in coolant pump. Electric 400/3/50.—BOX T693, MACHINERY, Clifton House, Euston Road, N.W.1.

Harrison (New) 11 in. Swing

S.S. & S.C. Gap Bed Centre Lathe, 24 in. between centres, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

LANG 8 1/2 in. S.S. & S.C. Gap Bed Lathes, 4 ft. between centres, motorised 400/3/50.

PARKES (MACHINE TOOLS) LTD.

WITTON ROAD, BIRMINGHAM 6.
Tel.: EAST 1742.

Hanson & Whitney Thread Mill-

4 in. by 9 in. Fully motorised and well equipped.—BOX V250, MACHINERY, Clifton House, Euston Road, N.W.1.

Cashmores

Selection of Machine Tools
from Stock or Early Delivery.

DRILLING MACHINES.

ASQUITH 4 ft. 9 in. Portable Universal Radial Drilling Machine, No. 4 M.T. spindle, 6 speeds 41/300 r.p.m., motorised 400/3/50 cycles supply.

LATHES.

MILES 15 in. Centre Heavy Duty Lathe, fitted with two saddles, to admit 27 ft. 0 in. between centres, swing over saddles 26 in. diameter, motorised 400/3/50 cycles.

LANG 15 in. Centre Heavy Duty Lathe, fitted two saddles, admit 16 ft. between the centres, swing over saddles 23 in. diameter, motorised 400/3/50 cycles.

New MITCHELL 12 in. Centre Gap Bed Lathe, admit 8 ft. 9 in. between centres, motorised 400/3/50 cycles.

HERBERT No. 12 All Geared Head Combination Turret Lathe, with roller bearing spindle, patent covered pneumatic bed, swing over bed 23 1/2 in., swing over cross slide 15 1/2 in. dia., 6 in. hollow spindle, 16 spindle speeds 15/598 r.p.m. Motorised 400/3/50 cycles.

HOLBROOK Model B Type No. 17 S.S. & S.C. Lathe, swing over bed 18 in. dia., admit 42 in. between centres, range of spindle speeds 10/526 r.p.m., motorised 400/3/50 cycles.

New MITCHELL 10 1/2 in. Lathe, 7 ft. 5 in. between centres, motorised 400/3/50 cycles.

SMALLPIECE No. 9 WSL Multi-cut Production Lathe, motorised 400/3/50 cycles.

WARD No. 2A Capstan Lathe, power feed to saddle and turret, ball chuck and bar feed, motorised 400/3/50 cycles.

WARD No. 3A Capstan Lathe, arranged for chuck work, six spindle speeds 84/1,650 r.p.m., motorised 400/3/50 cycles supply.

VERTICAL BORING MACHINE.

WALDRICH Single Column Type Vertical Turret Lathe, fitted pentagon turret on cross rail, side head, maximum swing 70 in. dia., motorised 400/3/50 cycles.

GRINDING MACHINES.

NEWALL 6 in. by 18 in. Hydraulic Plain Cylindrical Grinding Machine. D.C. variable speed workhead, speeds 365/3,000 r.p.m., built-in AC/DC rectifier for supplying current to workhead, hydraulic feed to table, motorised 400/3/50 cycles.

NEWALL 10 in. by 48 in. Hydraulic Plain Grinder, Model L, motorised 400/3/50 cycles.

REINECKER 21 in. by 66 in. Hydraulic Plain Grinder, motorised 400/3/50 cycles.

ORCUTT 20 in. Hydraulic Spindle Shaft Grinder, motorised 400/3/50 cycles.

CHURCHILL 12 in. by 36 in. Hydraulic Universal Grinder, with internal spindle and equipment, motorised 400/3/50 cycles.

MILLING MACHINES.

New VICTORIA Model U2 Universal Miller, table 45 in. by 11 in., motorised 400/3/50 cycles.

New VICTORIA Model V2 Vertical Miller, table 45 in. by 11 in., motorised 400/3/50 cycles.

BOHLE Heavy Duty Universal Miller, table 55 in. by 14 in., motorised 400/3/50 cycles.

SLOTING MACHINE.

MUIR 30 in. Stroke Slotting Machine, 50 in. by 50 in. table, motorised 400/3/50 cycles.

12 in. ORMEROD High Speed Slotting Machine, diameter of rotary table 2 ft. 3 in., distance centre of tool to frame 28 in., longitudinal traverse of table 24 in., motorised 400/3/50 cycles supply.

MISCELLANEOUS.

MASSEY 2 cwt. and 1 cwt. Slide Type Pneumatic Power Hammers, motorised 400/3/50 cycles.

WEINGARTEN Punching and Shearing Machine, cut plates 1/2 in. thick, punch dia. holes through 1/2 in. plate, crop 51 angles, motorised 400/3/50 cycles.

CLYDE 5 Ton Three Motor Overhead Travelling Crane, span 34 ft., floor controlled, totally enclosed gearing, motorised 400/3/50 cycles supply.

ERODES 160 Ton Vertical Double Sided Single Crank Geared Power Press, 8 in. stroke, bed area 38 in. by 24 in., motorised 400/3/50 cycles.

JOHN CASHMORE LTD.

GREAT BRIDGE, STAFFS. Tel.: Tipton 218
(Also at NEWPORT, MON.)

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

NEW
6ft. 0in. by 1in. CAPACITY
BENDING ROLLS
EX STOCK
W. FORREST & CO. LTD.
 Industry Works, Sylvester Gardens,
 SHEFFIELD, 1.
 'Phone. 23314/5.

Progress No. 5E (New) Pillar
 Drilling Machine. Compound table. 2in.
 capacity, motorised 400/3/50.—SOUTHERN
 ENGINEERING & MACHINERY CO., Con-
 naught Buildings, Tanners Brook, Millbrook,
 Southampton. Tel.: Southampton 73101.

CRANES FOR HIRE
SMITHS "21" CRAWLER CRANE.
 10 Ton Max. Load with 30 ft. Boom.
 4 Ton Max. Load with 80 ft. Boom.
SMITHS "ME" LORRY MOUNTED
CRANE. 15 Ton Max. Load with 30
 ft. Boom. 4 Ton Max. Load with 80 ft.
 Boom.

ROBERT CORT AND SON,
 Reading Bridge, Reading,
 Berks. Tel.: Reading 55046.

Incandescent Two-chamber Gas
 Heated Furnace for sale. With air blast,
 two burners, and mixture controller. Keith
 Blackman 15in. diameter rotary blower direct
 coupled to 400/3/50 motor. Water gauge and
 pyrometer, for temperatures up to 1,000 deg. C.
 Two chambers one above the other, 9 1/2in. by
 17 1/2in. by 6 1/2in. high.—F. J. EDWARDS,
 LIMITED, 359, Euston Road, London, N.W.1
 or 41, Water Street, Birmingham, 3.

1958 SPANNER BARGAIN EX. GOVT.
 Assortment of seventy Useful NEW
 Spanners, comprising of Whit., B.A.,
 S.A.E., Metric, A/F, etc., D.O.E., S.E.,
 Ring, Box, Sockets, etc. List value
 over £20, our price 110s., plus carriage.
 Money Refund Guarantee. This is a
 very useful lot to have. Order now or
 further details write: **WM. HURLOCK**
JNR. LTD., 5/7, Kingston Hill,
 Kingston-on-Thames.

Jones & Shipman 540 18in. by
 6in. Hydraulic Surface Grinder.
BROWN & SHARPE No. 2 18in. by 6in.
 Surface Grinder.
SCHUTTE 24in. by 8in. Heavy Duty Vertical
 Spindle Surface Grinder, segmental wheel.
EDWIN MILLEN,
 70, Clerkenwell Road,
 London, E.C.1.
 'Phone: Clerkenwell 6064.

DEAN, SMITH & GRACE 10 1/2in. S.S. & S.C.
 All Geared Head Gap Bed Lathe, 9ft.
 between centres, motorised 400/3/50.

PARKES (MACHINE TOOLS) LTD.
 WITTON ROAD, BIRMINGHAM, 6.
 Tel.: EAB 1742.

Wicksteed Power Saw. Serial
 No. C370. Hydraulic feed to saw and to
 clamp. Has a large capstan wheel for adjust-
 ment to clamp. Can also be clamped manually.
 Saw dia. 27in. by 1in. thick by 3in. hole. Two
 tooling holes 1/2in. by 5in. centres. Clamping
 box 6 1/2in. dia. Saw capacity 10in.—BOX V264,
 MACHINERY, Clifton House, Euston Road,
 N.W.1.



NEW MACHINE TOOLS FROM STOCK

GRANOR OF HALIFAX 11in. Gap Bed
 Lathe by 8ft. 0in. b.c. Hole in spindle
 3 1/2in. dia. 400-440/3/50.

MITCHELL OF KEIGHLEY 10 1/2in. Gap
 Bed Lathe x 5ft. 5in. B.C. 400-440/3/50.
EXCEL No. 3/12 Hydraulic Horizontal
 Spindle Surface Grinding Machine. Capa-
 city 24in. by 8in. Coolant equipment.
 Motorised 400-440/3/50.

VICTORIA V2 Vertical Milling Machine.
 Spindle speeds 32-1,050 r.p.m. Table
 45in. by 11in. Table traverse 29in.
 400-440/3/50.

NEW MACHINE TOOLS— EARLY DELIVERY

MITCHELL OF KEIGHLEY 8 1/2in. Gap Bed
 Lathe by 5ft. 3in. b.c. 400-440/3/50.
 Delivery—February, 1958.

MITCHELL OF KEIGHLEY 12 1/2in. Gap Bed
 Lathe by 6ft. 9 in. b.c. 400-440/3/50.
 Delivery February, 1958.

VICTORIA U2 Universal Milling Machine.
 Spindle speeds 30-1,010 r.p.m. Table
 45in. x 11in. Longitudinal traverse 30in.
 400-440/3/50.

USED MACHINE TOOLS

NORTON Horizontal Spindle Hydraulic
 Surface Grinding Machine, with hydraulic
 cross feed head. Capacity 48in. by 10in.
 Complete with D.C. magnetic chuck and
 generator. Coolant pump and fittings.
 400-440/3/50.

HERBERT 2D Capstan Lathe with draw
 back collet and power feed. Power feed
 to turret slide 400-440/3/50.

NEWALL Hydraulic "XL" 6in. by 18in.
 Plain Grinding Machine. 400-440/3/50.

NEWALL Type L. 10in. by 24in. Plain
 Grinding Machine. 400-440/3/50.

DENHAM 5 1/2in. by 2ft. 3in. B.C. A.G.H.
 S.S. & S.C. Gap Bed Bench Lathe, vee-
 rope motor drive.

STANLEY 7in. by 3ft. 0in. b.c. Gap Bed
 A.G.H. and S.C. Lathe. Vee Rope motor
 drive. 400-440/3/50.

LE BLOND A.G.H. S. & S. Lathe, 15in.
 dia. swing. 400-440/3/50.

**CHURCHILL-REDMAN 24in. N.D. Sur-
 facing and Boring Lathe. Hexagon**
 turret. Swing in gap 38in. dia. by 19in.
 wide. 400-440/3/50.

WICKSTEED 30in. dia. Hydraulic Cold
 Sawing Machine, hydraulic clamping,
 electric 400-440/3/50.

CLIFTON & BAIRD 30in. dia. Hydraulic
 Cold Sawing Machine, with hand clamp-
 ing, electric 400-440/3/50.

WE UNDERTAKE REBUILDING OF
ALL TYPES OF MACHINE TOOLS.

CENTAUR TOOL WORKS,
 EYRE STREET, SPRING HILL,
 BIRMINGHAM, 18.

Tel.: EDGbaston
 1118 & 1119.

'Gemma:
 Capstan, Birmingham.

Boley Lever Operated Lathe.

Series 320. Fitted with compound slide
 and back and front toolposts. 25 collets mostly
 metric 3.9 mm. to 1 1/4 in. and 6 multisize
 collets taking up to 3 1/4 in. dia.—BOX V204,
 MACHINERY, Clifton House, Euston Road,
 N.W.1.

One Phillips 20 kW Induction

Heater Unit. Type No. FV45/1. Has run
 6,447 hours. Fitted with manual and remote
 controls. Sumlock time switch. A.C. volts
 rectifier instrument showing rectifier filament
 volts. 0-5 F.C. D.C. ampere meter 0-1. A.C.
 volts rectifier 0-25 F.C. Filament volts. D.C.
 Kilovolts. 0-12 Anode volts. D.C. amperes
 0-5 anode current indicators. Switch position
 of frequency: B.D. 500 Kc/s, A.D. 400 Kc/s,
 C.D. 320 Kc/s, A.E. 220 Kc/s, C.E. 175 Kc/s.
 The switches select the frequencies. Surround
 for screening. Overall dimensions, not including
 screening: 8ft. long, 5ft. deep 6in. high.—
 BOX V257, MACHINERY, Clifton House, Euston
 Road, N.W.1.

Churchill-Redman 9in. Gap Bed

Lathe. Serial No. 4146/30. Flat bed
 heavy duty lathe. Swing over bedways
 18 1/2in.-4ft. 6in. between centres, 36in. in gap
 by 13in. Motor drive mounted on top of geared
 head giving 12 spindle speeds from 10.5 to
 280 r.p.m. Screwing and feeding through
 gearbox giving 40 feeds from 3 to 40 per inch
 and threads of equal value by 4. Heavy duty
 leadscrew with a 4 t.p.i. lead. Equipment:
 4-way toolpost mounted on compound slide,
 32in. dia. faceplate, 16in. dia. 4-jaw independent
 chuck, 12in. dia. 3-jaw concentric chuck,
 3-point steady, 2-point travelling steady.
 Belt drive suds pump, 7.5 h.p. motor. Isolator.
 Allen West starter. Electrics 400-440/3/50.—
 BOX V227, MACHINERY, Clifton House, Euston
 Road, N.W.1.

One Herbert No. 3 Capstan Lathe.

Geared head. Spindle speeds: 6 speeds;
 60-1,500. Hole through table, 6 holes
 40-480 and reverse. Motorised, Alfred Herbert
 motor, 940 r.p.m. No. 7312076, 5 h.p., 400-
 440/3/50. Motor pump, 1/10th b.h.p. for coolant
 supply. 3-jaw chuck (Herbert) and switchgear.
 4-way toolpost. Power traverse to saddle and
 cross slide and turret.—BOX V237, MACHINERY,
 Clifton House, Euston Road, N.W.1.

Massey 5-cwt. Pneumatic Power

Hammer. Overhauling type with slides
 Longest stroke 21in. Number of automatic
 blows per minute 140. Anvil set at an angle
 to accommodate long bars. Arranged direct
 motor drive. Complete with anvil. Centre to
 back 18in. Size of bar worked 6in. square.
 Weight about 6 1/2 tons.—F. J. EDWARDS,
 LIMITED, 359, Euston Road, London, N.W.1.
 Euston 4681, or 41, Water Street, Birmingham,
 3. Central 7606-8.



NEW HORIZONTAL AND VERTICAL BORERS

UNION 2 1/2in. Model BFT.63 Horizontal Boring
 and Facing Machine. Table Type.

UNION 3 1/2in. Model BFT.90 Horizontal Boring
 and Facing Machine. Table Type.

UNION 4in. Model BFT.100 Horizontal Boring
 and Facing Machine. Table Type.

UNION 5in. Model BFT.125 Horizontal Boring
 and Facing Machine. Table Type.

UNION 6in. Model BFT.150 Horizontal Boring
 and Facing Machine. Floor Type.

UNION 6 1/2in. Model BFT.160 Horizontal
 Boring and Facing Machine. Floor Type.

UNION 8in. Model BFT.200 Horizontal Boring
 and Facing Machine. Floor Type.

NILES 52in. Single Column Vertical Boring
 and Turning Mill, Model DKES.1320.

NILES 6ft. 6in. Double Column Vertical Boring
 and Turning Mill, Model DKZ.2000 x 1250.

NILES 13ft. Double Column Vertical Boring
 and Turning Mill, Model DKZ.4000 x 2000.

EARLY DELIVERY.

DEMONSTRATION BY APPOINTMENT.

Write for details.

DIMCO LTD.

415, 417, OXFORD STREET, W.1
 PHONE MAYFAIR 1585 (4 LINES)

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

THE HELIOT MACHINE TOOL CO.
BLACKHEATH HILL, GREENWICH, S.E.

Tilburyway 2819 and 4888.

All machines motorised 400/3/50 unless otherwise stated.

CAPSTAN LATHES.

WARD No. 7 bar feed and collet head.
WARD No. 7 chucking.
WARD 3A, bar feed and collet head.
WARD 3A, chucking.
WARD 2A, with bar equipment, rebuilt.
WARD 2A, bar feed and collet head.
WARD 2A, chucking.
WARD 2A, with bar equipment, rebuilt.
WARD 1A, bar feed and collet head.

TURRET LATHES.

WARD No. 7 Combination 21in. spindle, S.S. & S.C. (not covered bed).
WARD No. 7 Combination turret, C.B.
WARD 10/13 Combination turret, C.B.
WARD No. 10 comb., extended bed, C.B.
LIBBY 1/H6 3in. Hollow Mandrel.

CENTRE LATHES.

WARD 15in. by 25ft. between S.S.
D.S. & S.C. 12in. facing lathe, S.S. & S.C.

HORIZONTAL MILLERS.

ARCHDALE 25in. general purpose miller.
ARCHDALE 20in., 37in. by 10in. table.
MILWAUKEE 1H-12, 33in. by 10in. table.
BROWN & SHARPE 000 production miller.
EDGWICK No. 2, 46in. by 11in. table.
EDGWICK 18in. traverse, 40in. by 12in. table.

VERTICAL MILLERS.

ARCHDALE 12in. traverse, 25in. by 10in. table. Power feed, 235-1,500 r.p.m.
REED PRENTICE No. 5, 66in. by 16in. table.
HERBERT 15in. sliding head, 48in. by 11in.
ARCHDALE 18in. traverse, 40in. by 10in. table.
KNIGHT (U.S.A.), 33in. by 9in. table, with sliding head and measuring rods for jig boring.
WADKIN high speed, 40in. by 17in. table.

HORIZONTAL BORER.

KEARNS model 8, with facing head.

DRILLING MACHINES.

ARCHDALE 38in. Radial Drill, R. & F. Table. Power Feeds.
ARCHDALE 24 spindle cluster, hyd. feed.

SLOTING MACHINES.

BUTLER 16in. stroke, 39in. circular table.
MUIR 30in. stroke, 48in. circular table.
MUIR 12in. stroke, 32in. circular table.

PLANING MACHINE.

LIBERTY 10ft. openside, 2 tool boxes.

BROACHING MACHINE.

FORT 16 ton, vertical surface broach.

SURFACE GRINDER.

JONES & SHIPMAN 540, 18in. by 6in.

CYLINDRICAL GRINDER.

B.S.A.-LANDIS 18in. by 6in. hydraulic.

CENTRELESS GRINDERS.

SCHIVENER No. 2 centreless grinder.

B.S.A. No. 12 centreless grinder.

INTERNAL GRINDER.

CHURCHILL HBY hydraulic internal.

TOOL AND CUTTER GRINDERS.

SCHUTTE WU5, 24in. by 8in. capacity.

GRAND RAPIDS, 27in. by 6in. capacity.

SAWING MACHINE.

WICKSTEED Power Hack Saw, 10in. by 10in. capacity.

MISCELLANEOUS.

ABWOOD carbide tool grinder.

PRATT & WHITNEY spur gear grinder.

One Reed-Prentice 14in. Lathe.

Serial No. 16898. Heavy duty. American Metric lathe. Geared head machine with 8 spindle speeds 41-1,000 r.p.m. Gearbox for screwcutting and traversing. 14in. dia. through spindle. Spindle fitted with screwed collar for easy accurate fitting of chucks etc. Single Vee bedways. Distance between centres 30in. Apron fitted with screwcutting indicator. Electric built into machine 400/3/50. Equipment: 4-way toolpost, 3-jaw concentric chuck, 4-jaw independent chuck, faceplate, catchplate, 3-point steady.—BOX V245. MACHINERY, Clifton House, Euston Road, N.W.1.

Rapidor (New) 1A Heavy Duty

4in. by 8in. 3-speed hacksawing machine, motorised 400/3/50.—SOUTHERY ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Brown & Sharpe No. 13 Tool

and Cutter Grinder. Capacity 8in. by 24in. line workhead. Equipment includes universal attachment. Internal grinding spindle. Spiral grinding attachment. Surface grinding attachment, etc. Independent coolant tank and fittings. Motorised 400-440/3/50. Condition as new.—BOX V218. MACHINERY, Clifton House, Euston Road, N.W.1.

Craven 5ft. Double Upright Ver-

tical Boring and Turning Mill with two saddles on the cross slide. Motorised 400-440 volts, 3 phase, 50 cycles A.C. supply. NEW. Delivery: Immediately.—W. E. NORTON (MACHINE TOOLS), LTD., Grosvenor Gardens House, Grosvenor Gardens, London, S.W.1. Phone: Tate Gallery 0633/4. Cables: Nortrex, London.

PBR**HORIZONTAL BORING AND FACING MACHINE**


Spindle dia. ... 34in.
Range of speeds ... 35-1,200 r.p.m.
Traverse ... 24in.
Size of Table ... 39in. by 34in.
Rotates through ... 360 deg.
Max. distance spindle to table ... 32in.
Longitudinal traverse ... 36in.
Cross traverse ... 32in.
Max. distance facing head to outer support ... 72in.
Approximate weight ... 6 tons

PRICE £4,950

Approx. £600 returnable if Duty-Free Licence is issued.

PRICE INCLUDES

Facing head, 17in. dia.
Horizontal Milling Attachment with two Arbors 1 1/2in. and 1 1/4in. dia.
Universal Vertical Milling Attachment, No. 30 N.S. Taper.
Open Scale Verniers.
Dial Indicators for Vertical and Horizontal Traverses.
Coolant Pump and Fittings.



No Import Licence. No Extras. Quick Delivery.
Demonstration Machine can be seen at our works.

Extended Credit Facilities arranged and financed entirely by ourselves enable us to offer terms very much more attractive than those available elsewhere.

Sole Agents for Great Britain and the Commonwealth:

HERBERT WIDDOWSON & SONS, LTD.
CANAL STREET WORKS, NOTTINGHAM

PHONE: 42061

Richmond No. 3 Horizontal

Milling Machine, 28in. by 9in., with vertical attachment.

ALBA 48 18in. Shaper, with swivel vice.
TRIDENT Vertical Miller, 30in. by 6in., swivel head, auto feeds.

EDWIN MILLEN,
70, Clerkenwell Road,
London, E.C.1.

Phone: Clerkenwell 6064.

For Sale, Robertson 7-stage

Section Forming Machine with additional curving unit. Specially suitable for profiling and banding stainless steel sections. Drive is by 20-h.p. motor through 3-speed gearbox. Diameter of roller shafts 2in. Length of shafts available for forming rollers 8in. Rolling speeds with 6in. diameter rollers, 40, 80 and 120ft. per minute. Weight about 11 1/2 tons.—Full details and illustrations from F. J. EDWARDS LIMITED, 359-361, Euston Road, London, N.W.1, or 41, Water Street, Birmingham 3.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

NEW MACHINES FOR OLD!!!

Reconditioned

Ward 2a and Ward 3a
Capstan Lathes available in exchange
for your worn machines

Immediate Delivery

HELIOT MACHINE TOOL CO

Blackheath Hill, London, S.E.10

Phone: TIDEWAY 2819-4888



**THE NEWALL GROUP OF
COMPANIES MANUFACTURE:**

GRINDING MACHINES

- "KL" CYLINDRICAL, 4in. x 18in.
- "L" CYLINDRICAL, 12in. x 24in.—60in.
- "LA" HEAVY DUTY CYLINDRICAL, 12in. x 24in.—84in.
- "HLA" HEAVY DUTY CYLINDRICAL, 16in. x 24in.—84in.
- "KU" UNIVERSAL, 12in. x 24in. to 24in.—96in.
- "HAC" CRANKPIN, 20in. x 48in. to 72in.
- "U/HAC" UNIVERSAL CRANKSHAFT, 28in. x 84in.
- "NL" THREAD, 8in. x 16in. and 8in. x 32in.
- "AK" AUTOMATIC INTERNAL, 4in. to 6in. bores.
- "KSE" INTERNAL, 4in. to 14in. bores.
- "KN" INTERNAL, 4in. to 54in. bores.
- "KFG" ANGLE HEAD, 12in. x 24in. and 12in. x 36in.

JIG BORING MACHINES

- "1220" Table Size, 12in. x 20in.
- "2436" Table Size, 24in. x 36in.
- "OPTISET" Table Size, 24in. x 36in.
- "2442" Table Size, 24in. x 42in.
- "SPACEMATIC" Table Size, 26in. x 57in.

LAPPING MACHINES

- "10 U" For work to 14in. thick x 3in. square.
- "2 F" For work to 3in. thick x 8in. square.
- RIGIDLAP. For work to 14in. thick x 7in. square.

OPTICAL INSPECTION EQUIPMENT

- 10in. OPTICAL ROTARY INDEXING TABLES.
- 16in. OPTICAL ROTARY INDEXING TABLES.
- 30in. OPTICAL ROTARY INDEXING TABLES.
- 12in. and 16in. ROTARY AND INCLINABLE TABLES.
- UNIVERSAL TOOLMAKERS' MICROSCOPES.
- VERTICAL COMPARATORS.
- HORIZONTAL COMPARATORS.
- UNIVERSAL WORKSHOP PROJECTORS.
- PROJECTION PANTOMIMES.
- MEASURING MACHINES, 0—24in. to 0—144in.
- OPTICAL DIVIDING HEADS.

**SALES ORGANISATION,
NEWALL GROUP SALES LTD.,**

PETERBOROUGH.

Telephone: Peterborough 3227.
Telegrams: "Precision" Peterborough.

Newall Plain Cylindrical Grinding Machine. 10in. by 24in., motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Rapidor Manchester Major Hack-saw Machine. Motorised 400/3/50. In Stock for your inspection.—JAMES W. CARR & CO., LTD., 7/15, Rosebery Avenue, London, E.C.1. Tel.: Terminus 8866 (P.B.X.).

Wild-Barfield Furnace, Type
No. CTO1612. Celltype forced air circulating tempering furnace. Temperature range 0-700 deg. C. Contactor panel by Brochist, Cambridge controller. Current supply 415/3/50, 10 kW. Size 18in. by 18in. inside dims.—BOX T686, MACHINERY, Clifton House, Euston Road, N.W.1.

Reconditioned Wild-Barfield
Furnace. 0-1,050 deg. temperature range. Heavy hairpin 2 zone control (roof and hearth separate control). Heated door. Internal size 24in. by 48in. by 15in. high. 36 kW. 415/3/50. With contactor panel, 2 oil cooled transformers. C.A. couples.—BOX T706, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert 2D Capstan, 14in.
capacity bar machine fitted with collet, bar tube and stands, 16 spindle speeds to 2,550 r.p.m., Electric and supply. Immediate delivery.—Apply BOX V41, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert No. 3 Capstan. Hole
through spindle 14in. dia.; 6 spindle speeds 60 to 1,500 r.p.m. 6 feeds 40 to 480. Power feeds to saddle, cross-slide and turret. Fully motorised 400/3/50, with coolant supply. Reconditioned, sideways restored, ready in 14 days.—BOX V48, MACHINERY, Clifton House, Euston Road, N.W.1.

B.S.A. No. 7 Centreless Grinder.
Max. grinding dia. 3in., min. grinding dia. 3/64in. Grinding wheel speed 1,275 r.p.m. Range of speeds to control wheel 23.35-50.76. Speed of control wheel for truing 620 r.p.m. Grinding wheel dia. max. 18in. Grinding wheel width max. 4in. Wheel dresser slide. Vee rope drive (S). Coolant tank pump filter complete 10 h.p. motor at 1,458 r.p.m. Motorised 400-440/3/50. Offered subject to being unsold.—BOX V326, MACHINERY, Clifton House, Euston Road, N.W.1.

One No. 2D HERBERT Capstan, complete with bar feed and collet attachment. Serial number 29/28. £275.

Two No. 4 HERBERT Capstans, complete with bar feeds and collet attachments. Serial numbers 74/530, 75/237. £275 each.

All the above can be seen working.

GIB PRECISION LIMITED,
BARTON LANE, GIRENCESTER.
Telephone No.: Cirencester 726.

600 MACHINE TOOLS

ALL MOTORISED 400/3/50.

WARD No. 10 Combination Turret Lathe. All-gear head. Swing over bed 23in. by 61in. Spindle to turret 44in. Hollow spindle. 16 spindle speeds 16-470 r.p.m. **ARCHDALE 24in. Vertical Milling Machine.** Table size 40in. by 134in. Spindle speeds 45-812 r.p.m. Power feeds longitudinal and cross motion.

BUTLER 8in. Stroke Precision Slotting Machine. Table 20in. dia. Adjustable stroke. Speeds 35-115 cycles per min.

WICKMAN 5-spindle 6in. Chucking Automatic. Max. dia. swing 64in. Turning length 4in. to 5in. Speeds 106-1,152 r.p.m. Air-operated collet adaptors.

KITCHEN & WADE 6in. Heavy Duty Low Base Radial Drill and Tapping Machine. Spindle bored No. 5 M.T. Speeds 12-450 r.p.m. Base 42in. by 72in.

WILLSON 12in. All Geared Head Gap Bed S.S. & S.C. Centre Lathe. Admits 4ft. 9in. between centres. Swings in gap 46in. Hollow spindle 3in. dia. Spindle speeds 9.5-240 r.p.m.

VAN NORMAN No. 3V Ram Type Vertical Milling Machine. Table size 64in. by 14in. Spindle speeds 25-1,250 r.p.m. Power feeds and rapid traverse to all movements.

SNOW Model VA18 Vertical Spindle Surface Grinder. 15in. by 42in. table. Max. distance chuck to wheel 13in. Hydraulic table traverse 18in. Segmental wheel and 15in. by 42in. D.C. electric chuck.

HYDETSO Model 4H Hydraulic Shaping Machine. Max. stroke 23in. Variable cutting speeds. Table 24in. by 14in. by 14in.

ARCHDALE 4-spindle Drill, 3 spindles No. 2 M.T., 1 spindle No. 3 M.T. Table 49in. by 154in.

ORCUTT Spindle Grinder. 16in. by 3in. capacity. Hydraulic reciprocation to table. Table fitted Diamond Truing Device for wheel form and indexing head.

MASSEY 3 cwt. Pneumatic Power Hammer. Clear space type. Forging capacity 34in. by 6in. M.S. bar. Ram pallet face 6in. by 5in. Single and automatic blows.

GRAVEN 54in. Heavy Duty Single Ended Turning and Facing Lathe. All-gear head. Max. turning dia. 68in. Spindle speeds 1.37-10.15 r.p.m.

CINCINNATI Model 2MH Plain Horizontal Milling Machine. Table size 44in. by 7in. Spindle speeds 23-1,200 r.p.m. Power feeds all directions.

DEAN, SMITH & GRACE Type D 12in. All Geared Head Gap Bed S.S. & S.C. Lathe. Admits 5ft. 6in. between centres. Swing in gap 42in. Hollow spindle 3in. dia. Spindle speeds 9.9-180 r.p.m.

GEORGE COHEN SONS & CO., LTD.

SUNBEAM ROAD, LONDON, N.W.10.

Tel.: Elgar 7222, and

STANNINGLEY, NR. LEEDS.

Tel.: Pudsey 2241.

SYKES MODEL V.10 GEAR GENERATING MACHINES

Capacity 0in. to 14in. for external work; capacity 20in. for internal work. Maximum pitch 6 D.P.

F. J. EDWARDS LTD.,

359-361, Euston Road, London, N.W.1
EUSTON 4681

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

C.V.A. No. 79 Vertical Miller,
25in. by 94in. table, 400/3/50. £275.—
A. McNAMARA & CO., New Line, Bacup,
Lancs. 'Phone: Bacup 946.

One Loewe SW2 Tool and Cutter

Grinder. Table mounted on roller chain bearings. Table 31in. long by 44in. wide, with swivelling adjustment. Wheelhead fully rotating with wheels mounted at both ends of spindle. Fully motorised 400-415/3/50, 0.012kW, 2,840 r.p.m. Overall size 4ft. 10in. wide by 4ft. high by 3ft. 6in. deep. Equipment: One fully adjustable vice.—BOX V288, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert 9S Combination Turret

Lathe, 1944 model, in excellent condition. Fully motorised 400/3/50. Fitted with taper turning attachment, fourway toolpost, pilot knee toolholders to take several tools. Coolant supply. Seen in London area.—BOX V147, MACHINERY, Clifton House, Euston Road, N.W.1.

Ward, Haggas & Smith, Boring
and Facing Lathe, short bed, swing 50in. dia. over bed, war-time model, 400/3/50.—
A. McNAMARA & CO., New Line, Bacup,
Lancs. 'Phone: Bacup 946.

Heading Press For Sale. "Water-

bury Farrell" type No. 1 S.D.D.S. Motorised, Horizontal, Toggle Action, Double Stroke, Solid Die Type. Capacity up to approximately 1in. diameter. Maximum length of wire cut off 14in. Length of feed adjustable from 0 to 1in. Electrical equipment for 400-440 volts, 3 phase, 50 cycles.—Full details, photograph, etc., from F. J. EDWARDS, LIMITED, 359, Euston Road, London, N.W.1, or 41, Water Street, Birmingham, 3.

Churchill 72 CRM Crankshaft

Grinder. Landis 16 by 48 Crankshaft Grinder. Herbert No. 5 Chucking Auto. Lathe. Sunstrand 6in. Chucking Auto. Lathe. Full details from user.—HUNT & CO. (BOURNE-MOUTH), LTD., Bournemouth.

For Sale—Four Premier Stirrers,

complete. Model 2100, 2 h.p. motor, etc. Nearly new.—Full details from BOX V238, MACHINERY, Clifton House, Euston Road, N.W.1.

Fischer G.F. Copying Lathe,

model KDM 18-250, 100in. between centres, 14in. max. dia. Price reasonable. HENRY SIMON (E.W.), LTD., Cheshire Heath, Stockport. (Mr. J. Barnes.)

Herbert Auto. Junior Turret

Lathe. Chucking, semi-automatic, fully motorised. Reasonable offer considered.—BOX V54, MACHINERY, Clifton House, Euston Road, N.W.1.

Profiling Lathe. Churchill Red-

man semi-automatic hydraulic copying Lathe. Capacity 12in. dia. by 40in. between centres. 12 spindle speeds 260-1,000 r.p.m. Feeds variable from 1in. to 18in. per min. Headstock motor 15 h.p., 400/3/50/1,440. Hydraulic pump motor 3 h.p. Push-button controls. Excellent condition, year of manufacture 1951. Seen London area.—BOX V60, MACHINERY, Clifton House, Euston Road, N.W.1.

Victoria (New) U2 and V2 Milling

Machines, table 45in. by 11in., motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

One Billeter Rotary Surface

Grinder. Capacity 30in. dia. Rotary magnetic table 30in. dia. Power drive to traverse, with inching control. Segment grinding wheels. Integral wheelhead motor 11.4 kW, 415/3/50, 950 r.p.m. Table travel motor 415/3/50, 940 r.p.m., 2.2 kW or 3 h.p. Westinghouse rectifier mounted on rear of machine. 8type R.F. Type 448/3 A.C. 200/240v. 50/100 cycles. D.C. 200/240v. 2 amps. Serial No. 24996. Spec. No. R.1588. Switch contactor control panel. Coolant tank 22in. wide by 40in. and electric pump.—BOX V330, MACHINERY, Clifton House, Euston Road, N.W.1.

Edgwick, Vertical Surface

Broacher. Slide 60in. by 12in. Table 14in. by 14in. Motorised.—WILCOX & CO., Barr Street, Birmingham, 19. NORTHERN 1234/5

La Point Broaching Machines,

series 2950 and 2890. No. 0. 18in. stroke, 1in. dia. Broach capacity. Front aperture 4in. by 3in. Fitted with adjustable block reducing to 1 1/4in. dia. Rack and pinion drive, quick reverse to drive from countershaft.—BOX V143, MACHINERY, Clifton House, Euston Road, N.W.1.

There are
HUNDREDS
of **MACHINES**
to choose
from
at

**THE
F.J.E.
MACHINE
CENTRE**

**ISLINGTON PARK STREET, NEAR
HIGHBURY CORNER, LONDON, N.1**
(on the main A1 Road from the North)

For Sale. Solvent Extraction

Plant, 24 ton batch, consisting of storage tank, evaporator extraction vessel, lift out basket, 5-ton electric travelling block separator, condenser, steelwork and piping complete. Price and particulars on request.

BOX No. B.854.

LEE & NIGHTINGALE, Liverpool.

Excell No. 3 Diefiling and Sawing

Machine. Length of stroke 4 1/2in., throat distance 9 1/2in. Max. thickness of work admitted 3 1/2in. Strokes per min. 65, 100, 150, 220. Dia. of table 16in. Angular adjustment of table in 4 directions 15 deg. Length of files 8in., 1 h.p. motor at 900 r.p.m.—BOX V229, MACHINERY, Clifton House, Euston Road, N.W.1.

WILLIAM PARTINGTON LIMITED

Trafford Park Road, Trafford Park,
Manchester, 17.

Tel.: Trafford 0332.

CINCINNATI No. 3 Dial Type Plain Miller.

Reconditioned.

WARD No. 7 Combination Turret Lathe.

Covered bed.

KITCHEN & WADE Motor-driven 4ft. 6in.

Radial Drill. Low base. Loose box table.

CHURCHILL 60in. Model VXA Motor-driven

Vertical Spindle Surface Grinder, Hydraulic.

Magnetic chuck.

CHURCHILL Model "O" Universal Tool and

Cutter Grinder. Motor driven.

ARCHDALE 28in. Plain Miller with vertical

attachment.

TOWN 3ft. 6in. Radial Drill, 2-motor type.

RICHARDS 48in. Vertical Boring Mill. Cone

Drive.

GIBBOLT No. 5 Ram type Turret Lathe. Well

equipped.

HARRISON 7in. by 38in. S.S. S.C. Lathe. Cap

bed M.D.

FACEPLATE LATHE, 52in. swing. Motor

driven through cone pulleys.

KITCHEN & WADE 6ft. 6in. Radial Drill.

Box table. M.D.

EDGWICK No. 2 Vertical Miller. M.D.

CHAVEN-RIGID Semi Universal Miller.

KENDALL & GENT Broach, 20-ton pull. 50in.

stroke. M.D.

HERBERT Filing and Sawing

Machine, 15in. square adjustable table.
Alexander 16in. Cutting-off Machine, 12 1/4 h.p.,
440/3/50.

Taylor No. 2 Cutting-Off Machine, up to
6 1/2in. diameter.

Herbert Hack-saw, 13in. blade, belt driven.

Wicksted Hydrofused Hack-saw, 16in. blade,
6in. by 6in.

Rex Hydraulic Hack-saw, 18in. blade, 8in.
by 8in.

Colchester 7in. Centre Lathe, 7ft. gap bed.
A.G.H.

Herbert Horizontal Milling Machine, 3ND
table 61in. by 15in., 4 spindle speeds.

Rotary Cold Metal Saw, 24in. diameter blade.

Biss 20-ton Inclined Open Fronted Press.

V. & O. 50-ton Inclined Geared Open
Fronted Press.

Crow Harvey Punch, Shears and Angle
Cropper, 18in. blade, 27in. throat, heavy duty.

Fels Punch, Shears and Angle Cropper, 12in.
blade shear up to 1in., takes 6in. by 6in. by
1in. angles.

Craig & Donald Billet Shears, 8in. blade,
6in. by 1in. capacity.

Robertson Shears, 28in. blade, 9in. maximum
opening. (2).

Goliath Hand Operated Shears, 7in. blade,
1in. opening.

Robertson 7-roller Plate Flatteners, 8ft. 6in.
wide, approximately 1in. capacity.

Berry 3-roller Plate Bender, 7ft. wide,
approximately 1in. capacity.

Hearn Screwing Machine, 4in. capacity,
adjustable vice.

Sweeney Fly Presses, all sizes, 20 available.

Sedgwick Plate Folder, 8ft. wide.

Massey 3-wt. Bottle Forging Hammer.

Massey New 1-cwt. and 2-cwt. Hammers
(three).

Alldays New 1-cwt. and 2-cwt. Hammers
(five).

Oliver Planishing Hammer, 20in. gap.

FRED WATKINS (BOILERS), LTD.,
Coleford, Glos. 'Phone: Coleford 2271 (3 lines).

One Specima 2121 Universal

Cylindrical Grinding Machine, 6in. dia.
by 8in. centres. Powered wheelhead, swivels
90 deg. Fitted with collets. Powered wheel-
head swivels 30-0-30 deg. Hand feeds with
coarse and fine traverse. Wheelhead is also
adjustable for position on sideways. Wheel
size 6in. dia. by 4in. wide, runs at 2,800 r.p.m.
Table swivels 25-0-45 deg. and is hand fed with
coarse and fine feeds. Built-in electrics.
'Clant tank with electric pump. £450 ex-works.
This machine has been rebuilt and is in use on
our Toolroom and can be seen working.
BOX V322, MACHINERY, Clifton House, Euston
Road, N.W.1.

TRANSFORMER WELDERS

20/300 amps., 250 amps., and 180 amps.

Oil-cooled pattern Arc Welders for operation
on 400-440 volts single phase 50 cycles;
alternatively 230 volts single phase
50 cycles; dual welding voltages 60/80;
output current variable between 20/300
amps., fitted with coarse and fine
regulators in robust steel tank.

£25 Os. Od.

Similar, 250 amp. units, £71 Os. Od.

Similar 160 amp. units, but not fitted with
wheels, £45 Os. Od.

GEORGE COHEN SONS & CO., LTD.

WOOD LANE, LONDON, W.12.

Tel.: Shepherd's Bush 2070, and

STANNINGLEY, NR. LEEDS.

Tel.: Pudsey 2241.

Taylor Capstan Lathe, Serial

7330-2-45. Collet type with 3-cone pulley
drive. 4in. dia. capacity by 12in. long. Back
and front fixed toolposts and auto pump. Back
splash guard.—BOX V211, MACHINERY, Clifton
House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

Drummond Electraulic 12 Ton
Press. 18in. Gap under ram. 9in. throat to ram centre. 4 1/2in. U Gap in bed. 17in. Ram stroke. Front safety trip guard and side guards. Total bed area 15in. by 10in. Motorised 2 h.p. 3 ph.—BOX V239, MACHINERY, Clifton House, Euston Road, N.W.1.

Myford MG12 Internal Grinder, standard equipment, motorised 400/3/50. In Stock for your inspection.—JAMES W. CARR & CO., LTD., 7/15, Rosebery Avenue, London, E.C.1. Tel.: Terminus 8866 (P.B.X.)

2 Ryder 5-Slide Forging Hammers for sale. Capacity: round and square bars up to 1 1/2in. tubes up to 3in. diameter. Weight about 36 cwt. each. Photos available.—F. J. EDWARDS, LIMITED, 41, Water Street, Birmingham, 3. CENTRAL 7606.

HORDERN MASON & EDWARDS L20 Open-fronted Inclinable Ungear Power Press, 20 tons capacity, double roll feed, motorised 400/3/50.

PARKES (MACHINE TOOLS) LTD.
WITTON ROAD, BIRMINGHAM, 6.
Tel.: EAST 1742.



60 in. LANG BORING AND FACING LATHE

10ft. between centres.
Sliding bed.
12 spindle speeds 2.7-330 r.p.m.
Pedestal type tool holder and compound slide rest on separate bed mounted in front of machine.
6 1/2in. hollow spindle.
Power feeds and rapids to all movements.
4 face plate chucks.
Approximately 4 years old.
Weight 17 tons.

DIMCO (Gt. Britain) LTD.
415-417 Oxford Street,
London, W.1
Tel. Mayfair 1585

Willson Mk. V S.S. & S.C. Gap
Bed Centre Lathe, 15 1/2in. swing by 3ft. between centres, with Metro-Vick Copying Attachment, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Landis Cylindrical Grinding Machine, 6in. by 30in. capacity. Wheel size 20in. dia. by 2 1/2in. wide. Table swivelling with hydraulic feeds giving infinitely variable rate of traverse. Fully motorised, reasonable offer to BOX V97, MACHINERY, Clifton House, Euston Road, N.W.1.

Norton Plain Grinder, 13800 series. Type C. Size 10in. by 18in. American manufacture. Swivel table with hydraulic feeds to traverse. Fitted with Monitor control, all in nice condition.—BOX V107, MACHINERY, Clifton House, Euston Road, N.W.1.

One Keighley Cylindrical
Grinder. Serial No. 45/K/573. Fully hydraulic. Wheelhead max. 2,000 r.p.m., with plunge feed. Two-speed wheelhead, 14in. wheel. Max. distance between centres 16in. Swing over bed 6 1/2in. Pressure pump lubrication to main bearings. Swivelling table. Variable speed control. Picker feed mechanism. All-electric workhead. Workhead, live and dead centres. D.C. rectifier giving 6 workhead speeds. Quick release tailstock. Diamond dresser attachment. Motorised coolant system. built in, 400-440/3/50. Equipment: 14in. grinding wheel.—BOX V280, MACHINERY, Clifton House, Euston Road, N.W.1.

B. & S. "OG", "OOG" Automatics.
B.S.A. 1/2in.-1in. Automatics.
SKODA 40m/m. Automatic.
WICKMAN 10 m/m. Automatic.
HERBERT No. 1-25-28 Capstans.
MODERN No. 1 Capstans.
WARD "OE" Capstan.
WARNER & SWASEY No. 2 Capstan.
CORONA 12AX: 1/23 Spindle Drills.
HERBERT 25p. Drill, 1/2in. cap.
SNOW T.14 Surface Grinder.
JUNG 18in. by 6in. Surface Grinder.
NORTON 18in. by 6in. Surface Grinder.
B. & S. No. 2 Uni. Grinder.
CHURCHILL 6in. by 18in. Semi-Uni. Grinder.
CHURCHILL Mod. "AY" 6in. by 34in. Grinder.
CHURCHILL Mod. "HBY" 10in. by 24in. Grinder.
B.S.A. No. 7 Centreless Grinder.
WOTON Mod. RJ33 Internal Grinder.
NEWALL Thread Grinder.
NEWALL Hydrolapping M/c.
SEBASTIAN 6in. S.S. & S.C. Lathe.
D.S. & G. 7in. S.S. & S.C. Str. Bed. Lathe.
SOUTHBEND 7in. S.S. & S.C. Lathe.
CHURCHILL-REDMAN 8in. S.S. & S.C. Lathe.
LEBLOND 8in. and 10in. S.S. & S.C. Lathes.
SWIFT 8 1/2in. S.S. & S.C. Lathe.
IMPERATOR 8 1/2in. S.S. & S.C. Lathe.
LEBLOND 8 1/2in. (S.S. only) Centre Lathe.
COLCHESTER 8 1/2in. S.S. & S.C. G.b. Lathe.
EMRICAN TOOLWORKS 8 1/2in. S.S. & S.C. G.b. Lathe.
SPRINGFIELD 10in. Boring and Facing Lathe.
HILLE Thread Mill.
MANN 4102 Production Mill.
EDGWICK No. 1 and No. 2 Hor. Mills.
FALLAS M.O. Hor. Mills.
PEDERSON VILH Hor. Mill.
VICTORIA Mod. M.O. Plain Mills.
C.V.A. No. 79 Vertical Mill.
VAN NORMAN 18in. Vert. Mill.
ARCHDALE 30in. Vert. Mill.
MILWAUKEE No. 2 Vert. Mill.
WANDERER Universal Mill
THIEL Universal Mill.
B. & S. 2A Universal Mill.
CINNANT 2M. Universal Mill.
MOREY 25p. Profiling Machine.
E.H.J. No. 22 and No. 24 Tapping M/c.

All machines motorised 400/3/50 unless otherwise stated.

E.H. JONES
MACHINE TOOLS LTD
15 COLINDALE AVENUE LONDON N.W.9

Telephone: COLindale 5451-2-3 and
Midland 5593 Birmingham.

Snow P24 Surface Grinding Machine, capacity 8in. by 24in. Hydraulic feeds to table, electric coolant supply. This machine has recently been reconditioned. Seen London.—BOX V129, MACHINERY, Clifton House, Euston Road, N.W.1.

Grand Rapids Surface Grinding Machine. Capacity 8in. by 24in. Hydraulic feeds to table, fully motorised 400/3/50. Coolant supply fitted. Rebuilt as new.—BOX V135, MACHINERY, Clifton House, Euston Road, N.W.1.

24 by 8 Surface Grinder, Abrasive. 2 speeds to table traverse, fitted with coolant supply and dust extractor. Rebuilt to original maker's limits.—BOX V140, MACHINERY, Clifton House, Euston Road, N.W.1.

C.E.M

New **BENTLEY** Plate Bending Rolls, 6ft. x 1/2in. and 8ft. x 1/2in. for immediate delivery. 8ft. x 1/2in. for delivery February. Heavier capacities and lengths for early delivery. All Machines fitted with opening end frame and self-supporting top roll. Quotations and fully illustrated literature gladly supplied.

CHARLES E. MATTHEWS
(MACHINE TOOLS) LTD.
34, GLADSTONE ROAD,
CROYDON, SURREY.
THOrnton Heath 1783.

Herbert No. 11 Bar Turret
Lathe, 2 1/2in. H.S., bar feed, 400/3/50.—A. MCNAMARA & CO., New Line Bcup, Lancs. Phone: Bcup 946.

Aerograph Air Compressor Unit
Type D13 for sale. Single cylinder, vertical water cooled. Capacity 40 c.f.m. at 100 p.s.i. pressure. Motorised for 400/440 volts, 3 phase, 50 cycles, 10 h.p. Two air receivers, 18in. diameter by 60in. high for 80 lbs. p.s.i. Water tank.—Photo and full details from F. J. EDWARDS, LTD., 359, Euston Road, London N.W.1. Euston 4081, or 11, Water Street, Birmingham, 3. Central 7606.

Bryant No. 4 Internal Chucking
Grinder. Capacity 1 1/2in.-2in. bore. Max. swing 6 1/2in. dia. Motorised.—WILCOX & CO., Barr Street, Birmingham, 19. NORthern 1234/5.

Parkinson's N.A. Universal Miller. Speeds 29-775. Table 46in. by 10 1/2in. Power feed all directions. Motorised.—WILCOX & CO., Barr Street, Birmingham, 19. NORthern 1234/5.

Clifton & Baird Hydraulic Power
Saw. 6in. capacity. Speeds of cutter 40-60-90ft. per min. Graduated cutter feed 1/2in. to 20in. per min., with automatic stop and quick return. Work V-jaws and clamp 10in. long. Work stop bar graduated 12in. in 1in. Hand operated clamp. Motor mounted on top of machine on platform, 4 h.p., 400-440/3/50, 1,450 r.p.m. One pressure gauge. One work trolley. One saw sharpening machine.—BOX V267, MACHINERY, Clifton House, Euston Road, N.W.1.

600

GEARED AND VARIABLE SPEED MOTORS FOR 415/3/50.

H.P.	Make	Type	Speed
270/67.5	B.T.H.	Schraeg	370/95
100	Asca	Slipring	225
100	Asca	Slipring	200
260	B.T.H.	Ward/L.	300/1,500
100	L.D.C.	Ward/L.	300/1,500
60	C. Park	Ward/L.	300/1,500
50	Asca	Slipring	125
30/3	Harland	Ward/L.	1,750/175
27	Mather & P.	Ward/L.	500/2,800
24	E.E.C.	Ward/L.	300/1,650


Other special forms of equipment including Squirrel Cage A.C. motors with variable frequency supply equipment and frequency changers for all applications, etc.

GEORGE COHEN SONS & CO. LTD.

WOOD LANE, LONDON, W.12.
Tel.: Shepherds Bush 2070, and
STANNINGLEY, MR. LEEDS.
Tel.: Pudsey 2241.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



USED LATE TYPE MACHINES

LATHES

DEAN, SMITH & GRACE, A.G.H., 10 1/2 in. centre by 10ft. between, 35in. gap.
COVMAC Lathe, 8 1/2 in. by 60in. between, A.G.H., gap bed, spindle speeds 18-450 r.p.m., mot. 415/3/50.
CHURCHILL CUB Lathe, 6in. by 24in., A.G.H., mot. 415/3/50.

CAPSTANS AND AUTOS

WARD No. 7, A.G.H. Bar feed, ball chuck, etc. Motorised.
WARD 2A. Oversize spindle, complete with ball chuck, bar feed, and quantity of collets for 2A size. Motorised 415/3/50.
WARD 3A. Oversize spindle, complete with ball chuck, bar feed. Motorised 415/3/50.
WARD OE Capstans, 1in. collet cap. 480/2,850 r.p.m. Bar feed, mot. coolant pump 400-440/3/50 A.C.
WARD 1A Capstans, 1in. collet cap. H.S. range up to 4,130 r.p.m. Ball chuck, bar feed, mot. coolant pump. 400-440/3/50 A.C.
HERBERT 2D Capstans, 16 speeds, 50/2,500 r.p.m. Draw-in collet, bar feed, power feed turret, "duo-rate" cross slide, "Flanard" bed, mot. coolant pump 415/3/50.
HERBERT 18 Capstans, 1in. collet cap. Draw-in collet and bar feed, 16 speeds 18/4,020 r.p.m. Hand feed turret and cross slide. Mot. coolant pump, 415/3/50.
HERBERT No. 0 Capstans, 1in. cap. Dead length air chucks, 12 speeds 93/6,000 r.p.m., mot. coolant pump. 415/3/50.
BOLEY & LEDEN Precision Capstan. Model S.R.25. Collet cap. 1in., mot. 415/3/50.
INDEX O.R.12 Auto., 1in. cap. Flange mot. 415/3/50.

MILLING MACHINES

CLEVELAND No. 1 Horizontal Router. Spindle No. 5 M.T. compound table, with motor.
ARCHDALE 20in. Horizontal. Table 40in. by 10in. Dial type speed change 30 to 615 r.p.m. Dial feed. Mot. 415/3/50.
ARCHDALE 18in. High-Speed Vertical WB30. Table 34in. by 10in., 6 speeds 500/2,000 r.p.m. Mot. 415/3/50.

GRINDING MACHINES

CHURCHILL 14in. Vert. Surface (plough), cap. 18in. by 36in., segmental wheel 18in. dia. Humphrey mag. chuck, 12in. by 36in., mot. 415/3/50.
LANDIS Hydraulic Cylindrical Grinder, 12in. by 48in., mot. reconditioned.
NEWAL Hydraulic Cylindrical Grinder, 12in. by 24in., mot.
SNOW P.24 Surface Grinder. Cap. 24in. by 8in. Hydraulic variable feed to table, wheel dia. 10in., mot. 400/3/50 A.C.
E.S. Internal Grinder, 1/2 in. to 1 1/2 in. dia. Int. cap. Power feed to table, auto. sizing feeds, mot. 415/3/50. Late type machine, ex. con.
OLIVETTI Automatic Hydraulic Cylindrical Grinder. Type R4/1200, 14in. swing by 48in. between centres. Plunge cut. Mot. 415/3/50.

SHAPING MACHINES

G.S.P. Toolroom Shaping Machine. Stroke 23 1/2 in., with universal table swivel and rotate, automatic tool lift, mot. 415/3/50.

PRESSES AND SHEET METAL

KEETONA Guillotine, cap. 6ft. by 1in., under-crank feed, mot. 415/3/50.
BESCO Universal Swing Beam Folder, Cap. 6ft. x 1in., Geared Hand Operation.
TAYLOR & CHALLEN B2 Ricd Press, 10 tons adjustable stroke 1in. to 3 1/2 in. Mot. 415/3/50.
TAYLOR & CHALLEN B11 Press, 6 tons. Fixed stroke 2in. "Udal" guard. Mot. 415/3/50.

WILLIAM URQUHART

Head Office:—
1023, Garratt Lane, London, S.W.17

Showrooms:—
Ace Works, Plough Lane, Tooting, S.W.17

Phone: WIMBLEDON 6341

Richmond SR2 (New) 4ft.

Radial Drilling Machine, 1 1/2 in. cap., tilting table and suds, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

OG Brown & Sharpe Auto., 4570

series. Approx. capacity 1in. dia., bar machine. Motorised 400/3/50. Good condition.—BOX V578, MACHINERY, Clifton House, Euston Road, N.W.1.

One Brimsdown Two-spindle

Drilling Machine. Serial No. 27153. Spindle speeds 500-4,500 r.p.m. Two drill heads rotate around column. Height, chuck to table, 4in. Throat 6in. Column to chuck centre 6in. Base size 14 1/2 in. by 22in. Height of table 39in. Overall size 21in. by 39in. Motorised 400-440/3/50.—BOX V340, MACHINERY, Clifton House, Euston Road, N.W.1.

One Baker Borer. Vertical.

Serial No. 28180. Maker: Baker Bros., U.S.A., Toledo, U.S.A. Fitted with a 5 h.p. Crompton Parkinson motor, 400/3/50, 940 r.p.m., N.6, mounted on top of machine for main drive. Ditto, type K.6, 1.5 h.p., 400/3/50, 940 r.p.m. Motor to feed drive. Rise of spindle carriage activated by hydraulic cylinder, pressure gauge reading 2,000 lb. per sq. in. Rise and fall of spindle 2 1/2 in. approx. Table area 16in. by 18in. wide. Depth to base of work mounting 15in. Mounting is driven hydraulically. Size 34 1/2 in. wide by 9ft. high by 4ft. front to rear.—BOX V347, MACHINERY, Clifton House, Euston Road, N.W.1.

One Wickman Rowland Pedestal

Tool Grinder. Serial No. 360171. Machine No. 408/M. Heavy duty pedestal type tool grinder, for grinding Tunstun and Widia tipped tools. Two wheels, 12in. dia. max. Adjustable angle tool rests for form grinding. Coolant tank and built-in pump. Motorised 400-440/3/50.—BOX V295, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert No. 4 Senior Capstan,

collet or chucking auto feeds to cross slide, saddle and turret, taper turning attachment, screw cutting, ball chuck and bar feed. Complete with all aids and electrica.

EDWIN MILLEN,
70, Clerkenwell Road,
London, E.C.1.
Phone: Clerkenwell 6064.

Facing Lathe, "Wagner," Face-

plate 9ft. (1956), motorised. Excellent condition.—Further details from Dr.-Ing. EMIL LINGEMANN, Rather Strasse 49, Dusseldorf, Germany.

600

POWER FACTOR
CORRECTION CONDENSERS

kVA	Make	Nominal Voltage
117	T.C.C.	415/3/50
100	T.C.C.	420/3/50
80	Dubilier	415/3/50
38	Wego	415/3/50
30	B.I.C.C.	400/3/50
27	T.C.C.	400/3/50
15	B.I.C.C.	415/3/50
10	Johnson & Phillips	400/3/50
5	Byrce	415/3/50

Prompt Delivery, covered by our Guarantee.

GEORGE COHEN SONS
& CO. LTD.

WOOD LANE, LONDON, W.12.
Tel.: Shepherd's Bush 2070, and
STANNINGLEY, NR. LEEDS.
Tel.: Pudsey 2241.

One Herbert 4-spindle Drilling

Machine. Four No. 1 Morse taper spindles, 4 speeds 440-2,945 r.p.m., through 4-speed motor, and one reverse. Rise and fall table. Table working surface 10in. by 45in. Hand feed. Fully motorised suds pump. 400-440/3/50.—BOX V368, MACHINERY, Clifton House, Euston Road, N.W.1.

Gallmeyer & Livingston Surface

Grinder. No. 28. Serial No. 828210. Capacity 8in. by 24in. Fully hydraulic table. Infinitely variable speeds. Automatic cross feed both ways. Grinding wheel 10in. dia., 1in. thick. Independent motorised wheel spindle. Through 1 1/2 h.p. motor at 1,445 r.p.m. Micro adjustment to wheelhead feed. Hydraulic pump driven by 1 1/2 h.p. motor, 400-440/3/50. Push-button starters. Coolant tank built on with separate motorised pump. This machine has been rebuilt.—BOX V398, MACHINERY, Clifton House, Euston Road, N.W.1.

One Bryant Hole and Face

Grinding Machine. Model No. 16A. Serial No. P3190. Max. dia. of swing 16in. Max. travel of wheel 16in. Max. grinding travel 13in. Work spindle 150-325-300-450 r.p.m.—BOX V274, MACHINERY, Clifton House, Euston Road, N.W.1.

Covel Surface Grinder Made by

L.S. & W. (Machinery), Ltd. No. 128. Table size 18in. by 6in. Will accept a 10in. wheel. Throat 7in. Table to wheel centre 15in. Max. spindle speed 2,870 r.p.m. Driven by 1/2 V belt from a 3-step pulley. With dust extractor, water tank and pump.—BOX V302, MACHINERY, Clifton House, Euston Road, N.W.1.

K.E.N.T

Broomwade Air Compressor Set. Age

1947. Type EH 220. Amount of air delivered 60 c.f.m. Motor 15 h.p. £195.
A. & S. Lever Mill. Model No. 1. £95.
Dougherty C2. Uni. Mill. Table 34in. x 10in. £135.

G. & L. 24in. x 8in. Hyd. Sur. Grinder.

Model 28. Magnetic Chuck. £475.
Jos. Heap 1in. Tangential Screwing Machine. £165.

Ward 1A Capstan. Bar Feed. £195.

Ward OE Capstan. Bar Feed. £165.
Murad 3Q Capstan. Bar Feed. 5 years old. £150.

Hardinge Precision Lathe. 5in. £37 10s.

"Rollo" 6in. S.S. & S.C. Lathe. £150.
Colchester "Triumph" 7 1/2 in. S.S. & S.C. Lathe. Q/c box, chucks, etc. £345.

Peterman P.10 S.S. Auto. Extensive

collets and equipment. £395.
Ward No. 7 Capstan. Collet Machine. Late post-war model. £875.

Selson 42in. Radial Drill. 5 M.T. £325.

Southbend 7 1/2 in. S.S. & S.C. Lathe. £325.
Warner & Swasey No. 3 Capstan. £225.
Willson 7 1/2 in. S.S. & S.C. Lathe. £235.

Herbert 25 Capstan Lathe. £225.

All machines mot. 400-440/3/50.

K'E-N-T MACHINERY &
ENGINEERING CO.

Datchelor Place, London, S.E.5.

Telephone: ROD. 4149.

One Norton Cutter Grinder.

Table area 2ft. 6in. by 3 1/2 in. Table fitted with hand wheel. Control for slow feed. Table traverse 10 1/2 in. Lever for fast traverse. Wheelhead double mounted and swivels full circle. Wheels 7in. dia. Fully motorised 400-440/3/50, 1/2 h.p., 2,850 r.p.m. Overall size 4ft. 10in. high by 4ft. 10in. long by 3ft. 6in. deep. Approx. weight 28 cwt. Equipment: Manual workhead and tailstock.—BOX V310, MACHINERY, Clifton House, Euston Road, N.W.1.

Jones & Shipman Surface

Grinder. Serial No. 9811/9. 28x50. Size 6in. by 18in. Fully hydraulic. Variable speed table. Auto pick-off feed, 7in. dia. grinding wheel. Built-in coolant system. Counter-balanced wheelhead. Motorised 400-440/3/50. Push-button starter.—BOX V314, MACHINERY, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

ARE YOU LOOKING? FOR A MODERN MACHINE FROM STOCK

A selection from our 1,500 available tools

GLEASON 12in. stroke straight Bevel Roughing and Finishing machine, late type, NEW condition, longest cone distance with 3 $\frac{1}{2}$ in. face 12in., max. pitch cut 3 d.p.

LANDIS 10in. by 72in. type 'C' motor driven Hydraulic Plain Cylindrical Grinding Machine, Serial No. 21699, complete with seven steadies.

SCHNEIDER 24in. by 8in. Horizontal spindle Surface Grinder, hydraulic feeds grinding wheel head swivels through 90 degrees, enabling slide-way and cup wheel grinding to be done. NEW.

KITCHEN & WADE V.15 Vertical Honing (Hydraulic) machines, capacity 2in. to 9in. dia., and up to 25in. length of bore, speeds and strokes hydraulically variable, speeds 0 to 250 r.p.m., strokes 0 to 80ft. per minute.

ARCHDALE 30in. Vertical Millers, table 44in. by 14 $\frac{1}{2}$ in. auto. longtl. feed 30in., auto. cross feed 12in., hand vertical adjustment 18in., 12 spindle speeds 29 to 520 r.p.m.

FAIRBAIRN, LAWSON, COOMBE & BARBOUR S. & S. Lathe, swing 36in., takes 23ft. between centres, two saddles both with taper turning and electric control. 4 $\frac{1}{2}$ in. hollow mandrel, 24 spindle speeds 1.08 to 152 r.p.m.

SENTINEL 6in. by 30in. Hydraulic Copying Lathe operated on electric system, five slides, two back three overhead.

VOLMAN 8in. by 24in. capacity high speed Sliding and Surfacing Diamond Turning Lathe, 12 spindle speeds 95-1,180 r.p.m.

HAAG SS.30 Automatic Gear Grinding Machines for spur gears max. dia for up to 2 $\frac{1}{2}$ in. face 1 $\frac{1}{2}$ in. from 2 $\frac{1}{2}$ in. to 5 $\frac{1}{2}$ in., 8 $\frac{1}{2}$ in. min. pitch circle diameter 1 $\frac{1}{2}$ in., max./min. cutting pitch 2 $\frac{1}{2}$ in. to 12 $\frac{1}{2}$ d.p., max./min. number of teeth 120/10.

PITTLER RE.11.60 Turret Lathes 1 $\frac{1}{2}$ in. centres, spindle flange to turret 31in., spindle hole 2 $\frac{1}{2}$ in., swing 2 $\frac{1}{2}$ in., fitted chasing attachment.

WICKMAN 7 $\frac{1}{2}$ in. Sliding head Precision Automatic, with 3-spindle attachment H-S drilling or screwing attachment, slotting attachment and pump.

HERBERT 23V Vertical Miller, table 68in. by 17in., auto. longtl. feed 48in., auto. cross feed 18in., vertical travel 25in. vertical adjustment of head 10in., spindle speeds 16.5 to 427 r.p.m.

ORMEROD 12in. stroke Slotting machines, max. dia. of work admitted 28in., longtl. traverse 24in., transverse 24in., max. height 18in., dia. of table 30in., nine ram 10-63 strokes per minute.

CHURCHILL VXA Hydraulic Vertical Spindle Surface Grinder, table 60in. by 16 $\frac{1}{2}$ in., dia. of segmental wheel 18in., max. wheel to table 15in., table traverse hydraulically variable up to 100ft. per minute.

RYDERMATIC No. 12 single spindle vertical multi-tool Chucking Auto., max. swing 20in., dia. length between centres 16in., turning slide vertical stroke 8in., facing slide stroke 5 $\frac{1}{2}$ in., auxiliary stroke 4in., speed range 3 $\frac{1}{2}$ in. to 309 r.p.m.

BERTRAM (Niles type) S.S. & S.C. Lathe, 24in. centre on 39ft. bed 20ft. between centres, 3in. hollow mandrel, 2 saddles with independent electrical control and taper turning.

CHURCHILL PBH Universal Grinder, capacity 16in. by 50in., work speeds 46 to 181 r.p.m., table traverse (Hydraulic) up to 180in. per minute.

KNIGHT No. 20 Vertical Milling and Boring Machine canting table 9in. by 40in., longtl. feed 23in., cross feed 10in., speeds 98-2,000 feeds $\frac{1}{2}$ in. to 13 $\frac{1}{2}$ in.

PEARNS RICHARDS No. 1 Horizontal Boring and Facing machine with facing head, quartering table, Vernier Scale, table 20 $\frac{1}{2}$ in. by 32in., facing head 18in. dia.

ROWLAND Model ADD motor driven Hydraulic Duplex Surface Grinders, disc opening 13 $\frac{1}{2}$ in.

ALL MOTORS 400-440 volts, 3-phase, 50-cycle SUPPLY

LITTON'S MACHINE TOOL CO., LTD.

Telephone: SH0reditch 4814/5.

372-378, OLD STREET, LONDON, E.C.1 Telegrams: "Galloon," Avenue, London.

One Churchill Cylindrical Grinder. Fitted with Hydrauto bearings. Hydraulic feed to table. 6in. dia. by 18in. Serial No. 11081. Max. wheel 18in. dia. Max. revs 1,100. Motor speeds 1,430. Wheel W.H. Crompton Parkinson motor, 71/5/201, 7.5 h.p., 400-440/3/50. Metro-Vick. D.C. generator type DY1514, 2 poles, 0.67 kW, 6.1 amps, 110 volts, 1,440 r.p.m. Serial No. 25700B32. Metro D.C. generators type BD1256 for workhead. Motorised and pump. Indicator. Mandrel for wheel balancing.—BOX V285, MACHINERY, Clifton House, Euston Road, N.W.1.

Belliss & Morcom Compressor. 2 stage. 500 cu. ft. of free air per minute at 105 lb. per sq. in. With direct coupled G.E.C. motor, 105 h.p. No. B0576, 108 kW, 415/3/50, 333 r.p.m. G.E.C. exciter, 58 volts, 111 amps, 6.4 kW, 333 r.p.m. Control gear fitted with power factor meter and ammeter, etc. Inter and after coolers. Safety valves, back pressure valves, water flow indicator and connecting piping.—BOX T728, MACHINERY, Clifton House, Euston Road, N.W.1.

One Precimax Cylindrical Grinder. Serial No. 3362/1810 S.P.11. Capacity 6in. by 12in. Fully hydraulic machine. Variable speed table, swivelling. Swivelling table, Hydraulic picker feed. Wheel size 10in. by 1in. Live workhead, D.C. variable speed. Continuous rating 3,000 r.p.m. Wheelhead motor 1.5 h.p., 400-440/3/50, 2,820 r.p.m. Hydraulic motor 1 h.p., 400-440/3/50, 960 r.p.m. Coolant pump and fittings.—BOX V291, MACHINERY, Clifton House, Euston Road, N.W.1.

One Herbert Junior Hand Surface Grinding Machine. Capacity 6in. by 4in. Fitted with magnetic chuck and built-in motor 400-440/3/50. Suitable for form tools and thread chasers. Reconditioned.—BOX V271, MACHINERY, Clifton House, Euston Road, N.W.1.

For Sale—Two Large and Two medium sized choppers suitable for Rubber Pulverizers, etc.—Full details to BOX V234, MACHINERY, Clifton House, Euston Road, N.W.1.

HORDERN MASON & EDWARDS L25 Open-fronted Inclinable Ungeared Power Press, 25 tons capacity, motor driven 400/3/50.

PARKES (MACHINE TOOLS) LTD. WITTON ROAD, BIRMINGHAM, 6. Tel.: EAST 1742.

One Ward 1A Capstan Lathe. Serial No. WT/A4807, Test No. 3. With ball chuck, bar feed and single toolpost. One pair of change gears. Electric pump.—BOX V242, MACHINERY, Clifton House, Euston Road, N.W.1.

One Boley Multi-spindle Drilling Machine. Eight spindles each fitted with collet chucks, the max. dia. is 1in. Table area 11 $\frac{1}{2}$ in. by 7in. Table fitted with lift-up lever. Motorised 2 h.p., 400-440/3/50, 1,430 r.p.m. Overall size 20in. wide by 24in. deep by 72in. high. Approx. weight 10 cwt.—BOX V355, MACHINERY, Clifton House, Euston Road, N.W.1.

3A Ward Capstan For Sale, fitted with dead length collet, chuck and bar feed. All electric 400/3/50.—BOX T735, MACHINERY, Clifton House, Euston Road, N.W.1.

Adcock & Shipley No. 3 Plain Horizontal Milling Machine. Serial No. 7040. Spindle speeds 20-1,400 r.p.m. Feeds 16 changes. Table working dims.: 42in. by 9in. Longitudinal traverse 28in. Cross traverse 8in. Vertical traverse 18in. Table to spindle max. 19in. Table to spindle min. 1in. Double overarm arbor supports. Built-in coolant pump. Tank base. 400-440/3/50.—BOX V244, MACHINERY, Clifton House, Euston Road, N.W.1.

Edgwick No. 2 Horizontal Milling Machine. Serial No. V29283. Spindle speeds 9. Range 24-405 r.p.m. Feeds 9. Range 1in. to 9 $\frac{1}{2}$ in. Table working surface 38in. by 7 $\frac{1}{2}$ in. Overall table size 46in. by 11in. Pulley speed 500 r.p.m. Fitted dividing head. One square Arbor Bar. Fully motorised 400-440/3/50. Push button starters. Dial type.—BOX V253, MACHINERY, Clifton House, Euston Road, N.W.1.

Invicta 6MR 24in. Stroke Shaping Machine (New), motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

O'Keefe & Merritt Generator for sale, 12.5 kVA. Can be seen running. Has had very little use as it was used for stand-by plant only. Output rating 120 or 240-1.60.—BOX T722, MACHINERY, Clifton House, Euston Road, N.W.1.

New Besco Model 54 Type VM35/200 Motorised Multi-Purpose Punching Machine for sale. For interchangeable tool heads for punching, notching and cropping, etc. Max. punching pressure 35 tons. Will punch 1in. through 1in. or 2in. through $\frac{1}{2}$ in. Vee notches in angle iron 2in. by $\frac{1}{2}$ in. Gap 7 $\frac{1}{2}$ in. Complete with several tools.—F. J. EDWARDS, LIMITED, 350, Euston Road, London, N.W.1. or 41, Water Street, Birmingham, 3. Central 7606-8.

New MITCHELL LATHE S.S. & S.C.

Gap Bed. 10 $\frac{1}{2}$ in. H.C. by 9ft. 5in. B.C.

Delivery immediately Ex Stock. Price £1,549

London—

WELLING & WELLING LTD.

4, Victoria Street, London, S.W.1

Telephone - - - ABBey 2341

When answering advertisements kindly mention MACHINERY.


Classified Advertisements (PLANT FOR SALE contd.)

Dial

H O P

7 1 1 1

... FOR MACHINE TOOLS



The following are available for immediate delivery.

LATHES

- COLCHESTER** "Chipmaster" 5".
 "Student" 6".
 "Master" 6½".
 "Triumph" 7½".
 "Mascot" 8½".
- "MITCHELL" 8½" O.M.8", 10ft. Bed.
 10½" O.M.10".
- "CARDIFF" 7½" × 40".
 8½" × 48".
- "WILLSON" 7½", Mark V.
- MYFORD "Super Seven" on Base.
- BOXFORD 4½" × 16" Model CSB.
 4½" × 16" Model CSB on Base.
 4½" × 22" Model CSB on Base.
- HARRISON 4½".
 5½".

MILLING MACHINES

- "VICTORIA" U2 Universal.
 U3 Universal.
 V2 Vertical.
- "DENBIGH" C4 Horizontal.
 C4 Variable Speed, Reversing Table.
- "CENTEC" 2A on Stand.
 2B on Stand.
- "SENIOR" M1 Horizontal.
- DRILLING MACHINES**
- "PROGRESS" 1½" 4E Round Table.
 1½" 4E with Suds Equipment.
 1½" 4E Rectangular Table.
- 2" 2G Bench.
 2" 2GS Pillar.
 2" 1 Bench.
 2" 1S Pillar.
 1½" 3A Pillar.
- "RICHMOND" 48" 1½" Radial.

SHAPERS

- "INVICTA" 18" No. 4MR.
 "ALBA" 18" No. 4S.

HACKSAWING MACHINES

- "WICKSTEED" Hydraulic 8".
 "O & S" 6".
 "KINGLEY" 6".

FILING & SAWING MACHINES

- "EXCEL" No. 4.

DOUBLE ENDED GRINDERS—

- MOTORISED
- "MILFORD" 12".
 "UNION" 12".
 14".

"Attractive Hire Purchase Terms and Credit
 Sale facilities upon application."

IT SAVES TIME TO RING

Nettlefold & Moser

F.RST

NETTLEFOLD & MOSER LIMITED, London — Box 378
 170/194 Borough High Street, S.E.1. Phone: HOP 7111 (40 lines)

When answering advertisements kindly mention **MACHINERY**

Classified Advertisements (PLANT FOR SALE, contd.)

Selections from our Stocks of NEW MACHINES for IMMEDIATE DELIVERY

CINCINNATI No. 3 Dial Type Vertical Milling Machine.
CINCINNATI 3/36 Plain Hydromatic Milling Machine.
CINCINNATI 1/18 Automatic Milling Machine.
CINCINNATI No. 2LU Universal Milling Machine.
PARKSON 2T Universal Milling Machine.
VAN NORMAN 28 Horizontal Milling Machine.
HERBERT 47V and 28V Vertical Milling Machines.
ARCHDALE 18in. and 24in. Vertical Milling Machines.
BROWN & SHARPE No. 12 Production Milling Machine.
HERBERT 9B Combination Turret Lathe.
HERBERT 98 Combination Turret Lathe.
HERBERT 4 Senior Capstan Lathe.
WARD 7, 3A, 2A, 1A Capstans. Arranged Bar Feed.
WARD 7 Combination Turret Lathe.
RYDER No. 6 Vertical Auto.
BROWN & SHARPE 25 and 6G Autos.
B.S.A. 1in. Auto.
NEWALL 10in. by 36in. Plain Grinder.
CHURCHILL BY 10in. by 20in. Plain Grinder.
JONES & SHIPMAN 10in. by 27in. Plain Grinder.
BROWN & SHARPE No. 13 Universal T. & C. Grinder.
BROWN & SHARPE No. 13 Universal T. & C. Grinder.
BROWN & SHARPE No. 2 Universal Grinder.
CHURCHILL Model RA 12in. Ring Grinder.
CHURCHILL 12in. by 36in. Universal Grinder.
CHURCHILL 42in. Ring Grinder.
SCRIVENER 2C Centreless Grinder.
HEALD 46B Borematic.
DEAN SMITH & GRACE 8 1/2in. by 5ft. S.S. and S.C. Lathe Cap Bed.
OLDFIELD & SCHOFIELD 12 1/2in. by 7ft. S.S. & S.C. Lathe. Cap Bed.
DENHAM 7in. by 4ft. 6in. S.S. & S.C. Lathe. Cap Bed.
TOWN 4ft. No. 4 M.T. Radial Drill.
KITCHEN & WADE 4ft. No. 5 M.T. Radial Drill.
KEARNS OA Horizontal Borer.
 Machines Motorised 400-440/3/50.

WESTERN MACHINE TOOLS (SWANSEA) LTD.

72, MANSELL STREET,
SWANSEA.
Tel.: 50061/2.



New & Used Machine Tools.

ELECTRISKA 1 1/2in. capacity Geared Pillar Drill. New.
EDWARDS 6ft. 14 gauge Heavy Duty Universal Drill.
COLUMBIA No. 2 Sensitive type Radial Drill. 2ft. arm. No. 3 M.T.
 No. 20 Power Press. 2in. Fixed stroke.
RASKIN 400-ton Single Crank Toggle Press.
NORTON Horizontal Spindle Surface Grinder. Capacity 8ft. by 16in.
PALLAS Vertical Mill, Sliding and Swivel-head, table 44 by 12.
SANT ANDREA Horizontal Mill, table 72 by 16. Power feeds all ways, rapid traverses.
 All machines motorised 400 volts, 3 phase, 50 cycles.

STRAIGHT & VINES LTD.

MINT STREET, BOROUGH,
LONDON, S.E.1.

Telephone: HOP 4304.

MITCHELL 16 1/2in. Lathe, 17ft. 9in. between centres.
MARTIN 13in. Gap Bed Lathe, admit 13ft. 1in. between centres.
MEUSER 11 1/2in. Gap Bed Lathe, admit 80in. between centres.
CARDIFF 8 1/2in. Gap Bed Lathe, admit 48in. between centres.
KRETA 8in. Gap Bed Lathe, admit 40in. between centres. (Infinitely variable speed.)
WILSON 7 1/2in. Mark V Gap Bed Lathe, admit 36in. between centres.
CARDIFF 7 1/2in. Gap Bed Lathe, admit 40in. between centres.
MASTER 8in. Gap Bed Lathe, admit 36in. between centres.
EXCEL No. 4 Filing and Sawing Machine.

OLIVETTI 13 1/2in. by 48in. Hydraulic Production Cylindrical Grinder.
EXCEL No. 3C Hydraulic Surface Grinder.
BURDETT 18in. by 6in. Hydraulic Horizontal Surface Grinder.

BEACON & MILFORD 10in., 12in., 14in. and 16in. Tool Grinders.

HERBERT, Q. & S., SWIFT CUT and FORTUNA 6in., 8in., 10in. and 12in. capacity Hackawill Machines.

VICTORIA O2 Omnimill.
VICTORIA V1 Vertical Miller, 40in. by 11in.
VICTORIA V2 Vertical Miller, 45in. by 11in.
VICTORIA V3 Vertical Miller, 60in. by 12 1/2in.
SEIG Vertical Miller, 22in. by 9 1/2in.
TAYLOR Vertical Miller, 17 1/2in. by 5 1/2in.
MARLOW Vertical Miller, 22in. by 6in.
VICTORIA U0 Universal Miller, 36in. by 9in.
VICTORIA U1 Universal Miller, 40in. by 11in.
VICTORIA U2 Universal Miller, 45in. by 11in.
VICTORIA U3 Universal Miller, 60in. by 12 1/2in.
VICTORIA U4 Universal Miller, 72in. by 15in.
RICHMOND No. 3 Universal Miller, 48in. by 11in.
DENBIGH C2 Plain Miller, 54in. by 10in.
DENBIGH C4 Plain Miller, 46in. by 10in.
RICHMOND 4ft. Radial Drill, 2in. cap.
RICHMOND SE Radial Drill, 1 1/2in. cap.
REGIC 27in. Radial Drill, 1in. cap.
CONTINENTAL 1 1/2in. and 2in. Column Drills.
KERRY 1 1/2in. and 1in. Drills.
FEORRESS, FACERA, DENBIGH and ELECTRISKA 1in., 1 1/2in., 1 1/2in. and 2in. Drilling Machines.
INVICTA 14in., 18in. and 24in. Shapers.
INVICTA 30in. Stroke Shaper.
ALBA 10in., 14in. and 18in. Shapers.
MAIDEN 2in., 4in. and 6in. Screwing Machines.
SPEEDAX 20in. and 16in. Bandsaws.
MIDSAW Minor and Standard Bandsaws.
SPEEDPART Abrasive Cutting Off Machines.
KALTENBACH Mitre and Bevel Circular Sawing Machines.

TAYLOR, TAYLOR & HOBSON C, CX and CXL Engravers.

NEW MACHINES DUE SHORTLY

MITCHELL 8 1/2in. Lathe, 6ft. 3in. between centres.
EXCEL No. 3C Hydraulic Surface Grinders.
MURAD 2in. and 1in. Capstan Lathes.

Inspect under ideal conditions at
THE F.J.E. MACHINE CENTRE,
ISLINGTON PARK STREET,
Nr. Highbury Corner, London, N.1.

F. J. EDWARDS LTD.,
 359-361, EUSTON RD., LONDON, N.W.1
 Telephone: EUSTON 4681-3771.

And at Lansdowne House, 41, Water St.,
 Birmingham, 3. Telephone: Central 7606-8

Craven 20ft. by 6ft. by 6ft. Planing

Machine with two toolboxes on cross-slide and one side toolbox on each upright. Motorised 400-440 volts, 3 phase, 50 cycles A.C. supply.
 NEW. Delivery January, 1958.—W. E. NORTON (MACHINE TOOLS), LTD., Grosvenor Gardens House, Grosvenor Gardens, London, S.W.1. Phone: Tate Gallery 0653/4. Cables: Norbros, London.

"Drummond" Maximatic Auto-

matic Multi-tool Lathe, capacity 9in. by 42in. Max. swing over bed, 18in.; over slides, 12in. Fully automatic. S.C. motor drive, 400-440/3/50. Air-operated tailstock. Quick-action chuck. Post-war machine.—LEE & HUNT, LTD., Crocus Street, Nottingham.

Reconditioned Herbert 4BS

Chucking Capstan, motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Churchill Redman S.S. & S.C.

Cap Bed Lathe. Series 4000. 12in. by 8ft. between centres. Swing in cap 4ft. 4in. dia. by 20in. gap; 2ft. dia. swing over slide; 20in. dia. swing over saddle. Infinitely variable belt drive to spindle from 3 h.p. motor 400/3/50. With screwcutting change wheels, 48in. and 27in. dia. faceplates, 24in. jaw chuck, 3-point and travelling steady.—BOX V217, MACHINERY, Clifton House, Euston Road, N.W.1.

Schuler 25 Ton Inclinable Power

Press. Strokes per min. 110. Adjustable stroke 10-80 mm. 7in. throat (square). 8 1/2in. radial. Bed and bolster 21 1/2in. by 13 1/2in. with 1 1/2in. bore bolster 2 1/2in. thick. Minimum daylight 12in. from bed, 9 1/2in. from bolster, 40 mm. bore in ram. Fitted with 2 h.p. 3 ph. motor with switchgear and front safety guards. Foot control.—BOX V223, MACHINERY, Clifton House, Euston Road, N.W.1.

V. & O. 75 Ton Straight Sided Single Geared Power Press, 3in. stroke, 415/3/50.

BESCO 8ft. by 1in. Heavy Duty Universal Bending Machine, hand operated.

EDWARDS 4ft. by 12G. Universal Swing Beam Folding Machine, on stand, hand operated.

18in. by 6in. Horizontal Surface Grinder, automatic feeds, wheel truing device, dust extraction unit, 415/3/50.

HEALD No. 72A/3 Gageomatic Internal Grinder, hydraulic, D.C. motor drive, with converter for A.C. supply.

Two **B.S.A.** 9in. Chucking Automatics, 415/3/50. (Air Chucks.)

Two **WARD** No. 2A Capstan Lathes, 415/3/50, bar feed, ball chucks, power feed to saddle.

WARD No. 3A, as above.

VICTORIA U2 Universal Milling Machine, Table W.S. 40in. by 10in., 415/3/50.

VICTORIA U3 Universal Milling Machine, 415/3/50, with vertical milling attachment, dividing head, etc.


VAN NORMAN No. 3 Plain Horizontal Milling Machine. Prismatic arm. Table 64in. by 14in. Speeds 25 to 1,250 r.p.m., 415/3/50.

R.O. Gray

4/6, Minerva Road, Park Royal,
 LONDON, N.W.10.
 Telephone: ELGAR 4841/2.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



NEW MACHINES EX STOCK FOR IMMEDIATE DELIVERY

COLCHESTER MASTER Lathes, 6 1/2 in. by 36 in., quick change box. Motorised 415/3/50.
"ACE" Bench Lathe, 4 1/2 in. centres by 23 in. between. Norton feed box and on cabinet stand. 415/3/50.

ROBLING Lathe, Model 600/2, 5 1/2 in. centres by 24 in. between, 1,920 r.p.m., accuracy 0.0002 in. 415/3/50 A.C.

FEIFER Precision Toolroom Lathe, Model P.12, 9 in. centres by 44 in. between, 1,000 r.p.m. Norton feed box, 187 threads Whitworth, metric and module, turning accuracy 0.002 mm., 415/3/50 A.C.

TROGLIA Lathe, Model TPM20, 10 1/2 in. centres by 76 in. between, 31 in. in gap, 850 r.p.m., Norton feed box. Whitworth, metric and module. 415/3/50 A.C.

GRANVILLE SENIOR 3 1/2 in. H.D. Bench Centre Lathe, 21 in. b.c. Motorised.

ASTRA 6 in. Stroke Slotting Machine, 4 speeds to ram, compound table. Mot. 415/3/50.

SENIOR M.1 Horizontal Milling Machine, Table 25 in. by 6 1/2 in. W/S, long. power feed, spindle speed 12, 50/1,650 r.p.m., coolant pump. Motorised 415/3/50.

P.T.V. Universal Mill, Model 51, Table 33 1/2 in. by 8 1/2 in., power feed, 60/1,200. Dividing heads, etc. 415/3/50.

P.T.V. Vertical Mill, Model IV, Table 39 in. by 8 1/2 in., power feed all directions, swivel head, rise and fall, speeds 60/1,400, dial change. 415/3/50.

ASTRA Vertical Mill, Table 23 in. by 8 in. hand feeds to table in all directions. No. 8 Morse spindle. Motorised 415/3/50.

FIVE STAR Tool and Cutter Grinder, capacity 5 in. by 12 1/2 in., with motorised workhead for external and internal grinding. 415/3/50.

FLOTT Double End Pedestal Grinders, 8 in. and 12 in. wheels. 415/3/50.

Q. & S. SAWMASTER Hacksaws, Capacity 6 in. by 6 in., and 8 in. by 8 in., coolant pump, hydraulic lift. 415/3/50.

PLEASE ADDRESS YOUR ENQUIRIES TO
DEPARTMENT "P."

WILLIAM URQUHART

1023-1027, Garratt Lane, London, S.W.17

'Phone: WIMBLEDON 6341

New COLCHESTER 'Mascot' S.S. and S.C. Gap Bed Lathe

8 1/2 in. H.C. by 54 in. B.C.

PRICE: £898 Os. Od.

Delivery, immediately ex our
London stock.

WELLING & WELLING, LTD.

4 Victoria Street - London - S.W.1

Telephone: ABBeY 2341

Head Internal Horizontal
Spindle Grinder. Serial No. 9465. No. 50 hydraulic horizontal spindle machine, with planetary head. Single spindle hydraulically operated longitudinal and transverse table feeds. Table 15 in. by 28 in. Spindle centre to table 17 in. Automatic cut-out equipped with Head auxiliary table unit, with 20 in. dia. rotary indexing table. Fixture and 3-position micrometer adjusted wheel truing unit. Pressure pump and splash guards.—BOX V317, MACHINERY, Clifton House, Euston Road, N.W.1.

HARRY KIRK

can recommend the following modern
quality machines from STOCK:

BROWN & SHARPE HORIZONTAL
SPINDLE SURFACE GRINDING
MACHINE. Capacity 18 in. by 6 in.

CHURCHILL INTERNAL GRINDING
MACHINE. Capacity 2 1/2 in. diameter by
9 1/2 in. long.

CHURCHILL HORIZONTAL SPINDLE
ROTARY SURFACE GRINDING
MACHINE, 2 1/2 in. diameter. Tilting table.
MODERN OPTICAL PROFILE GRIND-
ING MACHINE.

LANG JUNIOR CENTRE LATHE. Capacity
6 1/2 in. centre height by 30 in. between
centres.

HERBERT No. 4 CAPSTAN LATHE,
fully equipped with Tooling and Bar
Chuck.

ASQUITH 4 ft. 9 in. PORTABLE UNIVER-
SAL RADIAL DRILLING
MACHINE. No. 4 M.T. spindle, 6 speeds
41,300 r.p.m., motorised 400/3/50 cycles
supply.

WEBSTER & BENNETT VERTICAL
BORING AND TURNING MILL,
Series "P", 36 in. table. Max. swing
42 in. Late machine.

B.S.A. 9 in. SINGLE SPINDLE CHUCKING
AUTOMATIC. Complete with air-
operated chuck.

KITCHEN & WADE VERTICAL FINE
BORING MACHINE. 14 in. stroke.
Compound table.

KITCHEN & WADE HEAVY DUTY
PILLAR DRILL. No. 5 Morse. Speeds
22-1,000 r.p.m.

NEWALL CYLINDRICAL GRINDING
MACHINE. Type L. Capacity 10 in.
by 36 in.

COLLET & ENGLEHART HORIZONTAL
BORING MACHINE, 3 in. sliding spindle.
39 in. cross feed. Max. distance spindle
to top table 42 in.

Further details from

HARRY KIRK ENGINEERING LTD.

BRANDON ROAD WORKS, BRANDON
ROAD, COVENTRY.

'Phone: WALSGRAVE-ON-SOWE 2213/4

One Leland Gifford Two-spindle

Drilling Machine. Independently motorised
spindles. Spindle speeds 4. Range 500-
3,000 r.p.m. Table area 25 in. by 15 1/2 in. Rise
and fall to knee table. Motorised 400-440/3/50.
Two machines available.—BOX V345,
MACHINERY, Clifton House, Euston Road, N.W.1.

New Boxford Model B Lathe,

complete with stand, standard equipment,
motorised 220/1/50. In Stock for your inspection.
—JAMES W. CARR & CO., LTD., 7/15,
Rosebery Avenue, London, E.C.1. Tel.: Ter-
minus 8866 (P.B.X.).

One Herbert Two-spindle Drill-

ing Machine. Motor type No. 8A53.
Motorised each spindle. Spindle speeds 2,000,
3,500, 5,000 r.p.m. Rise and fall table. Table
working surface 15 1/2 in. by 24 in. Throat 7 in.
Max. distance spindle to table 30 in. Built-in
lighting to each spindle. Motorised suds pump
and fittings. Push-button starter, 400-440/3/50.
—BOX V364, MACHINERY, Clifton House,
Euston Road, N.W.1.

One Pollard Corona Vertical

Borer. Vertical traverse of spindle 12 in.
One spindle speed approx. 350 r.p.m. Spindle
bored No. 4 Morse taper. Power feed to spindle.
Motorised 5 h.p. Crompton Parkinson motor,
400-440/3/50, 720 r.p.m. Motorised coolant
pump.—BOX V358, MACHINERY, Clifton House,
Euston Road, N.W.1.

Robot Surface Grinder. 6 in. by

18 in. Auto. feeds to table, fully motorised,
reconditioned.—BOX V75, MACHINERY, Clifton
House, Euston Road, N.W.1.

Pollard 4-spindle Drill with Pole

change motors to each spindle. No. 3
Morse taper. Hand feeds to quill. Electric
suds pump.—BOX V713, MACHINERY, Clifton
House, Euston Road, N.W.1.



A SELECTION OF MACHINE TOOLS FROM STOCK.

MILLERS.

DENBIGH C4 Universal, 46 in. by 10 in. New.
VICTORIA Model U2, 45 in. by 11 in. New.
VICTORIA Model U1, 40 in. by 11 in. New.
VARNAMO 50 in. by 12 in. Universal. New.
CINCINNATI 2M Vertical, 52 in. by 10 1/2 in.
CINCINNATI No. 2 Plain, Dial Type.
CINCINNATI No. 4 Plain, Dial Type.
KENDALL & GENT No. 25RVM Vertical.

CAPSTANS AND TURRETS.

WARNER & SWASEY No. 2, Chucking.
WARNER & SWASEY No. 3, Chucking.
WARD 2A and 3A, Bar Feed Capstans.
HERBERT 4B, Bar Feed.
WARD No. 7 Capstan. Covered bed.
WARD No. 8 Combination Turret. Covered
bed.
HERBERT 2B, Bar Feed.
PEGARD 2 1/2 in. Bar Feed. Several.
WARNER & SWASEY No. 4 Presselector.
Chucking.
HERBERT 1S, Bar Feed.
GISHOLT No. 3, Bar Feed.

LATHES.

FABIUS 8 1/2 in. Tool Room Lathe.

GRINDERS.

CHURCHILL 12 in. Model HBY Internal
Hydraulic.
THOMPSON 6 in. by 18 in. Hydraulic Surface
Grinder.
JONES & SHIPMAN 6 in. by 18 in. Model 540.
NORTON 12 in. by 36 in. Universal.
NEWALL Model LU 10 in. by 24 in. Universal,
with Internal Spindle. Hydraulic.
LANDIS 10 in. by 48 in. Type C Plain Hydraulic.

PLANERS AND SHAPERS

HULSE 24 ft. by 10 ft. Planer. 4 boxes.
DIMCO 24 in. Shaper. New.
WOTAN 27 in. Shaper. Hydraulic.
NEW ENGLAND Shaper, 10 in.
BURDETT Slotters, 7 in.-12 in. New.

DRILLING AND TAPPING.

ASQUITH 6 ft. Arm Universal Radial Drilling
Machine, with swivelling arm and saddle.
Low base.
HULLER UG3 Precision Tapping Machine,
3 in. capacity.
HULLER UG5 Precision Tapping Machine,
5 in. capacity.
JONES & SHIPMAN "Electrotap" Pre-
cision Tapping Machine, 3 in. capacity.

AUTOMATICS.

FOOTBURN 1 1/2 in.
B.S.A. 3 in. long stroke.

MISCELLANEOUS.

BALLINGER 2 in. Capacity Abrasive Cutting-
off Machine.
BUYER Light Jig Borer, table 24 in. by 9 in.

All machines motorised 400-440/3/50 cycles.
Detailed stock list on application.

DIMCO LTD.

415-417, OXFORD STREET, W.1

PHONE: MAYFAIR 1585 (4 LINES)

Potter & Johnson 5D Semi-

automatic machine. Powerful, large capacity
machine, well equipped. Modern machine.
Fully motorised.—For further details apply to
BOX V151, MACHINERY, Clifton House, Euston
Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

C.E.M.

SEDGWICK Univ. Plate Bender and Folder, 6ft. x 1in. cap., complete with standard tooling, full elect. equip., excellent condition, ready for operation.

EDWARDS Undercrank Guillotine, 8ft. x 1in. cap., guides, guards and holdown. Elect. equip., excellent cond., ready for operation.

EDWARDS 6ft. x 14g Chicago type Folding Machine, hand operated.

8in. WILLSON S.S. & S.C. Lathe, excellent condition.

7in. WILLSON S.S. & S.C. Lathe, excellent condition.

ACME-GRIDLEY Automatic, 4 spindle, 3in. cap., considerable equipment.

CHAMBERSBURG CECOSTAMP Stamping and Pressing Machine, bed and ram areas 96 in. and 48 in. air controlled.

PROGRESS 4E Pillar Drilling Machine with circular table and suds equipment. New.

Fully detailed Stock Lists available.

All Machines motorised 400/3/50.

CHARLES E. MATTHEWS
(MACHINE TOOLS) LTD.
34, GLADSTONE ROAD,
CROYDON, SURREY.
Thornton Heath 1783.

Wadkin Radial Arm Spar Drilling Machine, 4 spindle speeds 250 to 3,000. Power feed, No. 3 Morse taper in spindle, 4 h.p. motor.—BOX T934, MACHINERY, Clifton House, Euston Road, N.W.1.

Asquith Twin Headed Keyseat-ing Machine. Series 8.3160. Table 18in. long, 6in. between spindles. 3 spindle speeds 500 to 2,000 r.p.m. Mechanical reciprocating table with 8 cycle speeds 4.7 to 36 per min. Automatic cam feed to depth. Self-contained motor and suds pump.—BOX V261, MACHINERY, Clifton House, Euston Road, N.W.1.

Wanderer Thread Milling Machine, serial No. 24300. 11in. dia. capacity, 8in. traverse. Built in motor, 2 speed change pulley. Capacity 8 to 26 t.p.i., with change wheels.—BOX V177, MACHINERY, Clifton House, Euston Road, N.W.1.

Index 12 mm. Single-spindle automatic machine, 11000 series. Six hole turret machine with third slide, high speed drilling and slotting attachment. Auxiliary drive for attachments fitted. Bar feeds, tube and stands. Fully motorised 400/3/50.—Write to BOX V175, MACHINERY, Clifton House, Euston Road, N.W.1.

Cardiff S.S. & S.C. Gap Bed Centre Lathe, 7in. height by 40in. between centres. Motorised 400/3/50.—SOUTHERN ENGINEERING & MACHINERY CO., Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

One Electric Girder Drill. No. 1102. Capacity No. 2 Morse, hand feed, swivel arm and pedestal. Motorised Higgs 1 h.p. motor A.C. 400v., 3ph., 1,425 r.p.m. No. 242617. Push-button switch. Arm extended 37in. Base size 14in. by 9in. Height from bottom of taper to base 15in.—BOX V336, MACHINERY, Clifton House, Euston Road, N.W.1.

Cleveland Single Spindle Auto. for sale. 1in. capacity bar machine. Countershaft drive but could easily be motorised. Very nice condition. Some equipment available.—BOX T570, MACHINERY, Clifton House, Euston Road, N.W.1.

Excello Fine Borer, Style 1212A, fitted with two heads and fully motorised with electric control switches. Hydraulic feeds 1in. to 60in. per min. Table travel 12in., table area 22in. by 13in. Minimum hole 1in. dia. Centre height 8 1/2 in. Very good condition.—BOX T557, MACHINERY, Clifton House, Euston Road, N.W.1.

Bechler Model AE.4 Swiss Auto., capacity 4mm. bar machine, 4 tool slides and tailslide. Motorised 400/3/50. 3 h.p. motor mounted on outside bracket.—BOX T582, MACHINERY, Clifton House, Euston Road, N.W.1.

NORMAN E. POTTS (B'HAM) LTD.
offer:—

ABRASIVE 3B 24in. by 8in. Hor. spindle Surface Grinder.

CINCINNATI No. 2 Dial type Vert. Miller.

MIL. BARNES "Hydram" Hydraulic Drilling. Boring and Reaming or Multi-spindle.

4in. cap., 36in. stroke, 6 M.T. 30 h.p.

LOUPOIN 21ft. by 6ft. by 6ft. 6in. Double Column Planing Machine, with 3 Tool-boxes and Lancashire motor drive. New 1937.

130, MOSELEY ROAD, BIRMINGHAM, 12.
VIC. 1278.

FOR IMMEDIATE SALE

3-Electric Box type Vitreous Enamelling/Annealing 250 kw. Furnaces. Internal dimensions 54in. wide by 32in. high by 13ft. deep. Complete with loading forks, power operated door and temperature control gear 0-1000° C. by Cambridge. In first class order throughout and available for inspection.

The General Electric Co. Ltd.
Swinton Works, Mexborough, Yorks

Cincinnati Dial Change No. 3 Vertical Milling Machine. American manufacture. Fitted with sliding head and all power feeds. Fully motorised 400/3/50. Excellent machine. Seen London.—BOX V155, MACHINERY, Clifton House, Euston Road, N.W.1.

6ft. Asquith Radial Drilling Machine. Fitted with box table (loose). D.C. variable-speed motor drive to quill spindle and A.C. motor and generator with control panel. All in very good condition.—Apply BOX V160, MACHINERY, Clifton House, Euston Road, N.W.1.

Index 52 Single-spindle Auto-matic machine, 40,009 series. Capacity 2in. dia. bar. Fitted with 3rd slide and bar tube and stand. This machine is in excellent condition. A nearly new chasing attachment could be made available if required. Seen and tried in Weybridge area.—BOX V168, MACHINERY, Clifton House, Euston Road, N.W.1.

Cnomatic 4-spindle Automatic. Capacity 3 1/2 in. dia., 3 1/2 in. hex., 2 1/2 in. square. Bar feed equipment. 25-h.p. motor, 400/3/50. Excellent condition, 1943 manufacture. Reasonable offer.—BOX T760, MACHINERY, Clifton House, Euston Road, N.W.1.

Omes Upsetting Machine, Type R.T. Serial No. 154. Approx. capacity 15 kW. Hydraulic ram. Fully motorised 400/3/50.—BOX T683, MACHINERY, Clifton House, Euston Road, N.W.1.

LEONARD ROTH

ABBOT STREET,
KINGSLAND HIGH STREET,
DALSTON JUNCTION,
LONDON, E.8.
TERMS ARRANGED.
Tel.: CLIsold 0513/4.

RICHMOND Horizontal Milling Machine, Type O.3, with vertical attachment, 40in. x 9in. Table, 400/3/50. £250.

ALBA 22in. Shaper, Motorised 400/3/50. £250.

WARD No. 8 Combination Turret Lathe, 3 1/2 in. h.m., 12in. 3-jaw chuck, 10-h.p. Motor 400/3/50. £350.

SOUTHWARK No. 2 Capstan for chucking and collet operation, suds pump, etc. 400/3/50. £195.

WE HOLD BIG STOCKS OF LATHES, SHAPERS, MILLS, DRILLS AND PRESSES. PLEASE WRITE FOR LISTS.

Bliss 18 Power Press For Sale.

Serial No. 54639. Variable stroke 1/2 to 2. Motorised 400/3/50. Fitted with safety guards.—BOX T692, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert Hunt Tap Grinding

Machine. Capacity 1/2 in. to 2in. dia. taps. Motorised. Cheap.—BOX T666, MACHINERY, Clifton House, Euston Road, N.W.1.



INVITE ENQUIRIES
FOR REPRECISIONED
AND GUARANTEED
JIG BORERS
AND GRINDERS
OF ALL TYPES



**The Newall Used
Machine Division**

Oundle Road Works,
ORTON LONGUEVILLE,
PETERBOROUGH.

Telephone 6116

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

Newman**FOR MACHINE TOOLS**

Below are selected offers from our extensive and varied stock

SLOTING MACHINES**CRAVEN** 7ft. stroke Vertical Slotting Machine.**MUIR** 17in. Stroke Vertical Slotting Machine.**GRINDING MACHINES****CHURCHILL** Plain Hydraulic Cylindrical Grinding Machine Model BY capacity 10in. by 20in.**SCRIVENER** No. 2 Centreless Grinding Machine.**LANDIS** Plain Hydraulic Cylindrical Grinding Machine, capacity 10in. by 9in.**LANDIS** Hydraulic Universal Grinding Machine, 14in. by 36in. between centres.**LANDIS** Type D Hydraulic Crank Pin Grinding Machine, capacity 21in. by 72in.**NEW EXCEL** No. 3 Hydraulic Surface Grinding Machine.**NEW EXCEL** No. 5 Tool and Cutter Grinder.**MATTISON** Hydraulic Horizontal Spindle Surface Grinding Machine, 60in. by 14in. by 14in.**BROWN & SHARPE** No. 2 Surface Grinding Machine, capacity 6in. by 18in.**NORTON** Universal Grinding Machine, type "C", capacity 12in. by 36in.**LANDIS** Type "C" Plain Hydraulic Cylindrical Grinding Machine, capacity 10in. by 36in.**NORTON** 6in. by 18in. Plain Cylindrical Grinding Machine.**SNOW** Model VA12 Vertical Spindle Surface Grinding Machine.**BROWN & SHARPE** No. 22 Electrically Controlled Plain Grinding Machine, capacity 10in. by 36in.**CHURCHILL** Universal Grinding Machine 10in. by 24in. between centres.**B.S.A.-LANDIS** Type "C" Plain Hydraulic Cylindrical Grinding Machine, 6in. by 30in. (Two available.)**CINCINNATI** No. 2 Universal Tool and Cutter Grinder.**BORING MACHINES****ASQUITH** 7in. Horizontal Floor Boring Machine.**PENSOTTI** 48in. Vertical Boring Machine (1954).**BERTHIEZ** Model 9340 Vertical Boring Mill, table diameter 7ft. 10in., maximum turning capacity 9ft. 6in. (1953).**GRAFFENSTADEN** Model TW181 Vertical Boring Mill, table diameter 6ft., maximum turning capacity 6ft. 7in.**MILLING MACHINES****SUNDSTRAND** Hydro-Screw Rigidmill Automatic Production Milling Machine, table 7in. by 14in., table traverse 48in.**CINCINNATI** 1/12 Horizontal Production Milling Machine.**RICHMOND** Model 03SD Universal Milling Machine with Dividing Head, Vertical Attachment, etc.**NEW VICTORIA** Model V2 Vertical Milling Machine.**CENTEC** Model 3R Automatic Production Milling Machine, table 8in. by 30in.**CINCINNATI** 2M Universal Milling Machine.**REINECKER** Vertical Milling and Jig Boring Machine, table 32in. by 13 1/2in.**MILWAUKEE** No. 4H Plain Horizontal Milling Machine, table 74in. by 15 1/2in.**CINCINNATI** No. 3C Plain Horizontal Milling Machine.**VICTOMATIC** Automatic Cycle Production Milling Machine, capacity 50in. by 10in.**GEAR MACHINES****ORCUTT** 24in. Gear Grinding Machine.**KOLB** Gear Grinding Machine.**SYKES** V.10 Gear Generator.**GLEASON** 3in. Bevel Gear Generators, (Two available.)**GLEASON** No. 9 Bevel Gear Completer Machine.**DRILLING MACHINES****KITCHEN & WADE** 28V10 Single Spindle Vertical Drilling Machine, No. 4 M.T.**ARCHDALE** Multi-spindle Drill Machine, 36 spindles.**HETTNER** Radial Drilling Machine having 10ft. Radial Arm elevating column type.**POLLARD** Model 12MXT Multi-Spindle Drilling Machine, twelve adjustable spindles.**TOWN** 30in. Vertical Spindle Boring, Drilling and Tapping Machine, No. 5 M.T.**RICHMOND** 36in. Radial Drilling Machine.**CAPSTAN & CENTRE LATHES****WARD** 3A Capstan Lathe.**DEAN, SMITH & GRACE** Centre Lathe, 64in. by 31in. between centres.**CRAVEN** Sliding Bed Break Lathe, 8ft. dia. swing by 17ft. 6in. between centres.**EDGWICK** Centre Lathe, 7 1/2in. by 42in. between centres.**WARD** 7B Hexagon Turret Lathes with bar feed. (Two available.)**OLDFIELD & SCHOFIELD** Boring and Surfacing Lathe, cross-traversing Turret type.**LE BLOND** Regal Centre Lathe, 9 1/2in. by 42in. between centres.**BARDON & OLIVER** No. 5 Capstan Lathe.**BRADFORD** 8 1/2in. centre height by 30in. between centres Centre Lathe.**HERBERT** No. 8 Combination Turret Lathe. **DEAN, SMITH & GRACE** Centre Lathe 12in. by 60in. between centres.**WARD** 2A Capstan Lathe.**URQUHART LINDSAY & ROBERTSON****ORCHAR** Centre Lathe, 16in. by 30ft. 6in. between centres.**LIBBY** Model 2H-8 Combination Turret Lathe, 8 1/2in. hollow spindle.**SWIFT** Gap Bed Centre Lathe 15in. by 11ft. between centres, swing in gap 54in. by 18in.**HERBERT** No. 12 Combination Turret Lathe with comprehensive tooling.**NILES** Centre Lathes 13 1/2in. centre height by 27ft. between centres. (Two available.)**NILES** Centre Lathes, 15in. centre height by 28ft. between centres. (Two available.)**HERBERT** 2D Capstan Lathe with bar feed equipment.**BETTS-BRIDGEFORD** Centre Lathe, 15in. centre height by 16ft. between centres. (Two available.)**ATOMATICS****ACME GRIDLEY** Model RA6 2 1/2in. spindle Bar Automatic.**PONGRACZ** Single Spindle Automatic capacity, 10 mm.**CONOMATICS** 3 1/2in. 4-spindle Bar Automatics. (Three available.)**PLANING MACHINES****URQUHART LINDSAY & ROBERTSON****ORCHAR** Spiral Drive Heavy Duty Planing Machine, capacity 16ft. by 5ft. by 5ft.**STIRK HILOPLANE** Heavy Duty Planing Machine, capacity 19ft. by 7ft. 6in. by 5ft. 6in.**STIRK** Model CX Planing Machine, capacity 16ft. by 5ft. by 5ft.**MISCELLANEOUS****BRONX** Press Brake, capacity 8ft. by 1/2in.**Newman**
for
MACHINE TOOLS**Topical
Touch**

Empire Blend? *

* Machine Tool needs suited to a "T" from our stock.

All the machines on this page are motorised for 400-440 volts, 3 phase, 50 cycles
For further details of any item listed or for a copy of our complete Stocklist write or 'phone:**NEWMAN INDUSTRIES LIMITED**

Machine Tool Division

Telephone: Chipping Sodbury 3311

Branches at: London (Sloane 8206).

Birmingham (Midland 1143).

Manchester (Deansgate 2837/8).

Glasgow (Central 2101/2).

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

ELGAR**NEW MACHINES FOR IMMEDIATE DELIVERY****AUTOMATICS.****TRAUB** A.15 Single Spindle. $\frac{1}{2}$ in. bar capacity.**TRAUB** A.25 Single Spindle 1 in. bar capacity.**BANDSAWING.****KOLLE** BSH. 40M. Friction Bandsaw. Table 22 in. \times 24 in. Cutting speeds 5,400 ft./min.**KOLLE** BS.40F Bandsawing and Filing. Table 22 in. \times 24 in. Speeds infinitely variable 40-400 ft./min.**CO-ORDINATE BORER.****EMTAC** Small Co-ordinate Borer. Table 26 in. \times 11 in. Spindle speeds 350-2,800 r.p.m.**DRILLS.****MAS** VR.2 Radial Drill. Max. drilling capacity in cast iron 1 in. Spindle speeds 90-4,500 r.p.m.**MAS** VR.4 Radial Drill. Max. drilling capacity in cast iron 2 in. Spindle speeds 45-2,000 r.p.m.**MAS** VR.6 Radial Drill. Max. drilling capacity in cast iron 3 in. Spindle speeds 16-1,400 r.p.m.**WEBB** TS.1 Bench Type. Capacity 4 in. Spindle speeds 18,000 r.p.m.**MODEL** WR.80/3-2 Heavy Duty Radial Drill. Drilling capacity in C.I. 4 in. Max. drilling radius 11 ft. 6 in.**GEAR CUTTING.****VOLMAN** Model OH.4 Spur and Helical Gear Shaper. Capacity 6 D.P. \times 6 in. dia.**VOLMAN** Model FO.6 Heavy Duty Gear Hobber. Capacity 6 mod. \times 3 in. dia.**VOLMAN** Model OF.10 Heavy Duty Gear Hobber. Capacity 2 D.P. \times 4 in. dia.**GRINDERS.****A.T.F.** AU.400 Tool and Cutter Grinder. Max. work dia. 7 in. \times 19 in.**A.T.F.** AU.500 Universal Tool and Cutter Grinder. Hydraulic table feed. Capacity 10 in. dia. \times 25 in.**EXGEL** 3/12 Surface Grinder. 24 in. \times 8 in.**GIUSTINA** RU.1000 Universal Grinder. Capacity 12 in. \times 40 in.**KARSTENS** US.16a. Precision Hydraulic Universal. Centre height 5 in. \times 20 in.**OLIVETTI** R4/1200 Hydraulic Production Grinder. Capacity 13 in. dia. \times 48 in.**RIBON** RUR.500 Universal. Capacity 10 in. \times 20 in.**SCHNEIDER** JOH3/1500 Universal Surface and Sidesway Grinder. Table 60 in. \times 20 in.**HORIZONTAL BORING AND MILLING.****DEFUM** CWC50. 3 in. spindle. Table 35 in. \times 44 in. Speeds: spindle 15-515 r.p.m., faceplate 15-300 r.p.m.**DEFUM** HWC110 4 in. spindle. Table 47 in. \times 55 in. Speeds: spindle 81-562 r.p.m., faceplate 81-316 r.p.m.**LATHES.****BOLEY & LEINEN** S122a Precision Vertical Turret Lathe. Bar capacity 1 in.**BOLEY & LEINEN** ML24S Precision Lathe, with multiplier feed box. Spindle speeds 134-1,515 r.p.m.**VOLMAN** Model 8.28 Tool Room Lathe. Centre height 5 in. \times 30 in. Spindle speeds 20-3,150 r.p.m.**ZBROJOVKA** Model SV18R High Speed Precision Lathe. Centre height 7 in. \times 50 in. Spindle speeds 14-2,800 r.p.m.**MILLERS.****BEICHEL** WF.3 Die Miller. Working range 25 in. \times 17 in. \times 11 in. Spindle speeds 95-5,000 r.p.m.**BUSCH** NF1/500 Keyway Miller. Max. slot width 1 in. \times 20 in. long.**GIEWONT** 4FYA Vertical Miller. Table 16 in. \times 79 in. Spindle speeds 18-1,300 r.p.m.**SUPERINDUMILL** Universal Miller. Table 60 in. \times 12 in.**ELGAR MACHINE TOOL CO. LTD.,**172-178, VICTORIA ROAD,
ACTON, LONDON, W.3.

Tel.: Acorn 5555 (7 lines).

H. BELL (MACHINE TOOLS) LTD**Offer from stock:****FROST** 8ft. by 4 in. Cramp Folder. Power list to beam, beam has swing end. M.D. 400/3/50.**CLIFTON & BAIRD** 24 in. Model ACS Automatic Cold Saw. Cap. 8 in. Will cut bars to predetermined lengths.

Hydraulic feeds and clamping.

PLANER, 10ft. by 3ft. by 3ft. capacity. 1 toolbox. Table driven by rack and pinion.**ARCHDALE** 30 in. Vertical Millers. Speeds to 522 r.p.m. With 15 in. circular table.**CINCINNATI** O8 Vertical Miller. Table 24 in. by 9 in. Speeds 150-1,300 r.p.m.**WANDERER** Horizontal Production Miller. Table 23 in. by 7 in. Long traverse 22 in., and quick power.**DARLING & SELLARS** 6A Combination Turret Lathe. Centre height 10 in. Admits 6 ft. between centres.**WILLSON** 7 in. S.S. & S.C. Gap-Bed Lathe. Admits 3 ft. between centres.**WARD** No. 7 Capstans. Speeds to 416 r.p.m. Open head type.**JONES & SHIPMAN** 12 in. by 36 in. Universal Grinder. Hydraulic table operation.**JONES & SHIPMAN** 12 in. by 36 in. Plain Grinder. Admits grinding wheels 14 in. dia. by 1 in. face. Variable hydraulic table feeds.**HERBERT** 3A Chucking Automatic. Speeds to 500 r.p.m.**PETERMANN** Model P.4 Automatic. Six radial tool stations. Post-war machine, with bar feed equipment, etc.**WICKSTEAD** 28 in. Cold Saw. Takes blades 28 in. dia. Cap. in mild steel, 9 in. rounds, 9 in. squares and 18 in. by 6 in. joists.**For full list of modern motorised machine tools write or phone:—****H. BELL (MACHINE TOOLS) LTD**

WALTER STREET, LEEDS, 4.

Tel. 63-7398.

Large Electrical Muffle Furnace,

Box type with Balance Door. Inside dimensions 72 in. d., 30 in. w., 18 in. h., for 1,000 deg. C. W.T. Heavy Elements 50 kW. for 400-440 v., 3-phase, mains. Complete with Controlling Pyrometer and Switch Gear. Price £495.—BOX V281. MACHINERY, Clifton House, Euston Road, N.W.1.

New Drilling Machines.**RICHMOND** 4ft. 6 in. Radial Drill, model HB3/12, 2 in. cap. with coolant equipment.**RICHMOND** 36 in. Radial Drill, model SR2, 1 in. cap. with power elevation and coolant equipment.**PROGRESS** SE, 2 in. cap. Pedestal Drill. **PROGRESS** 4E, 1 in. cap. Pedestal Drill.OUR H.P. CHARGES ARE STILL ONLY 5 PER CENT. PER ANNUM.
G. M. BUCKINGHAM, LTD., 8, Clarendon Avenue, Leamington Spa. Tel.: 1215.**NORMAN E. POTTS (B'HAM) LTD.****offer:—****ARCHDALE** 20 in. Plain Horizontal Milling Machine. Double overarm support. Dial feed and speed change. Motor drive.**HERBERT** type V Junior 2-spindle Drilling and Tapping Machine. Independent motors. Brand New.**ABRASIVE** Model 3B Horizontal Spindle Surface Grinder. 24 in. \times 8 in. table. Motor drive.**URQUHART LINDSAY** 16 in. Centre Lathe, S.S.C. swing over bed 32 in., distance between centres 30 ft. Motor drive.**SMALLPIECE** No. 6 W.S.L. Multi Tool Lathe. Front and rear slide. Condition as new. Motor drive.**CINCINNATI** Production Miller 1/18.106, LORD STREET, WOLVERHAMPTON.
Tel.: 23727.**IN STOCK****KNEELESS TABLE TYPE
VERTICAL
MILLERS****CVM25 KENDALL & GENT.** Separate motor drive for spindle, table and rise and fall of spindle head, with circular table, table dia. 30 in., capacity 30 in. by 36 in. by 32 in., 18 spindle speeds from 15-320 r.p.m.**47V HERBERT.** Multi motor drive, table 72 in. by 17 in., capacity 48 in. by 16 in., max. distance table top to spindle nose 23 in., 16 spindle speeds from 21-750 r.p.m.**28 in. CINCINNATI Hydrotel.** Fixed height bed, single power control lever, stepless feed regulation, rapid power traverse, multi-motor drive, table working surface 28 in. by 32 in., capacity 60 in. by 30 in. by 14 in., vertical travel of spindle head gap 38 in., 16 spindle speeds from 52-1,300 r.p.m.

We also have a good stock of Table Type Milling Machines, Plain Horizontal, Universal and Vertical, by Cincinnati, Archdale, Brown & Sharpe, Parkinson, etc., available.

Inspection invited.

Full details on request to—

SOAG MACHINE TOOLS LTD.,

JUXON STREET, LONDON, S.E.11.

Phone: RELiance 7201.

'Grams: Sotoolasg, London, S.E.11.

Kearns OB Horizontal Boring

Machine. 2 in. travelling spindle. Table 36 in. by 30 in. Spindle speeds to 400 r.p.m. M/d 400/3/50.—ALBERT EDWARDS (MACHINERY), LTD., 79/89, Pentonville Road, London, N.1. Phone: TELmuni 0167/8/9.

Drummond Electric 12-ton

Press. 18 in. gap under ram. 9 in. throat to ram centre. 4 in. gap in bed. 17 in. ram stroke. Front safety trip guard and side guards. Total bed area 15 in. by 10 in. Motorised 2 h.p. 3 ph.—BOX V258. MACHINERY, Clifton House, Euston Road, N.W.1.

Hanson & Whitney Thread Mill.

4 in. by 9 in. Fully motorised and well equipped.—BOX V266. MACHINERY, Clifton House Euston Road, N.W.1.

Horden 160 Ton High Speed

Friction Screw Press, type 4A. Steel frame, 13 in. stroke, 21 per cent. tool space, 6 in. screw, 10 h.p. motor drive.—BOX V212. MACHINERY, Clifton House, Euston Road, N.W.1.

George Taylor Rotary Power

Saw. Blade 10 in. dia. Fully motorised Vee-rope drive. 3 h.p. motor at 940 r.p.m. 400/40/3/50. Equipped with 10 in. saw blades.—BOX V473. MACHINERY, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

NORTON

FOR "NEARLY NEW"

OFFER FROM STOCK—

AUTOMATICS

WICKMAN 5-spindle Bar Automatics, 1½in. capacity. Serial Nos. 423464/5.

BROWN & SHARPE OOG Bar Automatic, Vertical Slide, Bar Stand, turret tools, collets. Serial No. 12715.

CAPSTAN & TURRET LATHES

WARD 2A Bar Capstan Lathe, fitted collet chucks, speed 71 to 1,531 r.p.m. Serial Nos. WT/G. 7223.

HERBERT 4BS Bar Capstan Lathe, fitted turret toolholders, pump, bar feed, speeds 30 to 511 r.p.m.

HERBERT No. 20 Combination Turret Lathe, 7½in. diameter spindle, 28in. swing over bed, 97in. distance spindle to turret. Speeds 5 to 201 r.p.m.

CENTRE LATHES

BROADBENT 14in. S.S. & S.C. Gap Bed Lathe; admits 90in., swings in gap 50in., speeds 5.5 to 204 r.p.m. Well equipped. Nearly New.

CHURCHILL REDMAN 24 ND Facing and Boring Lathe, gap bed, hexagonal turret. Fitted 20in. dia. chuck. Speeds 14 to 408 r.p.m. BUILT 1950.

WILLSON Mark V 7½in. by 48in. S.S. & S.C. Gap Bed Lathes, admits 48in., speeds 54 to 954 r.p.m. and 37 to 739 r.p.m. NEW.

DEAN SMITH & GRACE Model "AN" 7½in. by 48in. S.S. & S.C. Straight Bed Lathe, speeds 11 to 490 r.p.m. Serial No. 20300.

REIDEN 7½in. by 40in. S.S. & S.C. Gap Bed Toolroom Lathe, fitted taper turning attachment, pump, 3-jaw chuck, speeds 25 to 1,350 r.p.m. NEW.

MYFORD Super Seven Lathe, 3½in. by 19in., speeds 25 to 2,150 r.p.m. NEW.

DRILLING MACHINES

G.S.P. 9ft. Elevating Arm Radial Drilling Machine, type 48-S-25, No. 6 M.T. Spindle, capacity 3½in. in steel. Maximum height under spindle 75in., speeds 8 to 1,725 r.p.m. Nearly new.

ARCHDALE 3ft. 6in. Elevating Arm Radial Drilling Machine, speeds 88 to 2,000 r.p.m. Serial No. RD. 5375.

PROGRESS 3A Pillar Drilling Machine. Circular table. NEW.

GRINDERS

BURDETT Hydraulic Horizontal Spindle Surface Grinder, capacity 18in. by 6in. by 10in. For early delivery. NEW.

LANDIS Hydraulic Universal Grinder, type "C", capacity 10in. by 24in. Serial No. 27916.

MYFORD M.G.12 Plain Cylindrical Grinder, capacity 5in. by 12in. NEW.

DISKUS Vertical Spindle Surface Grinder, 24in. dia. wheel. Built 1939.

NEWALL Model 420 Thread Grinder. Well equipped. Built 1943.

MILLING MACHINES—

Vertical

CINCINNATI No. 4 Dial Type Vertical Milling Machine, table 78½in. by 16½in., rapid and power traverses 42in. by 16in. by 16in. Speeds 18 to 1,300 r.p.m. British built 1941.

ASQUITH two-spindle Vertical Milling and Profiling Machine, type LDP, speeds 250 to 3,000 r.p.m. Nearly new.

Universal

CINCINNATI No. 4 Dial type Universal Milling Machine, table 78½in. by 16½in., rapid and power traverses 42in. by 14in. by 19in. Speeds 18 to 1,300 r.p.m. With Universal Vertical Attachment. British built 1947.

REIDEN H.F.30 Universal Milling Machine, table 59in. by 14½in., rapid and power traverses 39½in. by 11½in. by 15½in., speeds 44 to 1,457 r.p.m. NEW.

VICTORIA U.2 Universal Milling Machine, table 45in. by 11in., power feeds 29½in. by 6½in. by 16in., speeds 30 to 1,010 r.p.m. NEW.

DENBIGH C.4 Universal Milling Machine, table 46in. by 10in., automatic longitudinal feed 36½in., speeds 13 to 400 r.p.m. NEW.

Horizontal

ARCHDALE 20in. Plain Horizontal Milling Machine, table 40in. by 10in., traverses 20in. by 5½in. by 12in., speeds 30 to 615 r.p.m.

CINCINNATI 1/12 Automatic Milling Machine, table 35in. by 10in., speeds 50 to 1,500 r.p.m. British built.

SHAPERS & SLOTTERS

INVICTA 6M 24in. stroke Shaping Machine. NEW.

COLUMBIA 28in. stroke Heavy Duty Shaping Machine, Universal Table, U.S.A. Wartime built.

BUTLER 8in. stroke Toolroom Slotter 20in. diameter table. Built 1939.

VARIOUS

BRONX Series 48, 40-ton 8ft. by 14G Press Brake. NEW.

WELLMAN-RYDER Horizontal Borer, traversing spindle 36in., No. 5 M.T., Table 30in. by 54in. U.S.A. Wartime built.

CINCINNATI 10ft. by 3ft. by 3ft. Planer with two toolboxes on the cross-rail.

VELOX 10in. Hacksaw. NEW.

All machines motorised 400-440 volts, 3 phase, 50 cycles, A.C. supply.
Sole London and South of England agents for BRONX Press Brakes.

W. E. NORTON (MACHINE TOOLS) LTD.

GROSVENOR GARDENS HOUSE,

GROSVENOR GARDENS, LONDON, S.W.1

Telephone: TATe Gallery 0633-4-5

Cables: Norbros, London

Showroom and Stores

Bridge Works,

342 Queenstown Road (close Chelsea Bridge), Battersea, S.W.11

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



PIDGEN BROS. LIMITED

HELMET ROW, OLD STREET, LONDON, E.C.1.

Telephone: CLerkenwell 6481.

ALL MACHINES MOTORISED FOR 3 PHASE SUPPLY UNLESS OTHERWISE STATED

**AUTOMATICS**

CONOMATIC 4 4 Spindle.
INDEX OR/12. 4 in. capacity.
CLEVELAND 1 1/2 in. by 18 in. Model B.

CAPSTANS

TURNER 1 1/2 A.
Ward 2A, Serial WT. and 3A Serial M.
GISHOLT No. 4 Simplified. 2 in. cap.
DRUMMOND, Model K, 1 1/2 in. Bar feed.
HILLE R.H. 16 in. Bar feed.
ACCURATOOL 1 1/2 in. Bar feed.
WARNER & SWASEY No. 2 1/2 in. Bar feed.
HERBERT No. 7 Combination Turret.
ACME SW Universal Turret, 2 in. bar feed.
LIBBY 4A 2 in. bar feed.
MURAD 4 in. bar feed.
HAIN & KOLB RH25 1 in. bar. Unused.
SOUTHWARK No. 2. 1 1/2 in. bar feed.

DRILLS

GRIMSTON Electric.
J. & S. 16 in. Fig 739, 3 spindle.
J. & S. Bench, 1,400 to 6,000 r.p.m.
CORONA 12MX Cluster.
DENBIGH 2 1/2 in. B.G. New.
JONES & SHIPMAN 932 1 1/2 in. cap, 1 ph.
JONES & SHIPMAN 15 in. Speed Drill-Max.
HERBERT Type H Junior Pillar.
CORONA 12AX 4 in. cap.
BOLEY Cluster Type.
BRISDON 4 in. 2 Spindle.
ARCHDALE 20 in. Mfg.
J. & S. 20 in., 1 1/2 in. cap.
15 in. HERBERT Type C, No. 3 M.T.

ENGRAVERS

LEINHART IH.
T.H.A. Type G.3.
LIENHARD New. All sizes.

T.T.H. Multi Etcher and Type C.

FLING AND SAWING MACHINES

RAPIDOR No. 1 Hack saw.
CRYPTO ATLAS Horiz. Sawing.
THIEL No. 17 Bandsaw.
WICKSTEED Cold Saw No. 1, 6 in.

GEAR CUTTERS

PETERMANN No. 2.
MAXCUT 7 in. by 2 in. by 6 D.P.
RAPIDAN No. 1 1/2 2 1/2 dia. gears
FELLOWS "Hourglass."

GRINDERS (Cylindrical)

REINECKER 9 in. by 18 in. Hyd. Plunge.
MYFORD MG.12. New.
PRECIMAX MPH Plain. 10 by 24.
PRECIMAX U.P.J. Universal. 12 by 48.
NORTON 6 by 18 Hyd. Type C.
NORTON 10 by 36. Type C.

GRINDERS (Miscellaneous)

J. & S. 12 in. by 24 in. 305 T. & C.
EXCEL T. & C.
SCRIVENER No. 1 C.B. Centreless.
HAMMOND T. & C.
JONES & SHIPMAN Carbide.
VAN NORMAN Piston.
HERBERT HUNT No. 1A, 3 & 4 Drill.

GRINDERS (Surface)

SNOW P24, 24 in. by 8 in., Hyd.
ARWOOD.
P. & W. Vertical Spindle, 36 by 14.

GRINDERS (Internal)

CHURCHILL H.B.A.
SMART & BROWN.
BRYANT No. 16.
SAACKE Model VII, Jig.

GUILLOTINE

KEETONA 4 ft. x 14 G

HONERS

SUNNEN Type LA.

KEYSEATERS

EDGWICK.
CARTER & WRIGHT No. 2, 24 in. by 1 1/2 in.

LATHES

BERRY 1 1/2 in. by 5 ft., S.S. & S.C.
WILLSON 7 1/2 in. by 3 ft., S.S. & S.C.
BRADFORD 8 in. S.S. & S.C.
RYDERMATIC No. 12 Multi Tool.
CARDIFF 7 in. by 60 in.
DENHAM 5 1/2 in. S.S. & S.C.
CROWTHORNE 6 in. by 30 in., S.S. & S.C.
LE BLOND 1 1/2 in. by 16 in. Prod.
WILFIN 6 in. by 24 in., S.S. & S.C.
SOAG-OXFORD 6 1/2 in. by 24 in., S.S. & S.C.
SOUTH BEND 9 in. Workshop 13.
SMART & BROWN 4 in. S.C.
10 in. GLASS 7 1/2 in. b.c. S.S. & S.C.
SMALLPIECE Multi Tool. 9 WSL.
RIVETT S.S. & S.C. No. 608.
LEBLOND Regal 10 in. swing.

MILLERS (Horizontal)

RICHMOND O3.
CINCINNATI O3. & 1-18 Prod.
HATTERSLEY. Table 48 1/2 by 12.
BROWN & SHARPE No. 2 Univ. Light type.

KENT-OWEN 1-8 Manuf.
CENTEC No. 2. Table 12 in. by 3 1/2 in.
SUNDSTRAND No. 0 Rigidmill.
BURKE. Table 16 x 3 1/2.
MILLER & CROWNSHIELD Lever.
ARCHDALE 28 in. Mfr. and G.P.
CINCINNATI 3-24 Hyd.
HERBERT IS. Table 18 in. by 8 1/2 in.

MILLERS (Vertical)

JONES-SIGMA Precision.
HERBERT No. 10. Table 31 in. by 9 1/2 in.
ARCHDALE 18 in. Speeds 79-2,000.
RICHMOND VHM.
VICTORIA V.2. Table 40 by 10.
ARCHDALE 30 in. Table 48 by 12 1/2.
HERBERT ISS. Table 50 by 10 1/2.

PRESSSES (Power)

BLISS No. 39 Horning, 15 ton.
O. & S. 30 tons straightening.
BESCO EB4, 40 tons. New.
TAYLOR & CHALLER B2, 10 ton.
RHODES No. 19. 10 ton.
SCHULER VZZ 15 ton d/s gripper feed.

RIVETERS

TURNER RSS.

SCREWING MACHINES

OSTER 1 in.-6 in. Pipes No. 326.

ATLAS No. 2 3 in.-6 in. (Unused).

SHAPERS

BUTLER 18 in. Supersaper.
NEWLEY 14 in.
ALBA No. 45, 18 in. NEW.
ALBA 10 in. and 14 in.

TAPPERS

HERBERT Flash No. 2, 4 in. cap.
THIEL Nos. 3, 4 and 5.
J. & S. Electrocup 4 in.

THREAD MILLERS

FACKS Plain, cap. 3 in. by 4 in.
ARCHDALE, cap. 6 in. by 1 1/2 in.
REINECKER 8 by 7 1/2 in.
LEES BRADNER Mod. 40. 6 1/2 in. H.M.
HANSON WHITNEY. 8 in. by 40 in.

Churchill Model VS 40 in. by 1 1/2 in Surface Grinder, Segmental Wheel 14 in., with Humphreys 36 in. by 10 in. Magnetic Chuck Motorised 400/3/50.

Price £275

THE SURPLUS MACHINERY &**STORES CLEARING HOUSE LTD.**

EMPIRE WORKS, 108, EAST HILL,

LONDON, S.W.18

Phone: Vandyke 3266-7-8

Magnetic Crack Detector.

American Projection type. To work off 230/250-v. single-phase. Overall dimensions, 5 ft. by 2 ft. by 3 ft. New 1951. Price £165.—BOX V284, MACHINERY, Clifton House, Euston Road, N.W.1.

Schuler 25-ton Inclinable Power

Press. Strokes per min., 110. Adjustable stroke 10-80 mm. 7 in. throat (square), 8 1/2 in. radial. Bed and bolster 2 1/2 in. by 13 1/2 in. with 1 1/2 in. bore bolster 2 1/2 in. thick. Minimum daylight 12 in. from bed, 9 in. from bolster. 40 mm. bore in ram. Fitted with 2 h.p. 3 ph. motor with switchgear and front safety guards.—BOX V255, MACHINERY, Clifton House, Euston Road, N.W.1.

Used Capstans and Comb.

Turret Lathes.

WARD 2A Capstan, almost as new, fitted ball chuck, £450.

WARD 2A Capstan, almost as new, chucking, 2-speed motor, £450.

WARD 7 Comb. Turret Lathe, 2 1/2 in. H.S., reground bed and overhauled, £325.

HERBERT 9 Comb. Turret Lathe, S.P.D., 3 1/2 in. H.S., £150.

GISHOLT No. 4 Simplified Head Capstan, very clean condition, £225.

DRUMMOND Model K Capstan, 2 in. H.S., 1,000 r.p.m., covered bed, well equipped, and as new condition, £495.

OUR H.P. CHARGES ARE STILL ONLY 5 PER CENT. PER ANNUM.

G. M. BUCKINGHAM, LTD., 8, Clarendon Avenue, Leamington Spa. Tel.: 1215.

Wicksteed Power Saw. Series

C.370. Hydraulic feed to saw and to clamp. Large capstan wheel for adjustment to clamp, can also be clamped manually. Saw dia. 27 in. by 1 in. thick by 3 in. hole. 2 Tooling holes 4 1/2 in. by 5 in. centres. Clamping bolts 6 1/2 in. dia. Saw cap. 10 in.—BOX V476, MACHINERY, Clifton House, Euston Road, N.W.1.

Walcott 9 in. by 5 ft. Lathe, Series

AJFM9940. Swing 16 1/2 in. dia. over bed. 41 h.p. 2-speed motor, 3-cone pulley built on countershaft, with back gear gives 12 speeds. Top speed approx. 500 r.p.m. Pick off gearbox for feeds and screwcutting gives 48 selections from 2 to 112 t.p.i. With 12 in. dia. 4-jaw chuck, 16 in. dia. faceplate, 3-point and travelling steady.—BOX V251, MACHINERY, Clifton House, Euston Road, N.W.1.

Taylor Capstan Lathe, Serial

7330-2-45. Collet type with 3 cone pulley drive, 1 in. dia. capacity by 12 in. long. Back and front fixed toolposts and sub pump. Rack splash guard.—BOX V252, MACHINERY, Clifton House, Euston Road, N.W.1.

1,000 Ton Sizing, Coining and

Embossing Press by Eumuco, 2 in. stroke, table 31 in. wide, daylight 13 in., all-steel plate construction.

REED BROTHERS (ENGINEERING), LTD.,

Replant Works,

Woolwich Industrial Estate, S.E.18.

Telephone: : Woolwich 7611/6.

Plauert Vertical Milling Machine.

Swivel and sliding head. Table 50 in. by 12 in. Speeds to 750 r.p.m. M.d 400/3/50.—ALBERT EDWARDS (MACHINERY), LTD., 79/89, Pentonville Road, London, N.1. Phone: TERminus 0167/8/9.

When answering advertisements kindly mention MACHINERY.

WIDDOWSON

VERTICAL BORING & TURNING MILLS

SONDERMANN & STIER 8ft. Double Column Two Tool Ram Vertical Boring and Turning Mill with sidehead, 90in. diameter table to swing 104in. dia., taper turning arrangement, 35 h.p. motor, Rebuilt ready.

CRAVEN 7ft. Double Column Vertical Boring and Turning Mill, 81in. dia. table to swing 91in. dia., 25 h.p. motor.

DRILLING MACHINES

ASQUITH OD.1 4ft. Radial Drilling and Tapping Machine, No. 5 Morse Taper Spindle, speeds 42 to 1,130 r.p.m.

CORONA 15CY Two-Spindle Sliding Head Pillar Drilling Machine, auto feed, speeds 48-660 r.p.m.

JONES & SHIPMAN 20in. Pillar Drilling Machine, No. 3 Morse Taper Spindle.

HERBERT Type 'C' Geared Pillar Drilling Machine, No. 2 Morse Taper.

GRINDING MACHINES

REINECKER ERS.4 16in. x 84in. Capacity Hydraulic Cylindrical Grinding Machine, 15 h.p. motor.

LANDIS Type 'C' 14in. x 36in. Hydraulic Universal Grinding Machine, nearly new.

GIUSTINA R.150 Centreless Grinding Machine, capacity up to 114in. dia., 94in. wide, unused.

CHURCHILL AY. 6in. x 36in. Plain Cylindrical Grinding Machine.

CHURCHILL OSB. 40in. x 8in. Hydraulic Horizontal Spindle Surface Grinding Machine.

NORTON 24in. x 10in. Hydraulic Horizontal Spindle Surface Grinding Machine.

BROWN & SHARPE No. 13 Universal Tool and Cutter Grinding Machine, excellent equipment.

GEAR CUTTING MACHINES

FELLOWS 61 Gear Shaping Machine, capacity, 35in. dia. external; 24in. dia. internal; 4 DP 5in. face.

DEMM SRI-180 High Speed External and Internal Spur Gear Shaping Machine, capacity 6in. Internal, 7in. External, 2in. face.

SYKES HV.14 Universal Spur and Helical Gear, Wormwheel and Spline Hobbing Machine, capacity 14in. dia., 9in. face.

ADAMS No. 5 Gear, Spline shaft and Worm Hobbing Machine, 46in. dia., 46in. long.

PETERMANN No. 1 Bench Mounting Automatic Pinion Cutting Machine, capacity 4in. dia., with magazine, 1in. dia. without magazine, unused.

PLANING MACHINE

SELLERS' POWERFLOW 14ft. x 5ft. x 5ft. Heavy Duty Planing Machine, spiral drive, 50 h.p. motor.

CENTRE LATHES

STANLEY 144in. centres All-gear Bed S.S. & S.C. Lathe, admit 42in. between centres, swing 49in. dia. in gap.

CHURCHILL-REDMAN NM. 9in. Centres Heavy Duty Gap Bed S.S. & S.C. Lathe, admit 48in., between centres, swing 30in. dia. in gap.

MITCHELL NMI. 84in. Centres Gap Bed S.S. & S.C. Lathe, admit 54in. between centres, 34in. hollow spindle.

HOLBROOK C.16 8in. Centres High Speed Toolroom Precision S.S. & S.C. Lathe, admit 36in. between centres, taper turning attachment, rebuilt.

WILLSON 74in. Centres Gap Bed S.S. & S.C. Lathe, admit 78in. between centres, swing 264in. dia. in gap.

WILLSON 74in. Centres Gap Bed S.S. & S.C. Lathe, admit 36in. between centres, swing 264in. dia. in gap.

MILNES 44in. Centres Type DF.4 Gap Bed S.S. & S.C. Lathe, admit 28in. between centres, rebuilt.

DENHAM Junior 44in. Centres Gap Bed S.S. & S.C. Lathe, admit 21in. between centres, swing 124in. dia. in gap.

TURRET & CAPSTAN LATHES

WARD No. 10 Covered Bed Combination Turret Lathe, swing 23in. dia., 44in. dia. hollow spindle, pneumatic collet chuck, bar feed, concentric chuck, excellent equipment.

MINGANTI 20.40P. Universal Capstan Lathes, chucking and bar feed, swing 144in. dia., 14in. bar, several available.

WARD No. 7 Covered Bed Combination Turret Lathe, swing 16in. dia. over bed covers, hollow spindle 24in. dia., 40in. chuck to turret face.

HERBERT No. 7 Junior Combination Turret Lathe, swing 16in. dia. over bed covers, hollow spindle 244in. dia., good equipment.

WARD 3A High Speed Capstan Lathe, speeds 84 to 1,650 r.p.m., 14in. capacity ball chuck, bar feed.

HERBERT 25 Capstan Lathe, pneumatic concentric chuck, speeds 38 to 2,100 r.p.m.

HORIZONTAL MILLING MACHINES

CINCINNATI HYDROMATIC 34/48 Plain Horizontal Production Milling Machine, table 67in. x 18in., hydraulic traverse 48in.

CINCINNATI Model OM. No. 3P Single Dial Type Plain Horizontal Milling Machine, Table 624in. x 154in.

MILWAUKEE 2H Plain Horizontal Milling Machine, table 50in. x 10in. speeds 35 to 1,400 r.p.m.

ARCHDALE 28in. Plain Manufacturing Horizontal Milling Machine, table 49in. x 13in.

VAN NORMAN 22L Ram Type Horizontal Universal Milling Machine, table 45in. x 10in. vertical attachment, slotting attachment, dividing heads, etc.

INDUMA FUM2A Universal Horizontal Milling Machine, table 39in. x 94in., vertical attachment, dividing heads.

VERTICAL MILLING MACHINES

MAXIMILLER 4P Heavy Duty Vertical Milling Machine, table 76in. x 18in., 42in. traverse.

MILWAUKEE 4H Heavy Duty Vertical Milling Machine, speeds 20 to 1,000 r.p.m., power down feed head.

CINCINNATI No. 3 Dial Type Medium Speed Vertical Milling Machine, table 624in. x 154in.

BROWN & SHARPE No. 3 Standard Heavy Duty Vertical Milling Machine, table 64in. x 17in., speeds 25 to 950 r.p.m.

CINCINNATI No. 2 Dial Type High Speed Vertical Milling Machine, table 524in. x 124in., power down feed head.

ARCHDALE 18in. High Speed Vertical Milling Machine, table 40in. x 10in., auto rotary table 15in. dia. spindle speed 79 to 2,000 r.p.m., excellent equipment, unused.

POWER PRESSES

RHODES 120-ton Geared Double Sided Single Crank Power Press, 24in. stroke, bed 22in. x 30in., pneumatic guards.

RHODES' ULTRA SPEED No. 30 30-ton High Speed Blanking Press, auto gripper feed 6in. wide.

SELSON No. 4 Horizontal Straightening Press or Bulldozer, cross-slide 45in., 18in. stroke.

RHODES No. 20 18-ton Inclinable Power Press, 3in. stroke.

RHODES No. 19 10-ton Inclinable Variable Stroke Power Press, stroke 4in. to 3in.

ALL MACHINES INCLUDE 400-440 VOLTS 3 PHASE 50 CYCLES ELECTRICAL EQUIPMENT

Extended credit facilities arranged and financed entirely by ourselves, enable us to offer terms very much more attractive than those available elsewhere. Our agreement form includes our guarantee for all rebuilt and overhauled machines. "Make your machines pay for themselves whilst they work."

HERBERT WIDDOWSON & SONS LIMITED
CANAL STREET WORKS NOTTINGHAM

TELEPHONE 42061-2-3

TELEGRAMS TOOLS NOTTINGHAM

Classified Advertisements (PLANT FOR SALE, contd.)

TATE**MILLING**

CENTEC No. 2 Plain 12in. by 4in. with Vertical Head. £70
EMJ Model 225 Universal, 31in. by 8in. with Vertical Head. £295
EMJ Model 185 31in. by 8in. Plain. £185
PALLAS Horizontal Model HOO, 18in. by 6in. £150
ROCHAUD Horizontal, 40in. by 10in. with auto. cycle (almost new). £765
RICHMOND No. 01 Plain, 30in. by 8in. with Vertical Head. £375
VICTORIA Model V.2 Vertical, 45in. by 11in. (almost new). £985

GRINDING

LUMSDEN Model 70 LEOD Vertical Surface, with magnetic chuck, 48in. by 12in. £1,275
MYFORD Model M.G.12, 12in. by 5in. Cylindrical and Internal. £535
New UNION G.25 Tool and Cutter Grinding Machine. £169 5 0

SHEET METAL

BESCO Type F, Size No. 8, 50in. by 31in. Slip Roll "B" Hand-operated Gearing Bending Roller.
BESCO Production Treadle Guillotining capacity 48in. by 16in. S.W.G.
B.O.C. 36in. Oxygen Cutting Machine (as new) with rectifier for same.

SHAPING

INVICTA 2MR Shaping Machine (1957). £350

DRILLING AND BORING

KITCHEN & WADE Vertical Cylinder Drilling and Boring Machine. 5 M.T. spindle, 48in. by 24in. compound table (1948). £565
PROGRESS No. 3 1 1/2in. Pedestal Drill (almost new). £85

LATHES

HARRISON 11in. Swing Lathe (almost new). £325
MYFORD Model ML7 Lathe, on cabinet. £50
MILNES 6 1/2in. by 72in. Gap Bed Centre Lathe. (1953)
MITCHELL OF KEIGHLEY 6 1/2in. by 60in. Gap Bed Lathe (1952). £400
WILLSON 7 1/2in. by 32in. Gap Bed Centre Lathe "Nawel". £325
New COLCHESTER 6in. Student "Colt" with equipment (two machines). £349 each
New WILLSON 6 1/2in., with equipment. List
COLCHESTER 7 1/2in. by 48in., Triumph Lathe Lion (almost new). £465

CAPSTAN LATHES

SIMMONS 1 1/2in. Microspeed Collet Capstan. £125
MURAD 1A 1in. Capstan (unused). £565
WARD 1 1/2in. Bar Capstan (two years old).

POWER PRESS

SWEENEY & BLOCKSIDGE No. 9 Column 25-ton Power Press (1956).

SPECIAL FINANCE.**MACHINES BOUGHT****TATE MACHINE TOOL CO. LTD.,**

6, NORTH END PARADE,
 OPPOSITE OLYMPIA,
 LONDON, W.14.

Fulham 6563/4/5.

Precimax 6in. by 24in. Cylindrical grinding machine, hydraulic feeds. Wheel 20in. dia. x 4in. wide. Plunge control fitted. Variable speed to workhead. Reasonable offer to BOX V89, MACHINERY, Clifton House, Euston Road, N.W.1.

Cam Grinding Machine, by Car-lunger. Table stroke 24in. max.; swing 5in. dia. max. Master cam ground from pattern or prototype on machine using auxiliary attachment supplied. This machine has been rebuilt throughout.—Details from BOX V82, MACHINERY, Clifton House, Euston Road, N.W.1.

Pallas No. 1 Horizontal Miller, power feed all directions, 400/3/50. £300.—A. McNAMARA & CO., New Line, Bacup, Lancs. Phone: Bacup 946.

Arnett & Harrison Motorised
 Rolling Mill for sale. Bench mounting, 2 hardened rollers 8 1/2in. long by 3 1/2in. diameter set one above the other in inclined fashion with feed and delivery chutes. Motor drive through Croft reduction unit. Suitable for 230 volts, single phase, 50 cycles supply.—Full details from F. J. EDWARDS LIMITED, 359, Euston Road, London, N.W.1, or 41, Water Street, Birmingham, 3.

Corona 12 MX Multi-Spindle
 Drillers. 12 Spindle models. Table 14in. by 8 1/2in. R. & F. Motorised.—WILCOX & CO., Barr Street, Birmingham, 19. Northern 1234/5.

For Sale, One 14in. Centre
 height by 60in. between centres Churchill-Redman Hydraulic Profile Turning Lathe. Complete with all standard accessories, electrically suitable for 240/120 V. A.C., 3 ph., 50 cycles supply. Originally installed 1953. Excellent condition. Due to lack of suitable copy-turning work the machine has only been used for short periods, equivalent in total to some 9 months running time. Can be inspected in Sheffield.—BOX V259, MACHINERY, Clifton House, Euston Road, N.W.1.

Brown & Sharpe Automatics,
 Nos. 00, 0 and 2, high-speed machines. Also B.S.A. 1in. War-time. Reasonable offers accepted.—C. L. THOMAS, LTD., 18, Park Avenue, Solihull. 1281.

Taylor Challen Inclinable Power
 Press. Type 1290. Cap. 2 tons. Fitted with safety guards. Adjustable stroke. Motorised.—BOX V484, MACHINERY, Clifton House, Euston Road, N.W.1.

Taylor Challen B.2 Press. Series
 8170. 10 tons. Throat 6 1/2in. Daylight sin. Adjustable stroke.—BOX V485, MACHINERY, Clifton House, Euston Road, N.W.1.

5 1/2in. Cap. Precision Capstan
 8 Lathe, Leinen type, motorised, rapid quick change speeds and reverse. High grade lathe, complete with collets and studs equipment. Suitable for making small precision tools. Rebuilt a short time ago at high cost and unused since. Guaranteed as new throughout. Any examination. Price £195.—BOX V286, MACHINERY, Clifton House, Euston Road, N.W.1.

New Invicta "Major" Shapers,
 30in. and 24in., with swivel table and power down feed, £1,022 and £865.
 Also other standard Invicta and Alba models, 10in.-24in.
OUR H.P. CHARGES ARE STILL ONLY 5 PER CENT. PER ANNUM.
 G. M. BUCKINGHAM, LTD., 8, Clarendon Avenue, Leamington Spa. Tel.: 1215.

ACBARS LIMITED
57a, HOLBORN VIADUCT,
LONDON, E.C.1.

Telephone: Central 2287. Telegrams: Acfibr. Cent. London

AVAILABLE FROM STOCK.

All machines listed below are at our Works in Sutherland Walk, Walworth Road, S.E.17.

AUTOMATICS.

HERBERT Auto. Junior
 HERBERT 3A Chucking Auto.
 INDEX OR12 Autos. (2).
 ACME-GRIDLEY, Type R, 4-spindle, 1 1/2in. capacity.
 ACME-GRIDLEY, Type R, 4-spindle, 1 1/2in. capacity. (2 machines.)
 WICKMAN 4mm. Swiss Type.
 RYDERMATIC No. 12 Multi Tool Lathes.

BORERS.

New GRAFFENSTADEN AF.075 Horizontal Borer, 3in. dia. travelling spindle, 17 1/2in. dia. faceplate.

GRINDERS.

ABWOOD Vertical Spindle Surface.
 BROWN & SHARPE No. 2 Surface Grinder.
 NORTON Surface Grinder, hydraulic, 18in. by 6in.
 LANDIS 10in. by 18in. Plain Grinder.
 CHURCHILL 24in. by 10in. Universal.
 BRYANT 16C 16in. Internal Grinder.

CAPSTAN LATHES.

HERBERT No. 0, 1in. collet cap. (3).
 MURAD 1in. Capstan Lathes (3).
 MOREY 2G 1in. Capstan.
 SOUTHWARK No. 2 1 1/2in. Capstan Lathe.
 WARD 2A Capstan Lathes (3), with 1 1/2in. collet chucks and bar feed. Machines have 2 speed motors and power feeds to both saddle and turret.
 HERBERT 2D 1 1/2in. dead-length chuck.
 New MODERN 2C 1 1/2in. bar feed capacity.
 HERBERT No. 3 High Speed Capstan, Air Chucking. Spindle speeds 60-1,500 r.p.m.
 DRUMMOND Type K Capstan Lathes (2)
 GISHOLT No. 4 Friction Head Capstan.
 LIBBY 4R 2in. Capstan Lathe. Bar feed.
 BARONS & OLIVER No. 5 Capstan Lathe.
 HERBERT No. 7 Turret Lathe.
 FOSTER No. 2B Turret Lathe.

CENTRE LATHES.

DENHAM 4 1/2in. Gap Bed.
 New BOXFORD 4 1/2in. Gap A.
 SOAG OXFORD 6 1/2in. Centre Lathe.
 SOUTHBEND 13in. swing taper turning.
 WILLSON 8 1/2in. A.G.H. Lathe.

MILLERS.

New CHRISTEN Swiss Universal Tool and Die Mill.
 HERBERT No. 1 Horizontal (2).
 New VICTORIA U1 and U2 Universal.
 ARCHDALE 20in. Horizontal Mills (3).
 ARCHDALE 28in. Horizontal Mill.
 OLIVETTI FP2 Manufacturing Miller. Table 52 1/2in. by 14 1/2in. Longitudinal traverse 39 1/2in.
 New GRAFFENSTADEN Model GH3 Plain Horizontal, table size 67 1/2in. by 16 1/2in.
 New TAYLOR Vertical, table 17 1/2in. by 5 1/2in.
 RICHMOND VHM Vertical Mill.
 New VICTORIA V2 Vertical.
 New GRAFFENSTADEN FV.102 Vertical Mill. Table 51in. by 11 1/2in.; 39 1/2in. longitudinal traverse.
 HOLROYD T117 Thread Miller.
 HELLER Automatic Thread Millers (4).

MISCELLANEOUS.


ARCHDALE 38in. Radial Drill. Light type.
 JONES & SHIPMAN 2-spindle Pillar Drill, with No. 3 M.T. spindles, power feed.
 New VELOX 7 1/2in. and 10in. Hacksaws.
 New ESSEX 18 Bandsaw.
 New RICHMOND SR2 3ft. Radial Drill.
 New ALBA 18in. Shaper.
 MAIDEN Bar Chamferer, 1in.
 New Fly Presses up to No. 6.

All machines motorised 400/3/50 unless otherwise stated.

When answering advertisements kindly mention MACHINERY.



offer from STOCK this large capacity . . .



CHURCHILL "FB" 36 in.

PLAIN

CYLINDRICAL GRINDER

Max. grinding dia. 37in.
Max. grinding length 192in.
No. of table speeds 10
No. of wheel speeds 2
H.P. wheel motor 30
Type of drive No. 5

INSPECTION INVITED

SOAG MACHINE TOOLS LTD. LONDON
JUXON STREET • LAMBETH • S.E.11
PHONE: RELIANCE 7201 • GRAMS: SOTOOLSAG, LONDON, S.E.11

Wright Table Surface Grinder.

12in. Cup Wheel, flush fitting. Working surface of table 3ft. 6in. by 12in. Built in Dust Extracting Fan and Switchgear. In first-class condition. Price £145.—BOX V287, MACHINERY, Clifton House, Euston Road, N.W.1.

New Lathes Ex Stock

COLCHESTER Triumph, 7½in. by 48in.
COLCHESTER Student, 6in. by 24in.
COLCHESTER Chipmaster, 5in. by 20in. (mid-January).
COLCHESTER Mascot, 8½in. by 4ft. 6in.
COLCHESTER Master, 6½in. by 36in.
WILLSON 6½in. Mark 1, 7½in. Newel and Mark V, and 8½in. Pitel, various lengths b.c.
CARDIFF Lathes, 7½in.-10½in.
OUR H.P. CHARGES ARE STILL ONLY 5 PER CENT. PER ANNUM.
G. M. BUCKINGHAM, LTD., 8, Clarendon Avenue, Leamington Spa. Tel.: 1215.

6 Herbert No. 3 Chucking Automatics. £175.0.0 each.

2 Herbert No. 5 Chucking Automatics. £225.0.0 each.

Year of manufacture about 1934, all motor-driven 400/3/50.

PARKES (MACHINE TOOLS) LTD.,

Witton Road, Birmingham, 6,
Tel: East 1742.

One Specima Disc Grinder,

30in. diameter. Motorised Crompton Parkinson motor, K6, 940 r.p.m., 400-440, 2.8 amps., 3 phase continuous rating.—BOX V306, MACHINERY, Clifton House, Euston Road, N.W.1.

Edgwick No. 2 Horizontal Milling

Machine. Series 28010. Table area 10½in. by 40½in., movement 17in. Cross-slide movement 7½in. Rise and fall 16in. 9 speeds from 21-380. Change lever. Feeds ¼in. to 9½in. Motor enclosed. Fitted with switchgear and pump.—BOX V349, MACHINERY, Clifton House, Euston Road, N.W.1.

Wanderer Thread Milling Ma-

chine, serial No. 24300. 1½in. dia. capacity, 8in. traverse. Built-in motor, 2 speed change pulley. Capacity 8 to 26 t.p.i., with change wheels.—BOX V247, MACHINERY, Clifton House, Euston Road, N.W.1.

Southwark No. 2 Capstan,

4-speed motor combined with 3-cone pulley and high and low clutch lever gives 24 speeds from 23 to 2,560 r.p.m. 6 Power feeds to turret. Back and front toolposts. Fitted to take air chuck. Extension bottle. Suds pump and tank.—BOX V249, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert No. 1 Horizontal Milling

Machine. Table area 5in. by 15in. working. Motorised 0.75 h.p. 400/3/50, 700 r.p.m. Motorised suds pump.—BOX V300, MACHINERY, Clifton House, Euston Road, N.W.1.

Bullard 42in. Vertical Boring

Machine. Side head. Rapid traverse. M/d 400/3/50.—ALBERT EDWARDS (MACHINERY), LTD., 79/89, Pentonville Road, London, N.1. Phone: TERMINUS 0167/8/9.

Asquith Twin-headed Keyseating

Machine. Series 8.3160. Table 18in. long. 6in. between spindles. 3 spindle speeds 500 to 2,000 r.p.m. Mechanical reciprocating table with 8 cycle speeds 4.7 to 36 per min. Automatic cam feed to depth. Self-contained motor and suds pump.—BOX V268, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert No. 1 Hand Mill. 4-

spindle speeds 100-530. Longitudinal table traverse 7in. max. Cross-slide traverse 4in. max. Table top to Arbor centre 9in. max. Table working surface 16in. by 4½in. Motorised 400/3/50, 0.75 h.p. motor. Suds tank and pump.—BOX V327, MACHINERY, Clifton House, Euston Road, N.W.1.

**CRAVEN HYDRAULIC
SLOT HYDROMILL**

motorized 3 phase
for keyways up
to 12in. long by
1in. wide, 9 spindle
speeds, 4 h.p. motor,
excellent condition.

PERCY MARTIN LTD.

106/108, Melton Road Leicester.

When answering advertisements kindly mention MACHINERY.

Edwards

PILKINGTON 2 cwt. size Pneumatic Power Hammer. Overhanging type, without slides. Arranged motor drive for 400/350. Self-contained pump. Longest stroke approximately 17in. Centre of ram to back 14in. Diameter of ram 9in. Weight about 60 cwt. Complete with separate anvil.

NEW STEELING Pyramid Type Plate Bending Roller. Motorised 400-440/350. Capacity 10ft. wide \times 1in. mild steel. Diameter of rollers, top, 9in.; bottom, 7in. Drop end bearing for removal of completed cylinders. Support rollers to bottom rolls. Reduction gearbox drive to bottom rolls with multi-disc slipping clutches. Motorised adjustment to top roller.

GUYSON Shot Blast Unit with air compressor and dust extractor. Two guns. All electrical equipment for 400 volts, 3 phase, 50 cycles. Size of chamber 42in. \times 30in. \times 18in. high. Air receiver 72in. high \times 21in. diameter. Broom & Wade air compressor.

PELS Nibbler-Shear Type AS31260. Steel plate build. Motorised 400-440/350. Cutting head rotates 360 deg. Gap depth 30in. Capacity 1in. mild steel. Adjustable stroke.

NEW Type SK6203. No. 4. Motorised Geared Open End Guillotine. Undercrank type. Capacity 80in. wide \times 1in. thick. Depth of gap in open ends 6in. Automatic sheet hold-down. Calibrated rack and pinion back gauge and all other gauges.

RUSHTON & BRADBURN Double Ended Eccentric Clipping Press. Pressure exerted about 30 tons. Stroke 11in. and 2in. Centre to back 21in. Size of tables 14in. diameter with provision for poppets. Weight about 75 cwt.

Photographs of the above are available

MACHINE TOOLS, NEW AND USED.
Of every description. Attractive Prices.

F. J. EDWARDS LTD.

359-361, EUSTON RD., LONDON, N.W.1

Telephone: EUSTON 4681-3771.

And at Lansdowne House, 41, Water St. Birmingham, 3. Telephone: Central 7806-8

Snow OS 72 Open-side Horizontal

Surface Grinding Machine. Table 75in. by 15in. Hydraulic traverse M/d 400/350.—**ALBERT EDWARDS MACHINERY LTD.**, 79/89, Pentonville Road, London, N.1. 'Phone: TERminus 0167/8/9.

Sweeney & Blocksidge No. 6CP

Power Press, 25 tons. Open front, deep throat, adj. stroke. Mot. ex. condition. Also 40 ton inclinable belt drive.—**L. THOMAS LTD.**, 18, Park Avenue, Solihull. 1281.

Heenan & Froude, Type D.P.X.1

Dynamometer (New). B.T.H. Swinging Field type Dynamometer. Austin A.50 Engine. Excellent condition.—Apply: **BENZOLE PRODUCERS LTD.**, Otterspool Way, Watford Bypass, Watford, Herts. Gadebrook 2786.

13in. Capacity 5-spindle Wick-

8 man Automatic Machine. Fully motorised. In excellent condition.—**BOX T739, MACHINERY**, Clifton House, Euston Road, N.W.1.

Classified Advertisements (PLANT FOR SALE, contd.)

Covel Surface Grinder. Table

size 18in. by 6in. Will accept a 10in. wheel. Throat 7in. Table to wheel centre 15in. Max. spindle speed 2,870 r.p.m. Driven by 1 vee belt from a 3-step pulley. With dust extractor, water tank and pump.—**BOX V384, MACHINERY**, Clifton House, Euston Road, N.W.1.

6ft. Asquith Radial Drilling Ma-

chine. Fitted with box table (dowel). D.C. variable speed motor drive to quill spindle and A.C. motor and generator with control panel. All in very good condition.—**BOX V394, MACHINERY**, Clifton House, Euston Road, N.W.1.

Abrasive Surface Grinder 3B.

Series 2420. Rebuilt. Automatic and hand feed controls. Cap. 8in. by 24in. Max. grinding wheel 10in. by 1in. wide. Wheelhead calibrated 0.0001 divisions. Automatic cross traverse adjustable. Automatic table traverse 2 speeds, fast and slow. Fitted 8in. by 24in. magnetic chuck. Coolant system motorised tank unit. Fully motorised 400/350. With independent motorised dust extractor.—**BOX V385, MACHINERY**, Clifton House, Euston Road, N.W.1.

Craven 25ft. by 6ft. by 6ft. Planing

Machine with two toolboxes on cross-slide and one side toolbox on each upright. Motorised 400-440 volts, 3 phase, 50 cycles A.C. supply. **NEW**. Delivery January, 1958.—**W. E. NORTON (MACHINE TOOLS) LTD.**, Grosvener Gardens House, Grosvener Gardens, London, S.W.1. 'Phone: Tate Gallery 0633/4. Cables: Norbros, London.

No. 7 Ward Motorised All-

geared Combination Turret Lathe, with covered bed. Fitted with bar feed and 2 1/2in. capacity coil chuck, 8 spindle speeds, 37-750 r.p.m. Roller bearings. War-time machine.—**LEE & HUNT, LTD.**, Crocus Street, Nottingham.

Progress No. 4E (New) Pillar

Drilling Machine. 1 1/2in. capacity, motorised 400/350.—**SOUTHERN ENGINEERING & MACHINERY CO.**, Connaught Buildings, Tanners Brook, Millbrook, Southampton. Tel.: Southampton 73101.

Ward OE Capstan Lathe. 4

speeds, 435 to 2,775. 2 single toolposts. Lever slide and turret. Motorised 400/350. Electric suds pump. 1in. dia. capacity. Coilet machine.—**BOX V377, MACHINERY**, Clifton House, Euston Road, N.W.1.

Churchill Cylindrical Grinder.

Size 6in. by 18in. Fitted with Hydrauto wheelhead bearings, hydraulic feeds to table, wide wheel used, modern machine.—**BOX V380, MACHINERY**, Clifton House, Euston Road, N.W.1.

Blanchard No. 10 Rotary Surface

grinding machine. Ring wheel 10in. dia., on vertical spindle. 16in. dia. rotary table, magnetic chuck. Seen and tried London area.—**BOX V121, MACHINERY**, Clifton House, Euston Road, N.W.1.

24in. Leland-Gifford Motorised

4-spindle Drilling Machine, fitted with vertical pole-change motors to each spindle; 8 speeds, 1,500 max. Bored No. 3 M.T.; 3 sensitive feeds, 1 auto. feed. Table 72in. by 24in.—**LEE & HUNT, LTD.**, Crocus Street, Nottingham.

EX STOCK

New MODERN 2C Capstan, 1 1/2in. bar feed.

Used WARD 1A Capstan, 1in. bar feed. **Used WARD 2A** Capstans, bar feed, 1955 Serials.

Used WARD 3A Capstans, bar feed, 1955 Serials.

Used WARD 3A Capstan. Chuck.

New PROGRESS 4E Pillar Drill, 1 1/2in.

New Q. & S. Pillar Drill, 1 1/2in.

New Q. & S. (Kerry) Radial Drill, 3ft. \times 1 1/2in.

New RICHMOND Radial Drill, 4ft. \times 2in.

Selection of Bench and Pillar Drills, 1in. to 1 1/2in.

New MYFORD MG12 Universal Grinder.

New SMART & BROWN Precision Lathe, 14.

New SENIOR Horizontal Millers, M1.

New DENBIGH Horizontal Millers, C4.

New VICTORIA Universal Miller, U2.

C. H. JOYCE LTD

32-40, Monkton St., (Kennington), London, S.E.11.

REliance 1437-9.

Many other machines of various types available also, please ask for Stock list.

Bar or Rod Cleaning Machine.

Motorised on stand. Fitted 6in. dia. Circular Wire Brushes. Material passes between and is quickly brushed. Price £75.—**BOX V289, MACHINERY**, Clifton House, Euston Road, N.W.1.

Acme Gridley Model R, 1in.

cap. 4-spindle Bar Automatic, fitted screwing spindle, recently reconditioned and in exceptional condition, electric 400-440/350, £430.

I.S.A. 4-spindle 4 1/2in. Chucking Automatic motorised 400-440/350, £250.

OUR H.P. CHARGES ARE STILL ONLY

5 PER CENT. PER ANNUM.

G. M. BUCKINGHAM, LTD., 8, Clarendon Avenue, Leamington Spa. Tel: 1215.

Le Blond No. 2 Deep Hole Drilling

and Boring Machine, 400/350 motors. Will drill from solid up to 2 1/2in. dia. and 8ft. long at one setting. Swing over bed 15in.—**HICKS MACHINERY LTD.**, 26, Addison Place, London, W.11. Tel.: PARK 2333.

Southbend Lathe. Series 66140.

4 1/2in. centres. Compound slide. 3 1/2ft. bed length. Motor and countershaft mounted. 8 change wheels, plus 2 doubles. 6 speeds. 400/350 electric fitted with reversing switch. 3-jaw chuck and tailstock.—**BOX V370, MACHINERY**, Clifton House, Euston Road, N.W.1.

Gisholt Lathe. Serial No. 2907-

18. Max. swing over bed 18 1/2in. Max. swing between tools 13in. Swing over cross-slide 9 1/2in. dia. 6 spindle speeds 39 to 500 r.p.m. 8 feeds 0.002in. to 0.006in. 2 1/2in. hole through spindle. Fully motorised 400/350.—**BOX V372, MACHINERY**, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

**ALPHA GLASSCUTTING AND WORKING MACHINES, ETC.**

- New Machines for cutting-out irregular shapes in Sheet and Plate Glass. Motorised, or for Hand Operation only.
 New Machines for cutting-off Glass Rods and Tubes. Motorised 400/3/50.
 New Glassworkers' Lathes with Precision 3-jaw Chucks. Motorised 400/3/50.
 New (Positive Control) Mixture Control Valves for Oxy., Gas and Gas/Air.

PRESSES.

- BLISS** No. 18 Inclined Power Press, 1in.-2in. Adj. Stroke. Motorised 400/3/50.
 No. 2 Fly Presses, by **DENBIGH, NORTON, S. & B.**, etc.
 No. 3 Fly Presses by **DENBIGH, NORTON, S. & B.**, etc.
 No. 4 Fly Presses by **NORTON, S. & B.**, etc.
 No. 5 Fly Presses by **DENBIGH, NORTON, S. & B.**, etc.
 No. 6 Fly Presses by **DENBIGH, NORTON, S. & B.**, etc.
 No. 7 Fly Presses (**NORTON** type).
 No. 6 Tail Fly Presses, 12in. Daylight **NORTON**.
 No. 5 Tail Fly Presses, 12in. Daylight, **EDWARDS**.
FAIRBANK BREARLEY Fly Presses, 10in. Daylight.
 No. 2A **EDWARDS** 10in. Deep Back Fly Press.
 No. 3 **EDWARDS** 10in. Deep Back Fly Press.
 No. 3A **Q. & S.** 10in. Deep Back Fly Press.
 No. 4 **HAZELWOOD & DENT** Bar Fly Press.
SWEENEY & BLOCKSEGE Double Sided Fly Presses on stands.
MOSSBERG & GRANVILLE Foot Lever Press on stand.
EDWARDS Foot Lever Press on stand.

We have now some capacity for Rebuilding Machine Tools to Makers Limits, also for Planing and Grinding Lathe Beds up to 15ft. in length.

THE SURPLUS MACHINERY & STORES CLEARING HOUSE LTD.

Empire Works, 108, East Hill, Wandsworth, London, S.W.18.

*Phone: Vandyke 3266/7/8.
 *Grams: "Wandurk" Put. London "

Smart & Brown Centre Lathe.

Serial No. S.2040, 4in. centre lathe. Swing 8in. max. Between centres 18in. max. 6 speeds. Screwcutting 4 to 60 t.p.i. Surfacing and sliding. Motorised 400/3/50.—**BOX V350, MACHINERY, Clifton House, Euston Road, N.W.1.**

Metal Marking or Name Stamp-

ing Machine. For flat or round articles. Floor pedestal type. Air operated. Originally cost £350, for quick sale price £92.—**BOX V290, MACHINERY, Clifton House, Euston Road, N.W.1.**

Archdale 2-spindle Drill, with

pole change motors, 400-440/3/50. Power feed to quill and electric suds pump.—**BOX T730, MACHINERY, Clifton House, Euston Road, N.W.1.**

Cam Copy Milling Machines.

Greenbat for barrel cams; Legs for plate cams up to 10in. dia. Both 400/3/50.—**HICKS MACHINERY, LTD., 26, Addison Place, London, W.11. Tel.: PARK 2333.**

MIDLAND

B.S.A. 4in. S.S. Screwing Auto, 3rd slide, slotting attachment, bar feed and tooling.
SKODA 20 m.m. S.S. Bar Auto, fully fitted. Large quantity of tooling.
HERBERT Junior Chucking Auto, 6in. swing. Very well equipped.
VOUCHER COBRA 24in. capacity Cabinet Model Cold Saw. Pedal Feed 400/3/50. Electrics. With two blades.
HERBERT No. 4 Capstan A.C.H., 8 speeds, 30-750 r.p.m. Covered bed.
HERBERT Type C, 15in. Pillar Drill, 4in. cap. 15in. by 14in. R. & F. cable.
KITCHEN & WADE 24in. Pillar Drill, 14in. cap. No. 3 M.T. power feeds 18in. by 18in. R.F. swing-aside table.
NEW NORTON 10in., 12in., 14in., 16in. and 20in. Double Ended Grinding Machines.
EDWARDS 3ft. Power Guillotine. Cap. 14's gauge. Open-ended. Auto sheet hold down. Less motor.

Unless otherwise stated all above motorised 400 3 50

THE MIDLAND MACHINE TOOL CO.

BRADLEY, BILSTON, STAFFS.

Bilston 41953.

Tool and Cutter Grinder, Le

Blond No. 2, Serial No. L.L.281, speeds 2,600 to 5,400. Motorised work head swivels 90 deg. Table adjustable to 2in. taper per ft., and whole working apron swivels around the wheel column. This machine has been rebuilt and is in excellent condition. Reasonable offers accepted for quick sale.—**BOX T591, MACHINERY, Clifton House, Euston Road, N.W.1.**

Modern Automatics For Sale,

1in. dia. capacity, 3-operation machine. Fully motorised, 400/3/50. Two machines available, £250 each.—**BOX T595, MACHINERY, Clifton House, Euston Road, N.W.1.**

Wm. Hardill Planer and Thick-

nesser, drive through countershaft. With Brook motor, 20 h.p., 400-440/3/50. Size 8in. by 4in. 4-cutter machine. 4 slides cut simultaneously.—**BOX T622, MACHINERY, Clifton House, Euston Road, N.W.1.**

Overhead Mono-Rail Chain Con-

veyor, complete with 386ft. of chain and runners fitted at 2ft. intervals, with suspension trolley. 386 ft. of 2in. by 1in. rails. 126 ft. of 2in. by 1in. curved rails. Also single and double horizontal turn brackets and sprockets. Miscellaneous channel irons and tie rods, etc. Drive unit 1 h.p., 700 r.p.m., 400 volts. Max. output torque 715ft.-lb. on 72:1 reduction gear. Travel of worm 3/8in. Motor pulley 3in. dia. Worm pulley 12in. dia., with automatic chain tensioner and cut-out switch. This equipment is offered dismantled at about half maker's price.—**BOX T648, MACHINERY, Clifton House, Euston Road, N.W.1.**

Smart & Brown and Boley

Second-operation Lathes for sale. Cheap to clear from £100 each.—**BOX T708, MACHINERY, Clifton House, Euston Road, N.W.1.**

Milwaukee No. 4 Vertical Milling

Machine Model K. High speed series, 27 spindle speeds, 12 to 1,200 r.p.m., 27 feeds, 4in. to 15in. per min. Table 80in. by 16in. Quick traverse all directions. Power feeds to vertical head. In new condition. 400-440/3/50.—**BOX V224, MACHINERY, Clifton House, Euston Road, N.W.1.**

SNOW T.20 Surface Grinder 20in. wheel. Table surface 40in. by 19in.

PILKINGTON 5-cwt. air-operated Power Hammer.

LEBLOND "Regal" 13in. swing S.S. & S.C. Lathe. Speeds 25-500. Taper turning attachment. Well equipped.

HOLBROOK 13in. swing S.S. and S.C. Lathe. Speeds 22-600 r.p.m. Taper turning.

LANG 17in. swing Surfacing and Boring Lathe. Speeds to 900. Less motor.

1952 BIERNATZKI Heavy Duty Horizontal Mill. Table 55in. by 14in. Speeds 29-1,500 r.p.m. Quick power all ways.

Double Ended Punch and Shear. Cap. shearing 4in. by 3in. punch, 14in. through 4in.

JONES 20-ton O/F Power Press, inclinable, 3in. stroke. Fully guarded.

BROOK 24in. Shaper. Swivelling table. Speeds 12-80 strokes per minute.

Taylor Challen B.2 Press. 10

tons. Stroke 2in. Depth of throat 7in. Strokes per min., usual 100. Pressure exerted at bottom of stroke 10 tons. Motorised 3 h.p., 400/3/50. 710 r.p.m.—**BOX V434, MACHINERY, Clifton House, Euston Road, N.W.1.**

Milling Machines. New

VICTORIA Omnimills, Models 01 and 02, both with Hilger & Watts optics. Also all other Victoria Universal and Vertical models.

DENBIGH Model 14.

USED.
CINCINNATI No. 3 Plain, 63in. by 15in., war machine, £675.

VAN NORMAN 21P Plain, 45in. by 10in., rapid and power all ways, speeds 40-1,350, £425.

EDGWICK No. 3 Carbinil, 20in., unused condition, semi-auto cycle with rapid traverse, £675.

CINCINNATI 2M Vertical, 52in. by 10in., power all ways, almost as new.

OUR H.P. CHARGES ARE STILL ONLY 5 PER CENT. PER ANNUM.

G. M. BUCKINGHAM, LTD., 8, Clarendon Avenue, Leamington Spa. Tel.: 1215.

Daniels No. 3 Preforming Ma-

chine. Reconditioned. Output 1,500 pellets per hour. Cap. up to 24in. dia. by 1 1/2 thick pellets. Fully motorised and in very good condition.—**BOX V428, MACHINERY, Clifton House, Euston Road, N.W.1.**

Friction Screw Power Press.

Model No. 2, 22 tons. Table area 194in. by 17 1/2in. Daylight 10in. Motorised 3 h.p., 415/3/50. 950 r.p.m.—**BOX V431, MACHINERY, Clifton House, Euston Road, N.W.1.**

Taylor & Challen 20 tons Press.

Type 370, 1in. fixed stroke. Not inclinable. Throat 10in. Table overall 23in. by 27in. Motorised 400-440/3/50. 3 h.p. Vee rope drive.—**BOX V432, MACHINERY, Clifton House, Euston Road, N.W.1.**

Taylor Challen Single Action

Press. Max. blank 18in. dia. Largest article 12in. Deepest article 7 1/2in.—**BOX V430, MACHINERY, Clifton House, Euston Road, N.W.1.**

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)



KNIGHT No. 40 Vertical Milling Machine in showroom condition.

AS NEW MILNES High-Speed Vertical Milling Machine, with Measuring Equipment.

PALLAS V.1 Vertical Milling Machine. Speeds to 4,185 r.p.m. Working surface 30in. by 8in.

VICTORIA U.2 complete with Vertical and Slotting Attachment.

TRUMILL Horiz. Milling Machine. Power Feeds in all directions. Table 40in. x 10in.

AS NEW WILLSON 74in. Centre Lathe, with Equipment.

HERBERT No. 7 Combination Turret Lathe, complete with equipment, in excellent condition.

NORTON 6 x 18 Hydraulic Surface Grinder with Magnetic Chuck, Reconditioned.

LANDIS 6 x 18 (American built) Hydraulic Plain Cylindrical Grinder, in excellent condition.

Only a small selection of our new, reconditioned and used Machine Tools, at very reasonable prices, which can be inspected under power.

Our new Machines include the **COLCHESTER** range, **WILLSON** Mark V and W. & M. Centre Lathes. Ex Stock.

Write for Stock List.

THE CAUSEWAY, EGHAM, SURREY.

Tel.: Egham 3155/6.

Herbert Bench Drilling Machine.

Cap. 1in., single spindle. Quill movement 5in. Head movement 5 1/2in. Table area 10in. by 10in.—BOX V398, MACHINERY, Clifton House, Euston Road, N.W.1.

Drummond Electraucal Mandrel

Press. Type ABN.12/17. Fitted with interlocking safety guards and control mechanism. Electric motor and pump. Cap. 12 tons. Stroke 17in.—BOX V400, MACHINERY, Clifton House, Euston Road, N.W.1.

PARKSON MODEL 2N UNIVERSAL MILLING MACHINE

Standard voltage, table 51" x 11 1/2", auto feed in all directions, complete with 6" dividing heads, swivelling heavy duty vertical milling attachment, universal milling attachment, slotting attachment, 14" rotary table. In "as new" condition.

J. E. RAISTRICK LIMITED

RELANCE WORKS, POYLE TRADING ESTATE, COLNBROOK, BUCKS.

*Phone: Colnbrook 2421-2
*Grams: "RAISTRICK, COLNBROOK SLOUGH"

Conveyor Approx. 95ft. Long, and 3ft. high with ramp down to floor level. Approx. 24in. wide with rollers spaced at intervals of 18in. with no support in between. Motorised 440/3/50. 1 h.p. 420 r.p.m. Traveling belt suitable for heavy hampers or large parcels.—BOX V408, MACHINERY, Clifton House, Euston Road, N.W.1.

Churchill Redman S.S. & S.C.

Gap Bed Lathe. Series 4000. 12in. by 8ft. between centres. Swing in gap 4ft. 4in. dia. by 20in. gap. 2ft. dia. swing over slide. 20in. dia. swing over saddle. Infinitely variable belt drive to spindle from 3 h.p. motor, 400/3/50. With screwcutting change wheels, 48in. by 27in. dia. Faceplates, 24in. 4-jaw chuck, 3-point and travelling steady.—BOX V254, MACHINERY, Clifton House, Euston Road, N.W.1.

Excell No. 3 Dieffling and Sawing

Machine. Length of stroke 4 1/2in., throat distance 9 1/2in. Max. thickness of work admitted 3 1/2in. Strokes per min. 65, 100, 150, 220. Dia. of table 16in. Angular adjustment of table in 4 directions 15 deg. Length of files 8in. 1 h.p. motor at 900 r.p.m.—BOX V256, MACHINERY, Clifton House, Euston Road, N.W.1.

New Grinders.

MYFORD MG12 Cylindrical Grinder, cap. 5in. by 12in.

EXCEL Model 3/12 Hydraulic Surface Grinder, 24in. by 8in.

USED.

NEWALL 36in. by 10in. Plain Cylindrical Grinder.

SCRIVENER No. 2 Centreless Grinder, 6in. cap.

CHURCHILL Hydraulic 12in. by 36in. Semi-Universal Cylindrical Grinder, £350.

CHURCHILL Hydraulic Spline and Surface Grinder, 48in. by 6in., £325.

REID Surface Grinder, 18in. by 6in., fully motorised, £175.

ORCUTT 20in. Hydraulic Spline Grinder, £150.

JONES & SHIPMAN 1in. cap. motorised Twist Drill Grinder, £55.

OUR H.P. CHARGES ARE STILL ONLY 5 PER CENT. PER ANNUM.

G. M. BUCKINGHAM, LTD., 8, Clarendon Avenue, Leamington Spa. Tel.: 1215.

Conveyor About 48ft. Long, 3ft.

off the ground, with side panels about 9in. high with a belt about 24in. wide. Motorised 440/3/50. 1 h.p. 1,425 r.p.m. In good condition and suitable for light parcels.—BOX V463, MACHINERY, Clifton House, Euston Road, N.W.1.

Manesty No. 2 Pelleting Machine.

Fully motorised with built-in motors, 400-440/3/50. Max. dia. of pellet 1 1/2in. Output 3,300 pellets per hour.—BOX V427, MACHINERY, Clifton House, Euston Road, N.W.1.

Mills 4B 100 tons Oilauke Press.

Series 9720. 15in. stroke. Daylight 30in. max., 16 1/2in. min. Fitted with hydraulic pump with 2,240 lbs. per sq. in. pressure and dial pressure gauge to 125 tons. Motor 25 h.p. 400/3/50. 970 r.p.m.—BOX V419, MACHINERY, Clifton House, Euston Road, N.W.1.

Bradley & Turton Pelleting

Press, type P.4. Max. size of pellet 2 1/2in. by 1in. Strokes per min. 30. Motorised 5 h.p. 400/3/50.—BOX V420, MACHINERY, Clifton House, Euston Road, N.W.1.

Heavy Duty Roller Conveyor

Track by W. Cross. 6—24in. wide in 7ft. lengths. 20 rollers 3 1/2in. dia. Also 14 rollers on lower half at 2 1/2in. dia. Very good condition.—BOX V457, MACHINERY, Clifton House, Euston Road, N.W.1.

Herbert No. 1 Motorised Capstan

late model, collet chuck, barfeed suds, switchgear. Max. speed over 4,000 r.p.m., also No. 2B A.G.H. capstan, Flamard bed, power feeds, excellent condition.—C. L. THOMAS, LTD., 18, Park Avenue, Solihull 1281

1951 Ward 3A. Good Condition,

with equipment.—BOX V275, MACHINERY, Clifton House, Euston Road, N.W.1.

Swift S.S. & S.C. Lathe, 16 1/2in.

centre height by 10ft. 3in. between, 57in. swing in gap, rapid traverse saddle, Modern Machine.—DEREK HARTLE LIMITED, Wellington Road, Ashton-under-Lyne. *Phone: Ashton-under-Lyne 3631/2.

Kendall & Gent Vertical and

Horizontal Plano Milling Machine, capacity 14ft. by 7ft. by 3ft. 9in., complete with 4 milling heads and electric, suitable for 400/3/50.—BOX V279, MACHINERY, Clifton House, Euston Road, N.W.1.

Huller UG.5 Tapping Machine.

Cap. 1 1/2in. steel. Controlled pitch. Spindle speeds 100-560. Motorised.—WILCOX & CO., Barr Street, Birmingham, 19. Northern 1234/5.

Churchill "HBY" Motorised

Internal Grinder, built 1941; 4 spindles and standard equipment.—FROME TOOL & GAUGE, LTD., Market Place, Frome, Tel.: 2226.

Taylor Challen B.2 Press. Series

1290. 2 tons. Variable stroke. Table area 16in. by 10in. Daylight 7in. All guards. Motorised 1 h.p. 400/3/50.—BOX V489, MACHINERY, Clifton House, Euston Road, N.W.1.

Bliss 18 Power Press, Series

54630. Variable stroke 1 to 2. Motorised 400/3/50. Fitted with safety guards.—BOX V492, MACHINERY, Clifton House, Euston Road, N.W.1.

E.N.B. Straightening Press. 30

tons. Series 4180. Flexi-press by Jackson & Hunt. Bed plate 54in. by 13in. Fitted with centres. Motorised 7.5 h.p. 400-440/3/50.—BOX V498, MACHINERY, Clifton House, Euston Road, N.W.1.

Milwaukee Vertical Milling Ma-

chine No. 11B. Table size 11 1/2in. by 45in., moves 31in. Slide moves 10in. Rise and fall of table 12in. Motor 400-440, 4 h.p.—BOX V494, MACHINERY, Clifton House, Euston Road, N.W.1.

Colchester 6in. Master Centre

Lathe. Series 14760. All geared headstock & 8 spindle speeds 20-550 r.p.m. Full screwcutting range. Power surfacing and sliding 4-way toolpost. Prismatic bed. Motorised 2 h.p., 400-440/3/50.—BOX V499, MACHINERY, Clifton House, Euston Road, N.W.1.

Thread Grinding Machine.

Wickman Horstman No. 2, with form relieving attachment and overhead mounted wheel crusher. Very good condition.—Apply BOX V90, MACHINERY, Clifton House, Euston Road, N.W.1.

Churchill Surface Grinding Ma-

chine, model O.S.V. Capacity 30in. by 10in. Heavy duty machine with vertical-wheel spindle. Magnetic chuck. Fully motorised. Rebuilt as new.—Apply BOX V113, MACHINERY, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (PLANT FOR SALE, contd.)

Alcohol Slotting Machine. Rotary
type for screw heads and similar components. Work plates 9in. dia. on adjustable slide. The cutter spindle is horizontal, also the workhead. Cutter spindle driven by 1 h.p. motor 400/440/3/50. Vee rope drive. With coolant tank and pump. Starter.—BOX V477, MACHINERY, Clifton House, Euston Road, N.W.1.

Fraser Mono-Radial Hydraulic
Pump. Type D.5. Motorised 4 h.p. 400/3/50. 1,000 r.p.m.—BOX V452, MACHINERY, Clifton House, Euston Road, N.W.2.

Russell Saw Sharpener. Series
S.3070. With spindle of 1,880. Cap. approx. 1in. bore by 15in. to 40in. dia. Motorised 1 h.p. 400/3/50.—BOX V455, MACHINERY, Clifton House, Euston Road, N.W.1.

3 Lorenz Gear Shapers, Model
800. Automatic high speed gear shapers. Max. dia. for spur gears 180 mm. Max. dia. for spiral gears 165 mm. Width up to 50 mm. Index module up to 4. Driving pulleys 200-600 r.p.m. Max. length of stroke 2 1/2 in. Automatic cycle. Coolant pump. Motorised 400-440/3/50. All rebuilt.—BOX V469, MACHINERY, Clifton House, Euston Road, N.W.1.

Silvercrown Dryer. Model 2.
90 lbs. safe load. 17 1/2 in. dia. by 23in. deep. Fitted with heating elements and in good condition.—BOX V440, MACHINERY, Clifton House, Euston Road, N.W.1.

Brockhouse Gas-fired Vertical
Multi-tube Boiler. Type V8.987. Max. working pressure 110 lbs. per sq. in. Evaporation 144 lbs. per hour. Fitted with electrically driven feed pump and controlled by Drayton 1992 Float Switch, with pilot valve and mains alarm.—BOX V447, MACHINERY, Clifton House, Euston Road, N.W.1.



GOOD CLASS COLD SAWING MACHINES IN STOCK.

CLIFTON & BAIRD Model CSO.0, motor drive, dia. of saw blade 18in., capacity rounds 5 1/2 in., capacity squares 5in., 3 blade speeds 30-66 ft./min., h.p. 5.

RUSSELL 20/24 HYDROFEED, motor drive, dia. of saw blade 20in., capacity rounds 6 1/2 in., capacity squares 6 1/2 in., H-sections 12in. by 4 1/2 in., 4 blade speeds 35-90 ft./min., h.p. 7 1/2.

WAGNER DFA Fully automatic, motor drive, dia. saw blade 22in., capacity: rounds 7 1/2 in., squares 6 1/2 in., rectangulars 15 1/2 in. by 4 1/2 in., four cutting speeds from 38 ft./min. to 29 ft./min., h.p. motor 7 1/2.

WAGNER Model EF, motor drive, dia. of saw blade 27in., capacity rounds 9in., capacity squares 8 1/2 in., stepless feeds 0-12 in./min., h.p. 10.

NOBLE & LUND No. 1 B.S. Band Saw, motor drive, dia. of saw pulleys 4ft., depth of work admitted 2ft. 6in., overall table size 6ft. by 5ft., three cutting speeds, 75/168 ft./min., h.p. 3.

Full details on any of the above from:

SOAG MACHINE TOOLS LTD.,

JUXON STREET, LAMBETH, LONDON, S.E.11.

Phone: RELiance 7201.
Grams: Sotoolsag, London, S.E.11.

Rhodes Power Press. Eccentric
action. Stroke 1 1/2 in. Table area 16in. by 12in. Square hole in table 4 1/2 in. by 6 1/2 in. Throat 6in. to ram centre. Hole in ram 2in. dia. Rise and fall table. Motorised 400/3/50.—BOX V412, MACHINERY, Clifton House, Euston Road, N.W.1.

Besco Rotary Shearing Machine.
Capacity 14G by 42in. throat. 400/3/50.—BOX V299, MACHINERY, Clifton House, Euston Road, N.W.1.

Press Brakes—"Bronx" 40, 60
and 90 ton capacity for early delivery. From sole South of England agents, NEW. At maker's list prices. Write for detailed quotations and particulars of free tooling service.—W. E. NORTON (MACHINE TOOLS), Ltd., Grosvenor Gardens House, Grosvenor Gardens, London, S.W.1. Phone: Tate Gallery 0639/4. Cables: Norbros, London.

Two No. 6SP Potter & Johnston
Chucking Automatics, with self-contained motor drive, 15 h.p. 400/3/50, 30in. dia. air-operated chuck, 14in. dia. hole and single cross slide.—LEE & HUNT, LTD., Crocus Street, Nottingham.

Werner Pfleiderer Presses. 160
tons pressing power. 31 tons pull back power. Ejection power 42 tons. Working pressure 200 lbs. per sq. in. Max. stroke 21.840in. Stroke ejection 13.65in. Distance between columns 26in. by 37 1/2 in. Self contained with a 3-throw reciprocating pump. With pressure control valves, 8 gals. per min. Working pressure 2,940 lbs. per sq. in. 200 r.p.m. Rams 33 mm. by 69 mm. stroke. 400/3/50 motor, 29 amps. 14.5 kW. 1,440 r.p.m. Four available.—BOX V405, MACHINERY, Clifton House, Euston Road, N.W.1.

Wiengarten 70 tons High Speed
Lamination Press. Drive direct from motor through gears. Motor mounted integral with machine. Variable strip feed mechanism to take 7 1/2 in. wide strip. 3 1/2 in. feed. 8 1/2 in. throat. 20in. between push and pull feed units. 1 1/2 in. dia. ram hole. Pinion 7 1/2 in. o.d. 26 teeth. Approx. 8in. adjustment on conn. rod. Distance between table and ram 14in. Space on table 14in. by 20in. Two positions in fly-wheel giving 8 speeds. Variable stroke up to 80 mm. or 3 1/2 in. Motorised.—BOX V466, MACHINERY, Clifton House, Euston Road, N.W.1.

8ft. by 3/4 in. Guillotine. 400/3/50.
—BOX V297, MACHINERY, Clifton House, Euston Road, N.W.1.

FOR HIRE

One Horizontal Milling Machine
for hire. Hexagon motorised 42in. by 10in. 6/12 months' contract. 400/3/50 supply. London area.—BOX V299, MACHINERY, Clifton House, Euston Road, N.W.1.

RECEIVED TOO LATE FOR CLASSIFICATION

The Director-General, India
Store Department, Government Building, Bromyard Avenue, Acton, London, W.3, invites tenders for the supply of:—

1 NO. HYDRAULIC STRETCHING AND DETWISTING MACHINE FOR SEMI-HARD RODS AND PROFILES OF HEAVY AND LIGHT METAL AND OF SOFT IRON.

STRETCHING CAPACITY ABOUT 120 TONS.

Tender schedules and specifications may be obtained from the above address at a fee of ten shillings which is not refundable. Cheques should be made payable to High Commission of India. The applications for tender forms should state reference 2077/57/88B/ENG.3.

Tenders complete with specifications are to be submitted by MONDAY, the 3rd MARCH, 1958.

Wanted, Berninghaus Coil
Automatic of approximately 8-10 mm. capacity. Condition immaterial.—BOX V270, MACHINERY, Clifton House, Euston Road, N.W.1.

Wanted. Worm Cutting Machine
for worms up to 1 1/2 in. dia. similar to Waltham.—BOX V277, MACHINERY, Clifton House, Euston Road, N.W.1.

Urgently Required—Brown & Sharpe
Automatic Magazine bar feed attachments, suitable for No. OOG, B. & S. Autos.—Full details to BOX V278, MACHINERY, Clifton House, Euston Road, N.W.1.

Pantograph 3D Wanted, George
Alexander No. 2 or 3 or Taylor Hobson.—SWIFT COMPONENTS (LONDON), LTD., 434, Essex N.1. CANonbury 6727.

When answering advertisements kindly mention MACHINERY.

SITUATIONS VACANT

If you do not wish your reply to any Box No. advertisement in this section to be forwarded to certain firms, please advise us. Your reply will then be destroyed, but you will not be notified as this would disclose the identity of the advertiser.

Capstan Setter-Operator Required. Small machine shop S.W. London. —Write giving full particulars of age, experience and wages required in confidence, to BOX V154, MACHINERY, Clifton House, Euston Road, N.W.1.

Highly Paid Secure and Interesting posts are always available for technically trained men. Find out how you can put some letters after your name by preparing at home in "No Pass—No Fee" terms for A.M.I.Mech.E., A.M.I.Prod.E., A.M.S.E., City and Guilds, etc., etc. Full details of exams and hundreds of courses in all branches of Engineering, Draughtsmanship and Management, the Benefits of our Employment Dept., and unique record of 95 per cent. successes, are given in "Engineering Opportunities"—valuable 144-page Guide which will reveal many chances you are now missing. Write for your copy today (stating subject of interest). —FREE and without obligation—B.I.E.T., Dept. 34s, Wright's Lane, London, W.8.

Senior Jig and Tool Draughts-men required by Company situated near Bournemouth manufacturing specialised components for the motor industry. Experience of machine tool design and knowledge of hydraulics an advantage. —Write stating age, details of experience, technical training and salary required to BOX V152, MACHINERY, Clifton House, Euston Road, N.W.1.

Chief Inspector Required by expanding Company. A man with a good precision engineering background who has drive and initiative, able to organise the department, institute and maintain quality control of a product which is produced on a batch production basis. This is a tough job with a lot of hard work attached to it, particularly at the start. The company is situated in the Southampton area. —Reply BOX V110, MACHINERY, Clifton House, Euston Road, N.W.1.

Workshop Foreman/Manager for small sub-contract workshop with Autos, Capstans, Mills, etc. Keen active man with good organising ability and thorough knowledge of the trade required. This is a tough commitment and presents a good opportunity for the right man to exploit his abilities. —Write stating full details and your own salary figure to H. FRAZER, 70, St. Albans Road, Cheam, Surrey.

Draughtsmen, Junior and Senior required for work on advanced types of capstan lathes and automatics. Please give full details of training, experience and salary required. —MURAD DEVELOPMENTS LTD., Aylesbury, Bucks.

Metallurgist Required for Re-search and development on cutting tool materials, by leading manufacturers of Hard Metal. The work will include development of new cutting materials and investigation of the application of existing materials. University degree or equivalent qualifications required and preference will be given to applicants with some industrial experience. —Write, giving age, qualifications, experience and salary, to BOX V262, MACHINERY, Clifton House, Euston Road, N.W.1.

Capstan or Turret Setter Oper-ators required for Ward 7 or Ward 3A. Only highly skilled men accustomed to turning out absolutely first-class quality work need apply. The wages are top-grade. Plenty of overtime plus bonus, sick pay, etc., and pension scheme after establishment. Housing provided after 3 months trial period. Also vacancy for one good young centre lathe turner. —Applications in full stating past experience, to BALDING ENGINEERING, LTD., Bessemer Road, Norwich.

Production Superintendent for small works in West of England, engaged in close limit aircraft component production. State age, experience and salary required. —BOX V262, MACHINERY, Clifton House, Euston Road, N.W.1.

Capstans—Working Foreman. Must have extensive experience as first-class setter on close limit aircraft components. Ten Capstans, for West of England. State age, experience, salary required. —BOX V263, MACHINERY, Clifton House, Euston Road, N.W.1.

ASSISTANT PLANNING ENGINEER

Required with Machine Tool or similar manufacturing experience, for operation layouts on batch and prototype work. Some knowledge of tooling and mathematics would be useful. Excellent prospects for a young man (up to 35 years) seeking a permanent career. Send full details of age, education, experience and present salary to Personnel Manager,

W. E. SYKES LTD.
Manor Works, Staines, Middx.

Setter Mechanic, Experienced packaging machinery required for North London factory. Excellent conditions, non-contributory pension scheme. —Apply PERSONNEL OFFICER, INTERNATIONAL CHEMICAL CO., LTD., Braydon Road, N.16.

Hardinge Machine Tools Ltd., require a highly qualified designer, particularly experienced in design development of light machine tools of at least Swiss precision. Applicants must be capable of ideas which will keep Hardinge machines in the forefront of their field. This is a Senior appointment carrying high salary. —Apply MANAGING DIRECTOR, Hampton Road West, Hanworth, Middlesex.

Sales Engineer Required by City firm (E.C.3) for London and the South East with experience in machine tools and industrial plant. Only men of initiative, good presence and sound technical background need apply. Staff notified. Applications treated strict confidence. —Fullest details a/c experience, salary, BOX V240, MACHINERY, Clifton House, Euston Road, N.W.1.

Chief Estimator Required for engineering firm in Coventry, to take charge of Estimating Department. Experience in estimating for Jigs, Fixtures, Press Tools, etc., essential. This is a responsible position, with a commensurate salary. Every amenity, pension scheme, and excellent prospects of advancement. Also Works Manager to take full control of Works, Works Personnel, Production control, etc. Experience in such work essential. Good salary, pension scheme, together with excellent prospects in an expanding organisation. —Please apply with full particulars to BOX V260, MACHINERY, Clifton House, Euston Road, N.W.1.

Ratefixer (Assistant), Age 25-30, with similar previous experience in general machine shop and/or light electro-mechanical assemblies required. Applicants who have served an engineering apprenticeship preferred. Five-day week. Contributory Pension Scheme. —Apply with full details of career and salaries earned to PERSONNEL MANAGER, THE PHOENIX TELEPHONE AND ELECTRIC WORKS, LTD., The Hyde, N.W.9.

Designer-Draughtsman, 25-30 years, required in London by rapidly expanding company for examining customers' enquiries on mechanical applications of the company's products. Design experience in machine-tool and motor industry an advantage. This appointment offers a wide insight into nearly every type of engineering process in this country and personal contact with customers. —Apply to BOX V272, MACHINERY, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Classified Advertisements (SITUATIONS VACANT, contd.)

Machine Tool Merchants Re-
quite young person with drive and
enthusiasm to be Assistant to Sales Director
Prospects and income only limited by personal
effort.—Reply with full particulars to BOX V182,
MACHINERY, Clifton House, Euston Road,
N.W.1.

Capstans. Working Foreman.

Must have had extensive experience as
first-class setter on close limit Aircraft com-
ponents. New Ward machines, mixed labour,
Croydon area. Applicant must have held
similar position.—Write, giving particulars,
experience, age and salary required, to BOX
V174, MACHINERY, Clifton House, Euston
Road, N.W.1.

Planning and Estimating

Engineer required. A good practical
machine shop background is required, together
with previous experience as Planning Engineer.
Position suitable for younger man with energy
and desire to improve financial position. Small
factory Croydon area, mixed labour.—Write,
giving full particulars, experience, age, etc., to
BOX V176, MACHINERY, Clifton House, Euston
Road, N.W.1.

Capstan Setter Required for

light engineering works in Sussex. Must
be fully experienced and reliable. State age,
experience, wage.—BOX V226, MACHINERY,
Clifton House, Euston Road, N.W.1.

Production Manager. Applica-

tions are invited for the position of Produc-
tion Manager in established medium-size
electronic and light electro-mechanical company,
West Middlesex area. This appointment pro-
vides excellent opportunity of permanent post
for the right man with initiative and a good
educational standard. Essential requirements
are age 35-50 sound workshop training, preferably
with H.N.C. in Production Engineering, and
experience including light precision work,
application of small press tools, fabrication work
of type used for electronic equipment units, also
batch production wiring and assembly methods.
Post involves responsibility for all production
engineering and manufacturing operations.
Life Assurance and Pension Scheme.—Write
fully in confidence, stating age, qualifications,
experience, salary required, to BOX V228,
MACHINERY, Clifton House, Euston Road,
N.W.1.

A Production Engineer is Re-

quired to supervise the complete manu-
facture, construction and erection of special-
purpose machines. These machines are designed
by ourselves to our customers' particular
requirements, and will generally be built using
standard units and standard unit heads, which
are also designed and manufactured by ourselves.
Academic and practical training must be of a
very high order, as the successful applicant will
be required to work very closely with the
Technical Sales Engineer and Chief Designer
to make a team capable of controlling all design
and manufacture. This is a new job in a com-
paratively new field and to a suitably trained
engineer could lead to the position of Works
Manager.—Apply, writing, giving full details
of age and experience, to GENERAL MANA-
GER, BROOKE TOOL MANUFACTURING
CO., LTD., Aldridge Road, Perry Barr, Birming-
ham, 22b.

Draughtsman Required, Experi-
enced in plastic mould design. Good
opportunities for advancement.—Write SEA-
FORTH, Watchett Works, Oakhurst Road,
Southend-on-Sea, Essex.

THE DE HAVILLAND ENGINE COMPANY LIMITED

(ROCKET DIVISION)

PRODUCTION CONTROL

Applications are invited from suitably qualified engineers in the age
group 30 to 45 for the position of Production Controller.

Essential qualifications include a sound practical training in
engineering, and applicants must possess H.N.C. or equivalent.

Proved experience in the control of production, stock control,
material and shop ordering, progressing, machine loading and
programming is required, together with a knowledge of modern
control systems.

Experience of M.O.S. Stores procedure is desirable, but not
essential.

Assistance towards housing accommodation could be arranged.

Applications (quoting Ref. SC.750) should be sent to:—

**The Personnel Officer,
The de Havilland Engine Company Limited,
Stag Lane, EDGWARE, Middx.**

SENIOR DEVELOPMENT ENGINEER

An exceptional opportunity for a
Mechanical Engineer, in the 30-40 age
group, wishing to broaden his responsi-
bilities, occurs in our organisation.
The successful candidate would, after
experience of our products, take charge
of our Design Office and Development
Dept., comprising a staff of about 45 in
all.

An Honours Degree in Mechanical
Engineering followed by responsible
development or design experience in
light to medium engineering are the
minimum technical qualifications. Ex-
perience of research, especially in
machine dynamics, strength of materials
or elasticity would be considered
valuable.

Staff conditions, salary, pension scheme,
etc., are up to the standard expected
by those genuinely qualified for this
post.

Candidates should write initially to the
Secretary, The British Northrop Loom
Company Ltd., Blackburn, Lancashire.

DRAUGHTSMEN

required for old-established and expand-
ing die-casting company in North London.
Some experience of die-casting or plastic
moulds essential. Salary up to £1,000
per annum. Permanent monthly staff
appointment with comprehensive pension
and dependants' insurance scheme.

Assistance with removal expenses in
approved cases. Five-day week in pleas-
ant modern office; canteen facilities.

Apply with details of experience to

**Personnel Manager Box UK. 7982
A.K. Advg., 212a Shaftesbury Ave.,
London, W.C.2.**

OFFICE POSITION

for man aged 25-35

With some technical knowledge or
Machine Tools to deal with correspon-
dence and quotations, required by well-
established Machine Tool Importers.

**Good prospects. Apply Box V231
MACHINERY, Clifton House, Euston
Road, N.W.1**

WORKS SUPERINTENDENT REQUIRED

Immediately by expanding firm of
precision engineers in the West Midlands
area, employing over 3,000 people.

An experienced practical engineer of
first-class standing is required, and
applicants must be conversant with
modern production methods and must
be able to handle labour and be a good
disciplinarian.

The situation offers excellent prospects
for the right type of man, it is permanent
and progressive and a good superannua-
tion scheme is available.

Write, giving full details of past ex-
perience, positions held, salary, etc., in
chronological order, to Box V.232,
MACHINERY, Clifton House, Euston
Road, N.W.1.

JIG & TOOL DRAUGHTSMEN

Required by the Hoffmann Manufacturing
Company, Limited, Ball & Roller Bearing
Manufacturers. We have openings for
men with particular experience of
PRESS TOOL WORK. Conditions of
employment are good and posts are
pensionable. Please apply, giving full
details of age, training and experience to
Personnel Manager, The Hoffmann
Manufacturing Company, Limited,
Chelmsford, Essex.

When answering advertisements kindly mention MACHINERY.

TWO DESIGNERS OF SECTION LEADER STATUS

are required for Mechanical Engineering ranging from Precision Gauge and Machine Tool Work to Fabrication and Mechanical Handling. Knowledge of Instrumentation advantageous. Also a PLANNING ENGINEER with a good knowledge of Spherical Trigonometry to Plan, Supervise Manufacture and Inspection of High Precision Mechanical Engineering Projects mostly on a one off basis.

The work in both cases is largely for the Atomic Energy Authority and applicants are requested to write full details of previous experience and technical qualifications, in confidence to:—

B.O. MORRIS, LTD.,
Albion Works,
465, Commercial Road,
Portsmouth.

JIG & TOOL DRAUGHTSMEN

Required by The Hoffmann Manufacturing Company, Limited, Ball and Roller Bearing Manufacturers. We have openings for men with particular experience of tooling MULTI-SPINDLE AUTOS. Conditions of employment are good and posts are pensionable. Please apply, giving full details of age, training and experience to Personnel Manager, The Hoffmann Manufacturing Company, Limited, Chelmsford, Essex.

REPRESENTATIVES

Representative Required on Commission Basis only, to obtain Turning, Milling, Drilling, etc., and Assembly work from Trade or Ministries. Both precision jobbing and production runs. Should also be able to find contracts for manufacture of complete products, development of prototypes and design and manufacture of jigs and fixtures for Light Engineering. Small expanding company situated in Kent.—Reply in confidence to BOX V283, MACHINERY, Clifton House, Euston Road, N.W.1.

AMBITIOUS MECHANICAL ENGINEER

Required by Machine Tool Company as Representative in Yorkshire and surrounding area. The successful applicant will be required to have a sound practical knowledge of Machine Tools, Power Presses, etc., and to be authoritative and persevering. A high remuneration can be earned by salary and commission. Applications for interviews stating previous experience, should be addressed to

Box L 396, Willing's, 342 Gray's Inn Road, London, W.C.1.

TECHNICAL REPRESENTATIVES

required for East Midlands and West Midlands, for the sale of specialised production engineering equipment and special purpose machine tools.

Applicants must be workshop trained and able to demonstrate to production engineers.

Remuneration by fixed salary plus expenses. Car will be provided.

London interviews arranged with expenses paid—Write in strictest confidence.

Box V276, MACHINERY, Clifton House, Euston Road, N.W.1

Engineering Company on the

South Coast require additional representation throughout the Aircraft and General Engineering Industry and invites application from an experienced Engineer, who has sound connection with all the major Aircraft and Engineering Firms. The position calls for a man with enthusiasm and drive, and able to negotiate at top executive level, with a view to obtaining substantial contracts. References required.—Please write in first instance, stating age, experience and salary required, to BOX V213, MACHINERY, Clifton House, Euston Road, N.W.1.

Representative Required by Firm

of Gear Cutters to take over the East Coast area in which they are already well established. Commission basis only. The remuneration would not justify full time employment but could be worked in with an existing agency in some other line. Resident near Middlesbrough. Specialised knowledge of gearing is not essential, but should have a good general engineering experience.—BOX V294, MACHINERY, Clifton House, Euston Road, N.W.1.

Senior Technical Representative

required by leading Manufacturers of Machine Tools for London and Home Counties. This is a fine opportunity for man with experience and drive. Car provided.—Write, giving full details of experience, etc., to Managing Director, BOX V235, MACHINERY, Clifton House, Euston Road, N.W.1.

Sales Representative Required

for press work (Light Medium/Deep Drawn) by company in West Middlesex area. This is a sound progressive position.—Apply, giving full details of age and experience, to BOX V265, MACHINERY, Clifton House, Euston Road, N.W.1.

Representative Required by

small Midland Precision Engineering Company to introduce work on commission basis.—Write BOX V273, MACHINERY, Clifton House, Euston Road, N.W.1.

SITUATIONS WANTED

Works Manager, 20 Years as Top

executive, seeks change in Crawley or South Coast area, used to controlling 500 mixed employees, Buying, D.O. Methods, T. & M. study, tool room, machine shops, Assembly sheet metal, welding, plating, etc.—BOX V188, MACHINERY, Clifton House, Euston Road, N.W.1.

Practical Engineer, 30 Years'

experience in the Work Shops. Machining and fitting on prototypes, general and development. Present position engineers manager. Seeks similar position, or anything practical. Salary £18 0s. 0d. per week.—BOX V163, MACHINERY, Clifton House, Euston Road, N.W.1.

Buyer, Experienced in Light

engineering, seeks situation in London.—BOX V220, MACHINERY, Clifton House, Euston Road, N.W.1.

Universal Miller. Wide Experi-

ence production and toolroom. 30 years in trade. Seeks post where loyalty, skill, initiative and exceptional tool kit would be appreciated. Minimum starting rate 7s. 6d. per hour.—BOX V236, MACHINERY, Clifton House, Euston Road, N.W.1.

Toolmaker, 33. 17 Years' Experi-

ence on diecast moulds, plastic moulds glued to bench, desires change. Anything considered. London area.—BOX V241, MACHINERY, Clifton House, Euston Road, N.W.1.

Design/Development Engineer,

toolmaker, apprenticed, conscientious, hardworking. Sound background, bench, D.O., technical office, aircraft industry, labour control, general administration, technical or commercial. London/South.—BOX V292, MACHINERY, Clifton House, Euston Road, N.W.1.

Design Engineer. M.J. Inst.E.,

M.Inst.Pk., Grad.I.E.D., A.M.I.E.T., Grad.Inst. Mat. Hdq. (34). British, seeks any permanent progressive post of responsibility where devotion to duty, loyalty and hard work are appreciated. Experience: Workshop D.O., design office and negotiations at any level. Spec. purpose, lamp, line, packaging machines, machine tools, chemical engineering, factory maintenance. Immediate accommodation for family required. Please reply BOX V296, MACHINERY, Clifton House, Euston Road, N.W.1.

REPRESENTATIVES


Machine Tool Representative,

aged 40, 12 years experience in the London and Home Counties area, seeks similar position. Previous posts held, Jig and Tool Draughtsman and Planning Engineer. Good organiser, who wishes eventually to accept responsibility as Sales Manager.—BOX V293, MACHINERY, Clifton House, Euston Road, N.W.1.

When answering advertisements kindly mention MACHINERY.

Diprofil

POWER OPERATED

MULTI-PURPOSE
MACHINEfeaturing
**Diamond and
Tungsten-Carbide
Cutting Tools**

FILING...
LAPPING...
SCRAPING...
GRINDING...
HONING...
ENGRAVING...
MILLING... SAWING.



TAYLOR

**Screw and Plain
PLUG and RING GAUGES**



Highest standard of
workmanship ensures
consistent accuracy
and maximum
working life


BROOKS & WALKER LTD.,

47 Great Eastern St., London, E.C.2.

BIS 7633

Telex No. 23674



Midlands Office: Swan Lane, Coventry. Tel 64246

Branches throughout the Country

INDEX TO ADVERTISERS

PAGE		PAGE		PAGE	
Abbey Heat Treatments Ltd.	145	Blaker Motor & Welding Co. Ltd., The	142	Coventry Grinders Ltd.	149
Abbey Tool Co. Ltd., The	140	Bowes Road Eng'g. Co. Ltd.	144	Craven Bros. (Manchester) Ltd.	50
A.B.M.T.M. Ltd.	14, 17 & 18	Brasshouse, Peter Ltd.	182	Creed, A. R. Ltd.	128
Abrams, Syd. Ltd.	137	Brauer, F. Ltd.	132	Crosland, William Ltd.	135
Abwood Machine Tools Ltd.	85	Brilhart Ltd.	150	Cross Manufacturing Co. (1938) Ltd.	102
Acbars Ltd.	76 & 172	British Aero Components Ltd.	Back Cover	Crowthorn Engineering Co. Ltd.	99
Acrow (Engineers) Ltd.	126	British Die Casting & Engineering Co. Ltd.	97	Croydon Tool & Case Hardening Specialists	143
Adams, L. Ltd.	143	British Thomson-Houston Co. Ltd., The	69		
Adcock & Shipley Ltd.	79	Broadbent, Henry Ltd.	101	Davall Gear Co. Ltd., The	141
Aero Research Ltd.	30	Brockhouse, J. & Co. Ltd.	98	Dean & Mulhall Ltd.	134
Aircraft Unit Engineering Co.	144	Brookhirst Switchgear Ltd.	22	Dean, Smith & Grace Ltd.	9
Air Control Installations Ltd.	100	Brooks & Walker Ltd.	181	Delapena & Son Ltd.	16
Alexander, Geo. H. Machinery Ltd.	149, 150 & 151	Brown, David Corporation (Sales) Ltd., The	60	Denford's Engineering Co. Ltd.	7
Alka Co., The	144	Brown, F.	140	Designex (Coventry) Ltd.	139
Allspeeds Ltd.	115	B.S.A. Tools Ltd.	Front Cover, Back Cover	Desoutter Bros. Ltd.	62
Amblesey Engineering Co. Ltd.	145	Buck & Hickman Ltd.	2	Diamond H Switches Ltd.	39
A.M.D. Engineering Co. Ltd.	141	Burnand, W. E. & Son Ltd.	92	Dimeo (St. Britain) Ltd.	156, 160 & 165
Armstrong Springs Ltd.	128	Burton Griffiths & Co. Ltd.	Front Cover, Back Cover	Dinsdale Engineering Co. Ltd.	138
Armstrongs Sideley (Brockworth) Ltd.	26	Butcher, Henry & Co.	154	Doncaster, Daniel & Sons Ltd.	123
Armytage Bros. (Knottingley) Ltd.	26			Donovan Electrical Co. Ltd., The	112 & 150
Asquith, Wm. Ltd.	Inside Front Cover			Dorner & Wadsworth Ltd.	148
Atkins, Wm. (Coventry) Ltd.	140	Camdentools	138	Dowling & Doll Ltd.	40, 41 & 118
Austin, E. & Sons (London) Ltd.	128	Carder, R. E. Ltd.	139	Dowling, David Ltd.	137
Aylesbury Turned Parts (True Screws) Ltd.	144	Carter, B. & F. & Co. Ltd.	151	Drummond-Asquith (Sales) Ltd.	Inside Front Cover
		Cashmore, John Ltd.	155	Dumb & Cook Ltd.	112
		Centaur Tool Works Ltd.	130 & 156	Duplex Electric Tools Ltd.	114
		Challis, Henry Ltd.	114		
		Churchill, Chas. & Co. Ltd.	14	Elcipse Metal Industries Ltd.	145
		Churchill Machine Tool Co. Ltd., The	1	Edmonton Tool & Eng'g. Co. Ltd.	148
		Cincinnati Milling Machines Ltd.	1	E.D.S. Co. Ltd.	148
		Cohen, Geo. Sons & Co. Ltd.	21, 135, 158, 159, 160 & 161	Edwards Bros.	146
		Consolidated Pneumatic Tool Co. Ltd.	44	Edwards, F. J. Ltd.	154, 158, 159, 164 & 174
		Cooke, Troughton & Simms Ltd.	96	Elcar Machine Tool Co. Ltd.	45 & 168
		Corfield & Buckle Ltd.	92	Ellay Tubes Ltd.	110
		Cornercroft Ltd.	122	Elliott, B. & Co. Ltd.	31 & 49
		Cort, Robert & Son Ltd.	142 & 156		(continued on page 182)
Baker, W. A. & Co. Ltd.	54				
Baldwin Instrument Co. Ltd.	24				
Bedford, James & Co. (Halifax) Ltd.	104				
Bell, H. (Machine Tools) Ltd.	168				
Bell Precision Engineering Co. Ltd.	143				
Benton Engineering Co. Ltd.	149				
B.G. Machinery Ltd.	116				
B.H.P. Machine Tool Co.	56				
Birfield Industries Ltd.	104				
Birmingham Tool & Gauge Co. Ltd.	77				

When answering advertisements kindly mention MACHINERY.



PRODUCTION

the best
bushes —
and the set-up
that gives the
best service



ORDERING



PROGRESSING



DESPATCH




Over 23,000 sizes available—and this figure does not include all the Continental and American standards in regular production. The B.A.C. range is unmatched for scope or availability, pointing to one clear conclusion—*the best bush maker gives the best bush service.*

BRITISH AERO COMPONENTS LTD.
MONTAGUE ROAD, WARWICK TELEPHONE WARWICK 320.


Cogent

The **B.S.A.** range


of high-production
machine tools




1




4




2



5



3



6



7

B.S.A. TOOLS LTD • BIRMINGHAM 33 • ENGLAND

1. **SINGLE - SPINDLE AUTOMATIC SCREW MACHINES** in a range of sizes from $\frac{1}{4}$ " to 2" diameter capacity, including **SIMPLIFIED** and **TURRET THREADING** versions.
2. **B.S.A. ACME-GRIDLEY BAR AUTOMATICS**, 4, 6 and 8 spindle machines in various sizes up to 3 $\frac{1}{2}$ " diameter capacity, and **CHUCKING MACHINE**, Six-spindle, 6" diameter capacity.
3. **SINGLE - SPINDLE CHUCKING AUTOMATICS**, 7 $\frac{1}{2}$ " and 12 $\frac{1}{2}$ " swing.
4. **MULTI-TOOL PRODUCTION LATHES**, 6" x 20" and 28", and 6" **HYDRAULIC COPY TURNING LATHE**.
5. **CENTRELESS GRINDING MACHINES**, No. 4, $\frac{1}{16}$ " to 3" diameter, and No. 8, $\frac{1}{8}$ " to 6 $\frac{1}{2}$ " diameter capacity.
6. **FORM GENERATOR**, $\frac{1}{4}$ " to 3" diameter capacity, and **THREAD GENERATING MACHINE**, 2 B.A. to $\frac{1}{2}$ " B.S.F.
7. **AUTOMATIC TAPPING MACHINES**, $\frac{1}{16}$ " to 1 $\frac{1}{2}$ " diameter capacity (in steel).
Tool Holders, Tools, Attachments and Special Equipment

Sole Agents Gt. Britain: BURTON GRIFFITHS & CO. LTD.
KITTS GREEN • BIRMINGHAM 33

Telephone: STECHFORD 3071



AD. No. 423